This is a digital copy of a book that was preserved for generations on library shelves before it was carefully scanned by Google as part of a project to make the world's books discoverable online.

It has survived long enough for the copyright to expire and the book to enter the public domain. A public domain book is one that was never subject to copyright or whose legal copyright term has expired. Whether a book is in the public domain may vary country to country. Public domain books are our gateways to the past, representing a wealth of history, culture and knowledge that's often difficult to discover.

Marks, notations and other marginalia present in the original volume will appear in this file - a reminder of this book's long journey from the publisher to a library and finally to you.

Usage guidelines

Google is proud to partner with libraries to digitize public domain materials and make them widely accessible. Public domain books belong to the public and we are merely their custodians. Nevertheless, this work is expensive, so in order to keep providing this resource, we have taken steps to prevent abuse by commercial parties, including placing technical restrictions on automated querying.

We also ask that you:

+ *Make non-commercial use of the files* We designed Google Book Search for use by individuals, and we request that you use these files for personal, non-commercial purposes.

+ *Refrain from automated querying* Do not send automated queries of any sort to Google's system: If you are conducting research on machine translation, optical character recognition or other areas where access to a large amount of text is helpful, please contact us. We encourage the use of public domain materials for these purposes and may be able to help.

+ *Maintain attribution* The Google "watermark" you see on each file is essential for informing people about this project and helping them find additional materials through Google Book Search. Please do not remove it.

+ *Keep it legal* Whatever your use, remember that you are responsible for ensuring that what you are doing is legal. Do not assume that just because we believe a book is in the public domain for users in the United States, that the work is also in the public domain for users in other countries. Whether a book is still in copyright varies from country to country, and we can't offer guidance on whether any specific use of any specific book is allowed. Please do not assume that a book's appearance in Google Book Search means it can be used in any manner anywhere in the world. Copyright infringement liability can be quite severe.

About Google Book Search

Google's mission is to organize the world's information and to make it universally accessible and useful. Google Book Search helps readers discover the world's books while helping authors and publishers reach new audiences. You can search through the full text of this book on the web at `http://books.google.com/`

ASE DO NOT REMOVE THIS BAND
Storage
MOTE STORAGE
se return at the circulation desk.
enew your material call:
) 723-6691 ext. 3
e due in Lane Library:

RY

D)

THE CHANGE OF LIFE

IN

HEALTH AND DISEASE.

OPINIONS OF THE PRESS.

"THIS volume is an expansion of a much smaller one, which made its appearance some years ago. Dr. Tilt has now fairly occupied the field with a work, which is a repertory of information upon a subject not very generally understood. It is divided into twelve chapters: the first five are, an introductory one on the physiology of the change of life, one on its pathology, one on its therapeutics, and one on its hygienics. Then follow chapters which treat consecutively of the diseases of the reproductive organs at this period of life, of the diseases of the digestive organs, and of the skin; the tenth treats of the diseases of the ganglionic nervous system, and the eleventh of the cerebro-spinal affections; and the concluding chapter is miscellaneous. Thus the subject of climacteric derangements is pretty nearly exhausted, and additional value is given to the volume by numerous interesting tables, which exhibit various physiological and pathological facts in a clear and definite manner.

"There is a fund of practical matter in Dr. Tilt's book, and no small share of theory also, which is very clearly enunciated. As the best work on the subject of which it treats, we can cordially recommend it to the profession."—*Lancet.*

"Dr. Tilt has been a very earnest and a very faithful worker in the physiology and diseases of women, and has made contributions to the literature of the subject, which are all of accepted value. His treatise on The Change of Life has probably always been most popular. It is a full, careful, and yet gossiping treatise, founded on a very thorough search of the literature of the subject, and a careful digestion of clinical examples. It has, too, its own seal of originality, and is altogether one of those books which do not fail to arrest attention and arouse interest, and which succeed in stamping the author as a good clinical observer and writer, even if they do not mark any definite progress in science."—*British Medical Journal.*

THE CHANGE OF LIFE

IN

HEALTH AND DISEASE.

A PRACTICAL TREATISE

ON

THE NERVOUS AND OTHER AFFECTIONS

INCIDENTAL TO

Women at the Decline of Life.

BY

EDWARD JOHN TILT, M.D.

SENIOR PHYSICIAN TO THE FARRINGDON GENERAL DISPENSARY AND LYING-IN CHARITY,
VICE-PRESIDENT OF THE OBSTETRICAL SOCIETY OF LONDON,
FELLOW OF THE ROYAL MEDICAL AND CHIRURGICAL SOCIETY,
AND OF SEVERAL FOREIGN SOCIETIES.

FROM THE THIRD LONDON EDITION.

LANE MEDICAL LIBRARY
1706
SAN FRANCISCO

PHILADELPHIA:
LINDSAY & BLAKISTON.
1871.

LTS.

LANE LIBRARY

SHERMAN & CO., PRINTERS.

T 58
1871

PREFACE.

THERE are many milestones on the road that leads from the cradle to the grave—seven, fourteen, and twenty-one are clearly written on the first; forty-two, forty-nine, and sixty-three are distinctly visible, though less deeply cut, on those that mark the last part of the journey. These dates point to periods of the human life characterized by very important changes, many of which give a peculiar aspect to the physiology of the human being, and impart a family likeness to the diseases of epochs justly deemed critical. No division of labor is so praiseworthy as the study of these great periods of human life; and if many of those who fritter away their meritorious energy in writing monographs would devote it to thoroughly investigate the physiology and diseases of the great periods on which nature has put a special stamp, they would very much increase their fame and greatly contribute to the progress of medicine.

When the last census was taken in 1861, 1,177,535 of our fellow-countrywomen of the age of forty-five and under fifty-five were living in Great Britain and Ireland, and I can scarcely exaggerate the importance of a work which tells their history, records the probabilities and the inevitabilities of their future, and investigates the many diseases by which it may be chequered. This volume professes to do so, and it is founded on the tabulated estimates of the symptoms and of the diseases of five hundred women who were at the change of life, or who had passed the ménopause.

In this new edition I have kept to the original plan, giving a paramount importance to physiology, without which, the diseases of any critical period cannot possibly be understood. Although I have retained the statistical information on which the work was based, I have drawn largely on my experience among the upper classes of society during the last thirteen years, so as to rectify any pathological one-sidedness that may have arisen from the statistics having been principally derived from dispensary practice; and I trust I may be permitted to state that, partly because the importance of the subject was recognized by the profession, but chiefly because my work was the only one on the subject in the English language, I have been consulted by a very considerable number of women suffering from diseases of the change of life, since the publication of the second edition thirteen years ago.

To review the labor of rewriting this book is to comment on some of the events of the last few years; thus I have gathered valuable materials for my physiological study of the change of life from the contributions to the International Medical Congress that was held in Paris.

The chapter on the Diseases of the Reproductive Organs has been greatly increased, for I have lost no opportunity of taking careful note of whatever might illustrate this part of the subject, and the reader will there find information he will seek for in vain elsewhere; at least, Dr. Barnes said so of a sketch of the chapter that I read before the Newcastle Meeting of the British Medical Association in 1870.

A reviewer of the second edition, in the *Archives Générales de Médecine*, stated that, although the chapter on diseases of the brain extended to a great length, it was not long enough to do justice to the subject. This is an answer to those who may complain that the chapter is too long.

In the preface of the second edition, I mentioned that "the

present century has witnessed magnificent discoveries in the pathology of the brain and of the spinal cord; but it will be obvious to those conversant with medical literature that the pathology of the ganglionic nervous system has received comparatively little attention, neither can it be much advanced until experimental physiologists have accurately investigated many points connected with the physiology of the ganglia and their nerves. My object has been to prepare the ground for other laborers, by throwing on an intricate subject all the light I could collect. I have, moreover, attempted to trace the boundary-line between cerebral and ganglionic affections, now considered entirely dependent upon cerebro-spinal disturbance, largely illustrating the varied relations in which cerebral disorders stand to ganglionic diseases." Since then, Claude Bernard discovered that congestion, heat, and redness of surrounding tissues resulted from the section of the cervical ganglionic nerves; and Brown-Séquard has made us understand that this was caused by paralysis of the vaso-motor nerves, thus giving us the key for the right comprehension of the pathology of the ganglionic nervous system, and enabling pathologists to raise it from the slough of wild or silly hypothesis in which it has slumbered up to the present time.

Since the appearance of the last edition, Dr. Beale has published, in the Philosophical Transactions, a remarkable paper on the microscopic anatomy of the ganglia. Dr. Handfield Jones has repeatedly made valuable contributions to our medical journals, in which he has shown how fully one of our best pathologists is alive to the importance of distinguishing the diseases of the ganglionic nervous system from those of the cerebro-spinal nerves. Dr. Edward Meryon has recently entered the lists, and promises another valuable paper to the R. M. C. Society's Transactions. Like these esteemed fellow-laborers, my study of diseases of the ganglionic nervous sys-

tem, has been clinical, but I have moreover attempted to give a general sketch of ganglionic pathology. I have not, however, the presumption to think that I have done otherwise than reason more or less correctly on what is known of this recondite subject, and if those who take interest in diseases of the nervous system will criticize this chapter to the utmost, they will do good service to me as well as to science.

So far for the book; and now, as I have come to that time of life when a man is frequently startled by learning that another fellow-laborer has rested from his labor, and has forever done with ambition, I myself wish to state in a few words what has been my object and my course of work.

Early in life I was struck by the wise remark of Goethe, that if a man wants to make his mark he must set bounds to his work, beyond the limits of which he must not suffer his steps to stray, and work to the uttermost of his power within those appointed bounds. I took to myself the physiology and the diseases of women as my field of labor,—no limited specialty, I trow!

In my Elements of Health and Principles of Female Hygiene I have given the rules by which the health of women might be maintained at each successive period of life; it is a treatise of preventive medicine, for I am more and more convinced that most diseases of women are preventible, and that their frequent occurrence depends on the lamentable ignorance in which young women are brought up concerning all that relates to those very functions by which they are constituted women.

The physiology of puberty and its diseases were treated of at considerable length in the work last mentioned, and it forms the subject of the first half of my work on "Uterine and Ovarian Inflammation, and on the Physiology and Diseases of Menstruation," in which I endeavored to show that the best way to commence the study of, and to rightly understand the

diseases of women, is to study first the natural history of menstruation and its disorders. I hope at some future day to recast what I have written about this period of life, and to make a companion book to the present volume, under the title of "Puberty in Health and in Disease."

In a treatise on Uterine and Ovarian Inflammation, and in a Handbook of Uterine Therapeutics and of Diseases of Women, I record my views of diseases of women and their treatment. Among other things, I have tried to impress upon the reader that however much we may parcel out the body into more or less judiciously defined divisions for the convenience of study and the necessities of practice, there must be no special pathology nor therapeutics for each separate division. I have never ceased to inculcate that medicine should be one and indivisible, that we should reason upon diseases of the womb as we do upon diseases of any other part of the body and treat them by the same remedies, and that however different may be our modes of diagnosis, they should be all based on the same principle,—that of bringing to bear every available organ of sense upon the elucidation of disease. As far as I can judge, this teaching has told favorably on many of the junior members of the profession. I regret, however, that I should be sometimes consulted by women evidently suffering from chronic inflammation of the uterus, with ulceration of the mouth of the womb dipping into the cervical canal, as far as can be seen, and who, nevertheless, had been told by consulting practitioners that they were suffering from chronic debility, and had nothing the matter with the womb. Although in these cases the symptoms of protracted ill-health all pointed to the uterus and to no other organ, the practitioner had not thought it right to ascertain the nature of the case by an ocular examination, and his diagnosis was erroneous because he only made a digital exploration.

Although a digital examination be invaluable to ascertain the consistency, the size, and shape of the womb, it is often perfectly useless and unreliable for the diagnosis of ulceration, and of those various morbid states of the uterine mucous membrane that lead to ulceration. This conviction becomes stronger as I grow older, keeping pace with the increase of experience, now extending over thirty years. Indeed, it cannot be too often repeated to those who treat the diseases of women, that if the ocular examination of diseases of the womb were to fall into disuse, all further progress of uterine pathology would be arrested; nay more, it would soon retrograde to what it was before Récamier took it up, when uterine pathologists gave their chief attention to heteromorphous growths, when cancer was accepted as an ordinary result of chronic inflammation, when all forms of acute inflammation of the womb and the ovaries were considered the same disease, and called inflammation of the bowels; while chronic uterine affections escaping detection, kept many women in a more or less constant state of ill-health; till nature fortunately came to their relief and cured them at the change of life.

I have thus stated what has been my object as well as the plan on which I have worked; and as I have already introduced this new work, I have only now to place it in the reader's hands, trusting that it may help him to solve some of the difficulties of practice; but I cannot conclude without a warm expression of thanks to my friend, Mr. JOHN CHIPPENDALE, for kindly seeing the work through the press.

E. J. T.

60 Grosvenor Street, Grosvenor Square,
September 16, 1870.

TABLE OF CONTENTS.

CHAPTER I.

INTRODUCTION.

PAGE

Synonyms of the change of life—Importance of the period—Critical periods in general—Curative influence of the change of life—Its strengthening effects on the constitution—Its pathology little understood—Its diseases insufficiently attended to—Influence of the change of life on the mind and on the moral principles, . 17–27

PART I.

PHYSIOLOGY OF THE CHANGE OF LIFE.

CHAPTER II.

PHYSIOLOGY OF THE CHANGE OF LIFE.

The physiology and pathology of puberty compared with those of the change of life—Sketch of ovarian action in health and in disease at each stage of reproductive life—Date of cessation, and comparative date of cessation—Late cessation—Causes of protracted menstruation—Causes of early cessation—Diagnosis of the change of life—Typical appearance of women at the change of life—Cessation simulated by uterine diseases and pregnancy—Length of the dodging time—Average and comparative duration of the menstrual function—Terminations of the menstrual flow—

PAGE

Compensating agencies at cessation: respiration, urinary deposits, perspiration, mucous discharges, hemorrhages—Heat, nervous and chemical—Vicarious menstruation, ... 31–84

PART II.

GENERAL PATHOLOGY OF THE CHANGE OF LIFE.

CHAPTER III.

PRINCIPLES OF PATHOLOGY AT THE CHANGE OF LIFE.

Morbid liabilities of the change of life and their prognosis—Causes of disease at the ménopause, weakness of constitution, temperamental modifications—General diseases, a liability to uterine diseases, previous menstrual eccentricities, the sudden stoppage of the menstrual flow, the disuse or abuse of the sexual organs, social position—Nerve theory and blood theory of diseases of cessation, ... 87–100

CHAPTER IV.

PRINCIPLES OF TREATMENT AT THE CHANGE OF LIFE.

Main indications of treatment—Bleeding—Local depletion, purgatives—Alkalies, mineral acids—Sedatives—Sudorifics—Baths—Mineral waters—Issues, ... 101–118

CHAPTER V.

PRINCIPLES OF HYGIENE AT THE CHANGE OF LIFE.

Reproductive organs—Digestive functions—Cutaneous functions—Muscular system—Nervous system—Mental and moral hygiene, 119–132

PART III.

SPECIAL PATHOLOGY OF THE CHANGE OF LIFE.

CHAPTER VI.

DISEASES OF THE GANGLIONIC NERVOUS SYSTEM.

PAGE

Physiology and pathology of the ganglionic nervous system (and p. 202)—Gangliopathy—Ganglionic hyperæsthesia—Ganglionic dysæsthesia—Ganglionic paralysis—Hysterical asthma—Causes of gangliopathy (also p. 209)—Symptoms and Diagnosis (also p. 206)—Terminations (and pp. 157, 208)—Treatment of gangliopathy, ... 135–163

CHAPTER VII.

DISEASES OF THE BRAIN.

Nervous irritability—Headache and cerebral neuralgia—Pseudo-narcotism and coma—Hysteria—Epilepsy—Insanity—Delirium—Mania—Hypochondriasis and melancholia—Uncontrollable perversion of moral instincts—Temper—Dipsomania—Kleptomania—Erotomania (also p. 239)—Homicidal mania—Suicidal mania—Impulse to deceive—Demonomania—Hemiplegia—Theory of mental diseases—Insanity sometimes a termination of gangliopathy—Treatment, ... 164–215

CHAPTER VIII.

NEURALGIC AFFECTIONS.

Dorsal pains—Hypogastric pain—Paraplegia—Sciatica—Aphonia—Ocular neuralgia—Deafness—Rheumatic pains—Treatment, 216–227

CHAPTER IX.

DISEASES OF THE REPRODUCTIVE ORGANS.

PAGE

Flooding — Leucorrhœa — Vaginitis — Follicular vulvitis—Prurigo pudendi—Erotomania—Pudendal neuralgia—Ovario-uterine neuralgia—Diseases of the cervix—Ulceration of the womb—Acute internal metritis—Chronic internal metritis—Uterine deviations —The ovaries at the change of life—Uterine polypi—Uterine fibrous tumors—Cancer of the womb—Hydatids—Fatty degeneration of the womb—Ovarian tumors—Mammary irritation—Mammary neuralgia—Benignant mammary tumors—Mammary cancer—Tumors of the meatus urinarius—Diseases of the kidneys, 228–261

CHAPTER X.

DISEASES OF THE GASTRO-INTESTINAL ORGANS.

Biliary and dyspeptic affections—Vomiting—Diarrhœa—Constipation—Entorrhagia—Hæmorrhoids—Inflammation of the rectum—Permanent enlargement of the abdomen—Treatment, . . 262–272

CHAPTER XI.

DISEASES OF THE SKIN.

Flushes—Perspirations—Sweats—Cutaneous affections—Treatment, 278–282

CHAPTER XII.

OTHER AFFECTIONS OCCURRING AT THE CHANGE OF LIFE.

Gout—Rheumatism—Ascites—Consumption—Bronchitis—Hæmoptysis—Epistaxis—Ruptured varicose veins—Heart disease—Hypertrophy of the thyroid gland—Otorrhœa—Spinal deviation—Ptyalism, ... 283–287

LIST OF TABLES.

TABLE		PAGE
I.	Date of the Cessation of Menstruation,	38
II.	Comparative Dates of Cessation in different Countries,	39
III.	Fecundity of Women at various Ages,	42
IV.	Table of the Number of Marriages, and the Issue from such Marriages, occurring in the Eleven Years ending 1841, for Women under the Ages of 17, 46–55, and above 55,	42
V.	Fecundity Table for Sweden and Finland,	43
VI.	Chances of Pregnancy late in Life,	44
VII.	Ages of Women dying from Childbirth, in the Year 1852, in England and Wales,	45
VIII.	Date of last Menstruation in the early Menstruated and the late Menstruated,	48
IX.	Causes of early Cessation in 27 Women,	50
X.	Length of Dodging Time,	65
XI.	Duration of the Menstrual Function,	66
XII.	Comparative average Duration of Menstruation,	67
XIII.	Influence of early and late Menstruation on the Duration of the Menstrual Function,	68
XIV.	Duration of Menstruation according to the Age at which it begins,	69
XV.	Terminations of the Menstrual Flow in 637 Women,	70
XVI.	Monthly Occurrences after Cessation in 53 out of 500 Women,	75
XVII.	Cutaneous Exhalations in 300 out of 500 Women,	76
XVIII.	Analysis of Perspiration,	80
XIX.	Frequency of Mucous Discharges amongst 500 Women at the Change of Life,	82

TABLE		PAGE
XX.	Comparative Frequency of Hemorrhages at the Change of Life amongst 500 Women,	83
XXI.	Relative Frequency of Morbid Liabilities at the Change of Life in 500 Women,	88
XXII.	Comparative Morbid Liabilities at Puberty and at Cessation,	94
XXIII.	Nature of the Affections of 500 Women at the Change of Life,	100
XXIV.	Liability to Diseases of the Ganglionic Nervous System in 500 Women at the Change of Life,	135
XXV.	Frequency of Cerebral Diseases in 500 Women at the Change of Life,	164
XXVI.	Relative Frequency of Insanity at different Periods,	184
XXVII.	Liability to Neuralgic Affections at the Change of Life,	216
XXVIII.	Liability to Diseases of the Reproductive Organs in 500 Women,	228
XXIX.	Age of 2568 Women dying from Disease of the Sexual Organs in the Department de la Seine, from 1830 to 1835,	258
XXX.	Mortality of Ovariotomy,	258
XXXI.	Liability to Diseases of the Gastro-intestinal Organs in 500 Women,	262
XXXII.	Liabilities of the Skin to Disease at the Change of Life in 500 Women,	275
XXXIII.	Liability of 500 Women to other Affections at the Change of Life,	283
XXXIV.	Relative Mortality from Gout in both Sexes at successive Periods,	284

LIST OF CASES.

CASE		PAGE
I.	Chlorosis mistaken for cessation,	54
II.	Ulceration of the neck of the womb mistaken for cessation,	54
III.	Uterine polypus mistaken for cessation,	56
IV.	Fibrous tumor of the womb during the change of life supposed to be pregnancy,	56
V.	Uterine hydatids supposed to be the change of life,	51
VI.	Cessation mistaken for pregnancy,	59
VII.	Cessation supposed to be pregnancy,	60
VIII.	Cessation and spurious pregnancy mistaken for pregnancy,	61
IX.	Sudden embonpoint a sign of cessation,	78
X.	Bad effects of venesection,	104
XI.	Good effects of venesection,	104
XII.	Habitual relaxation of the bowels,	107
XIII.	Insanity at the change of life,	121
XIV.	Marriage at the change of life,	121
XV.	Ganglionic hyperæsthesia,	139
XVI.	Ganglionic hyperæsthesia,	140
XVII.	Ganglionic dysæsthesia,	142
XVIII.	Ganglionic dysæsthesia,	144
XIX.	Ganglionic paralysis,	145
XX.	Gangliopathy and hysterical asthma,	146
XXI.	Hysterical asthma,	147
XXII.	Periodical headache at cessation,	167
XXIII.	Cerebral neuralgia,	168
XXIV.	Pseudo-narcotism,	170
XXV.	Pseudo-narcotism,	171

CASE		PAGE
XXVI.	Successive fits of coma at menstrual periods,	177
XXVII.	Hysteria,	179
XXVIII.	Aphasia,	181
XXIX.	Epilepsy and impetigo,	182
XXX.	Delirium,	186
XXXI.	Delirium,	186
XXXII.	Mania,	187
XXXIII.	Apathy and sudden change of previous habits,	190
XXXIV.	Melancholia, with suicidal tendencies,	191
XXXV.	Melancholia,	192
XXXVI.	Hemiplegia,	199
XXXVII.	Melancholia and gangliopathy,	208
XXXVIII.	Lumbo-abdominal neuralgia,	219
XXXIX.	Frequent attacks of paraplegia, with gangliopathy,	222
XL.	Paraplegia,	223
XLI.	Sciatica,	224
XLII.	Herpetic affection of the labia,	237
XLIII.	Ovario-uterine neuralgia,	242
XLIV.	Ovario-uterine neuralgia,	243
XLV.	Acute internal metritis,	247
XLVI.	Pyelitis,	261
XLVII.	Jaundice,	263
XLVIII.	Repeated jaundice at cessation,	264
XLIX.	Chronic diarrhœa,	266
L.	Diarrhœa aggravated by cessation,	267
LI.	Periodical entorrhagia,	267
LII.	Repeated entorrhagia and hæmoptysis,	268
LIII.	Inflammation of the rectum,	271

CHANGE OF LIFE.

CHAPTER I.

INTRODUCTION.

THE terms "Climacteria" in Latin, "Climacteric disease," "Change of life," "Critical time," "Turn of life," in English, "Temps critique," "Age de retour," "Ménopause," in French, and "Aufhören der Weiblichen Reinigung," in German, are understood to mean a certain period of time, beginning with those irregularities which precede the last appearance of the menstrual flow, and ending with the recovery of health.

Variable as the duration of this time is in different women, it receives a certain degree of precision from the date of the last menstrual flow, which divides the change of life into two periods. When in the course of this work I speak of *cessation*, I always mean the cessation of the menstrual flow. There is no medical term to designate the time included between the first indications of the failure of ovarian energy, and cessation, but women call it "the dodging time," and as it happily expresses the uncertain and erratic appearance of the menstrual flow, I shall use the phrase to indicate the first part of the change of life in contradistinction to the last part, which begins at cessation, and concludes with the permanent restoration of health.

Although the importance of this epoch has been denied by Tissot, Dewees, Meissner, Saucerotte, and Landouzy, their opinion is not generally admitted by the profession, as is evident from many works of the last century, and from the more

modern writings of Fothergill, Sir C. M. Clarke, Dr. Meigs, and Dr. G. Bedford. The last author has truly stated, that "in addition to structural and malignant disorders so frequent at this period, there are many forms of eccentric nervous disturbance, various forms of temporary or permanent paralysis, and that the varieties of simple nervous irritation, without involving any peculiar lesion, are beyond calculation." German pathologists have admitted the importance of this epoch, which has, however, been chiefly recognized by the French. In addition to those whose names I shall soon have occasion to cite, Lisfranc completely adopted the popular belief in the dangers of the change of life; and Moreau de la Sarthe says, that "the change of life is characterized by headaches, syncope, leipothymia, general or partial spasmodic affections, hypochondriasis, the various symptoms of hysteria, and of insanity." Brierre de Boismont and Dr. Dusourd have recognized the vast influence of the change of life on the health of women, and I shall have frequent occasion to refer to their valuable works. I cannot equally commend the only two works expressly written on this subject, with which I am acquainted—one by Gardanne, in 1816, entitled *Avis aux Femmes entrant dans l'Age critique*, and the other, a treatise by Dr. Menville, published in 1840, and called *Du Temps critique chez les Femmes*. These two works have little scientific merit, but their hazardous assertions have suggested inquiries which would not otherwise have been undertaken, and they have afforded me some valuable cases for the illustration of the subject.

Some admit, with Voisin, the frequency and singularity of nervous affections at the change of life, but deny they can be caused by the monthly retention of a few ounces of blood; whereas it is contended that the cessation of the menstrual flow and the attendant changes, whether physiological or morbid, are principally induced by structural changes progressing in the ovaries, and by their various reactions on the system. One objection claims special notice, because it is founded on an erroneous interpretation of statistics. Benoiston de Chateauneuf and Odier de Genève have proved that, if a large number of women, between the

ages of forty and fifty, be compared with a similar number of men within the same periods of life, the rate of mortality will be greater among the males than the females. But those who bring forward these results, may as well say that parturition has no influence on the health of women, because it has little on their mortality; and, moreover, Finlayson has shown that, at all periods of life, more men die than women. Those who deny that the change of life is a critical period, argue as if *critical* meant *fatal*. In medical language, crisis means a sudden change for the better or the worse, leading as often to recovery as to death. Instead of flowing on in smooth tranquillity from the cradle to the grave, the stream of life is marked by rapids, which have been called critical, metamorphic, or developmental epochs, and during which an unusual predominance is acquired by one or by several of the organs which together form the human frame. The object of each successive critical readjustment of our frame is, to insure the greatest possible amount of health consistent with each subsequent period of life. This object is attained in the vast majority of cases, but the constitution only rallies after having been severely shaken for a certain period, varying according to constitution and temperament. In some, the critical changes of dentition and puberty are brought about without ill-health, but in many, these epochs are marked by disease, or by a prolonged condition resembling convalescence, and often checkered by serious disease. At all critical epochs, the activity of some important apparatus may be too powerful, and totally disturb the functions of its allied organs, as do the reproductive organs in hysteria, or it may be too feeble to react with sufficient energy on the system, as is the case with the reproductive organs in chlorosis. Whether the energy of the preponderance-seeking power is above or below par, health is impaired, for the system is deprived of the power of duly reacting against stimuli, whether physical or emotional. With regard to the pathogenic influence of the critical periods of life, first and second dentition seem to influence both sexes in the same way. Puberty is common to both, but the impulse then given to the constitution of man by the sexual apparatus is, in general, fully effective and all-

sufficient to insure its permanent activity until extreme old age; whereas, in woman this crisis is very liable to be delayed or perverted, and even when puberty has been effectually established, the health of woman is dependent on those oscillations of vital power which render menstruation healthy or morbid. Matrimony, pregnancy, parturition, lactation, are like critical periods, curing some complaints, giving greater activity to others; and when, after having lasted thirty-two years, the action of the reproductive organs is withdrawn from the system, prolonged ill-health is a frequent result. Then arise a series of beautifully adjusted critical movements, the object of which is to endow woman with a greater degree of strength than she had previously enjoyed; but if the seeds of destruction have been slumbering for years in the system, the change of life will give them increased activity. Thus Dionis of old, and Madame Boivin, Dupuytren, Tanchou in our time, have proved, that the greatest proportion of cancerous affections and polypi of the womb are complained of at that period, and it is the same with cancer of the breast, as well as with adenoid and neuromatic tumors of the breast, according to Velpeau. If the term critical be taken in a more restricted sense, as indicating a period in which the system finds relief by critical discharges, what time of life is so rife with critical phenomena? The floodings, leucorrhœa, diarrhœa, and perspirations, are eminently critical, and restore to health the vast majority of women.

This volume will forcibly show the evil effects of the change of life; its sanative influence cannot be so easily depicted, as patients consult the profession for actual disease, not to tell of diseases previously cured. With respect, however, to women who had been suffering for many years from intractable chronic affections that had baffled our best efforts to bring about recovery, the results of cessation are in general eminently satisfactory. We are most of us in the habit of telling our patients that they will be certainly cured by the change of life, and although this promise is often given to keep up the patient's hope rather than as the result of a well-grounded prognosis, still it is surprising how frequently the prophecy proves true. This remark particularly applies to ovarian

congestion and subacute inflammation, and to most chronic diseases of the womb.

I have notes of some forty patients who were for many years before the ménopause confined to the bed or the sofa by chronic uterine inflammation, who made marvellous recoveries very soon after the change was effected, and who are once more actively engaged in those pleasures and duties of society from which they had been divorced for ten or fifteen years. Out of many similar cases, in which recovery was not thus rapid and perfect, I cannot call to my recollection a single instance in which great improvement was not obtained. I have also ascertained from twenty-six women who had ceased to menstruate, that they were no longer troubled by habitual leucorrhœa, and doubtless many suffer for years from unrecognized uterine affections, which are at last completely cured by the change of life. Prolapsus of the womb was cured in three cases; thirty-five women no longer suffered from uterine deviations, though they still existed; in four cases varicose veins had gone down; in twenty-four, piles had disappeared; and in eight other cases they had ceased to bleed. Fifty-three women spoke of the great additional strength obtained, and of the abatement of their liability to dyspepsia. Ganglionic affections then often lose their gravity and become less frequent, and the same remark applies to almost all cerebro-spinal affections, even to the most formidable, for Esquirol has seen many women remain maniacal so long as menstruation lasted, who immediately and spontaneously recovered after the ménopause.

Reporting on the female lunatics at Colney Hatch, Dr. Davey says: "There are many females between the ages of forty and fifty, whose recoveries may be expected when the uterus shall have fairly resumed its original inaction, and when also the brain shall have lost a fertile source of irritation and disease. Unfortunately it happens that the poorer classes are much too unmindful of the health of women at the critical periods of life, and pay too little attention to the means whereby the uterus may be assisted in its efforts to preserve its due influence on the human economy; and therefore is it, in a very great measure, that insanity is of so frequent an occurrence among women." I have dwelt on this subject in

another work,* contending that in many of the worst cases, there was a prospect of the mental faculties being restored at the change of life; and quoting my suggestion, Sir W. C. Hood has admirably pleaded the cause of many most unfortunate women confined for life at Broadmoor for infanticide or other great crimes, committed during a temporary attack of puerperal mania, rightly observing that,† though there may be danger in restoring them to society while impregnation is possible, and therefore another attack also of puerperal mania, there can be none in releasing them some time after the change of life, and the late Dr. Ferrus, Inspector-General of French Prisons, entertaining the same opinion, the plan was successfully tried, and several women have been restored to society, for ten or twelve years, without a relapse having occurred.

The following case related by Négrier exemplifies the intimate connection between marked ovarian action and insanity, as well as the beneficial influence of cessation:

Case 1.—Madame X. was tall and lymphatic, and had been badly brought up. Menstruation first came at twelve, was very painful and irregular, accompanied by epigastric oppression, palpitation, convulsions, hypochondriasis, and suicidal mania. During the year that followed marriage, at thirty-eight, the attacks were less severe, but they became more so on the menstrual flow becoming scanty, and she never conceived. Some days before the menstrual period Madame X. became melancholy and secluded herself; there were lumbar and lower-limb pains, but the right iliac fossa was the spot whence radiated all her sufferings. She had made twenty different attempts at suicide, and when detected was ashamed of herself, and promised not to do it again. The fits would last five or six days, being most severe on alternate months. During the dodging time the fits were less severe, always coinciding with the menstrual flow; they failed to come in winter, and ceased altogether when menstruation left off at fifty-four.

* "Elements of Health and Principles of Female Hygiene." Bohn, York Street, Covent Garden, London.

† "Criminal Lunacy," by W. C. Hood, M.D. Churchill, New Burlington Street.

The critical nature of a period is shown by its effects on the health in ensuing years. Thus puberty is not only the crisis of most of the complaints of the preceding epochs, but it determines the health of the subsequent period for good or evil; in like manner, the change of life not only terminates critically many complaints of the preceding years, but it has a decisive action on the state of health during the whole subsequent period of life; so much so, that from the manner in which this crisis is accomplished, I believe it possible to predict whether, in after-life, the health will be good or bad. Fifty-three women, in whom there had been no menstrual flow for five years, and whose health had been habitually bad, spoke of their great additional strength of constitution, and this result may be taken as a rule which harmonizes with the popular belief. It is shown by the greater longevity of women, by their being less liable to sudden death, and by their general immunity from disease, for the little said about women in works on diseases of old age is a strong proof of the good health with which they are generally blessed during the last stage of existence.

In treatises on diseases of women the critical time and its infirmities are generally dismissed with half a page, and in none of our classical works have I found diseases of the change of life brought within the range of the laws of general pathology and general principles of treatment. Perhaps the deficiencies of medical literature are corrected in the daily practice, though some eminent practitioners are of a different opinion. They do not pretend that nothing is done to relieve the sufferings of women, but not enough; that a placebo is given where systematic treatment is required. Thus, Sir C. M. Clarke, commenting on the diseases of this epoch, states that "it is not unusual with women to refer all their extraordinary sensations to 'the change of life,' and to consider that, when they have thus accounted for their diseases, they have at the same time cured them; and in this most medical men, judging at least from their practice, seem to be of the same opinion."

Dr. Meigs likewise says: "In America too little regard is paid to the dangers of the crisis; and when the threatening

consequences of mismanagement or misapprehension have become startling, those fatal mutations are attributed to some trivial cause, and the victim passes away to the sound of the passing bell, and no increase of knowledge, acquired by such a mournful experience, stands in the way of the next victim to a management as unwise and as thoughtless."

"The complaints," adds Dr. Meigs, "which women at the change of life often make, are frequently hushed with the unsatisfactory reply that such complaints are owing to the change of life, and are likely to cease whenever the change shall become complete. A physician has no moral right, by his opinion, to put to sleep the anxieties of his patient, and to save himself the trouble of thinking by so concise and unphilosophical a mode of proceeding. Whenever, therefore, a female, at this period, which is universally admitted to be a critical and dangerous time for her, comes to complain of symptoms referable to some morbid condition of the reproductive tissues, it is clearly our duty to give a considerate attention to her case, and not to dismiss her until our judgment should be fully satisfied as to the therapeutical or hygienical indications of the case."

So much for pathology; and with regard to the physiological results of this great change in comparatively healthy women, I will say, with M. Flourens, that "from forty to fifty-five is a period of *invigoration* for both sexes—a period in which the deep interior work proceeding in all our tissues renders them firmer, and thereby insures a more perfect performance of all the functions. This change is insensibly worked out in man, but in woman the passage is often perilous, and the result is more marked. The great improvement in the general health subsequent to the change of life is a notorious fact." Although the phenomena of the change of life are principally due to ovarian involution, it may be helped by other changes proceeding in both sexes. For instance, Sir W. Jenner has lately stated, in one of his remarkable lectures, "that the spleen, the lymphatic glands, and Peyer's patches all suffer involution at the same period of life—about fifty. At that time the spleen grows smaller, the lymphatic glands waste, and Peyer's patches smooth down and lose their peculiar structure."

Dr. Day, in his work on "Diseases of Old Age," has not failed to note the true character of the changes taking place at cessation, for he shows how "climacteric *decay* is less frequently observed in women than in men, not only because women lead a less tumultuous life, but because their constitution has been so remodelled by the change of life that the causes of this decay have less hold over them." The immense importance of this change on the subsequent lifetime of women cannot be too highly rated, and as it is well got over or full of suffering, so will the subsequent lifetime be healthy or otherwise. It is a *final* settlement, for if it does not develop pathological seeds fatal to the system, the rest of life is generally passed in uninterrupted health, longevity being attained more frequently by women than by men. This invigoration of health is sometimes accompanied by a very great improvement of personal appearance, when bones become covered by a fair amount of fat; which "suave incrementum" is both comely and conducive to health. Others do not recover health without some sacrifice of feminine grace, their appearance becoming somewhat masculine, the bones projecting more than usual, the skin is less unctuous, and tweezers may be required to remove stray hairs from the face.

The effects of the disturbance of ovarian action on the mental faculties towards the first part of the change of life have been already alluded to. There is almost always, while the change is proceeding, a partial paralysis of ganglionic and of cerebral power, causing various forms of nervous irritability and some amount of confusion and bewilderment, which seems to deprive women of the mental endowments to which they had acquired a good title by forty years' enjoyment. They often lose confidence in themselves, are unable to manage domestic or other business, and are more likely to be imposed on either within or without the family circle. When the change is effected, the mind emerges from the clouds in which it has seemed lost. Thankful that they have escaped from real sufferings, women cease to torture themselves with imaginary woes, and as they feel the ground grow steadier underfoot, they are less dependent on others—for, like the body, the mental faculties then assume a masculine character. The

change of life does not give talents, but it often imparts a firmness of purpose to bring out effectively those that are possessed, whether it be to govern a household, to preside in a drawing-room, or to thread and unravel political entanglements. When women are no longer hampered by a bodily infirmity periodically returning, they have more time at their disposal, and for obvious reasons they are less subject to be led astray by a too ardent imagination, or by wild flights of passion.

The disturbance of regular ovarian action during the first part of the change of life sometimes tells unfavorably on woman considered as a moral agent. Her mode of dealing with the everyday occurrences of life may betray a certain want of principle, contrasting in a striking manner with her previous rectitude of conduct. There is often unusual peevishness and ill-temper, sometimes assuming the importance of moral insanity. After having lived in a most exemplary manner up to the change of life, some, for a scamp, desert husband and children, while others only stay at home to make it intolerable by their ungovernable temper, and to hate the long-cherished objects of their affection. A few are most miserable pictures of melancholy self-corrosion, sitting in silent and gloomy seclusion, neither loving nor hating, only wishing to be left alone to chew the cud of most baleful introspection. Some, in the midst of affluence, indulge a propensity for stealing, and four women confessed to me that they were obliged to have their children removed, for fear they should murder them; while others are tempted to commit suicide. Unless there be some strong hereditary taint, all these shades of moral insanity are susceptible of being cured by judicious treatment, as I shall amply show hereafter, and when the change of life is passed, the habitual rectitude of moral action returns. Doubtless the subsidence of ovarian action deprives one form of love of those strong emotional impulses which gift the passion with surprising energy; but although the heart becomes at last capable of listening to the head, still love rules paramount in the breast of woman, and whether called charity, friendship, conjugal or maternal affection, it still engrosses the thoughts, and failing all other forms and opportunities of

love, religion often takes a stronger hold, crowning the evening of life with unanticipated happiness.

When safely anchored in this sure haven, a woman looks back on the time when her health was disturbed by ever-recurring infirmities, by pregnancy with its eccentricities, by the perils of childbirth, and the annoyances of nursing. From the tranquillity she has attained, she may well revert to the long years when passion, jealousy, and their attendant emotions, often harrowed up her soul, presenting everything to the mind through a delusive prism. She will find how much her existence is changed from what it was, and will understand the saying of Madame de Deffand—"*Autrefois quand j'étais femme.*"

These results of the change of life are not only most important, but are daily occurring in about 1,200,000 of our countrywomen, so I need offer no apology for studying their complaints more accurately than has been previously done; and as I am one of those who maintain that physiology and pathology are interdependent, that their rate of progress invariably coincides, I infer that the little knowledge we have of diseases of the change of life is principally owing to the neglect in which physiologists have left many questions relating to this epoch, and that a better understanding of it is not to be attained without a careful investigation of all that relates to its physiology, and this I shall attempt in the next chapter.

PART I.

PHYSIOLOGY

OF

THE CHANGE OF LIFE.

CHAPTER II.

PHYSIOLOGY OF THE CHANGE OF LIFE.

If, hitherto, some of the physiological phenomena of the change of life have been unnoticed or imperfectly understood, it is because physiologists have not sufficiently considered their relation to the other critical periods of the reproductive functions. If pathologists are at a loss how to treat the continually recurring infirmities of the change of life, it is because they have not compared them with the diseases frequently met with at puberty. To explain how the change of life so completely modifies the constitution of woman, leading either to improved health or to diseased action, I am obliged rapidly to review the reproductive function, referring those who wish for further details to another of my works.*

About the age of thirteen, in the latitude of Great Britain, the constitution of girls is seen to change. Those who are delicate become more so; those who are in rude health suffer slightly. There is a frequent recurrence of pains in the back, in the lower limbs, and in the abdomen; there is a tendency to headache, nervous irritability, and fitfulness of temper. After this has lasted for twelve or eighteen months, a small quantity of blood is perspired from the womb, and the nervous symptoms abate, but they generally return again for a few months, until the recurrence every twenty-eight days of the menstrual flow, with a certain amount of nervous irritability, pain, and headache, has become a confirmed habit. In the meantime the body attains to its full proportions; the pelvis acquires sufficient size to permit the passage of a child; the

* "On Uterine and Ovarian Inflammation, and on the Physiology and Diseases of Menstruation." 3d edition.

breasts swell to prepare its food; there is a general improvement in health, and woman soon attains to her highest point of physical perfection. Unless interrupted by pregnancy and lactation the menstrual flow recurs every month for about thirty-two years, then it becomes irregular as at puberty, and after being so for about two years it ceases altogether. As at puberty, so at the change of life, women are habitually more irritable, more sensitive, more subject to headaches and to lowness of spirits. As at puberty, so at the change of life, a renewal of strength generally follows. Such is the menstrual function under favorable circumstances, but there is a reverse to every medal. Instead of recognizing puberty by increased health, how often do we infer it from the undeveloped form, the sickly look, and the chlorotic cast of countenance. Instead of slight pains in the back, limbs, and hypogastric regions, the pains may be severe and long continued, leading to, what has been called, spinal irritation and contraction of the limbs. Headache may incapacitate the patient for all exertion; her mental faculties may seem lost in a state of drowsy forgetfulness or pseudo-narcotism; nervous irritability may grow to hysteria under its worst forms; and instead of fitfulness of temper and waywardness of disposition, she may become morose and mischievous. In fact, the conduct of a girl at puberty sometimes betrays such a dereliction of all principle, that moral insanity is not too strong a term to characterize it. When the long-expected menstrual flow at last appears, it does not always bring health. Its return may be too long delayed, or should it come regularly, instead of being a bearable infirmity, it may be attended by so much abdominal pain and nervous symptoms as to constitute a disease; or there may be something amiss in the reaction of the reproductive organs on the nervous system, so that the menstrual flow may return every fifteen or twenty-one instead of twenty-eight days.

The change of life has also its diseases. Instead of being a period marked by slight infirmities, it may be characterized by very complicated morbid phenomena. There may be great debility and chlorosis as at puberty, or confirmed biliousness; the abdominal pains may be very severe; headaches frequent and agonizing; instead of a slight haziness of the mental

faculties there may be continued drowsiness and stupor; if hysterical convulsions are less frequent than at puberty, the globus hystericus and the minor manifestations of hysteria are very frequent, and insanity occurs oftener. If unrelieved by repeated critical discharges, such as flooding, leucorrhœa, diarrhœa, or perspiration, these complicated nervous symptoms may continue for years, and still be amenable to proper treatment, by which their occurrence might have been effectually prevented.

Puberty and the change of life are caused by anatomical changes, the one by ovarian *evolution*, the other by ovarian *involution*. At puberty the ovaries increase in size, become more vascular, and let fall ovula. At the change of life ovula are more and more scantily secreted. Little is known of the anatomical condition of the ovaries *during* the dodging time, and those in hospital practice would do well to ascertain whether they present any particular appearance in women dying at that epoch. After cessation, from smooth and turgid the ovary becomes shrivelled up, so as to resemble a peach-stone; then it becomes more and more difficult to trace the cavities of the Graafian vesicles, for their hypertrophied walls are pressed together. Later in life it is more and more atrophied, and I have found it not larger than a horse-bean, the place of the ovary being sometimes only indicated by a small fibro-cellular substance. This ovarian atrophy determines corresponding changes in the Fallopian tubes, which contract and are sometimes obliterated; it also causes the womb to become atrophied, and its neck thinner and shorter. Virchow has noted the closing of the internal os uteri in old age, and I have found an obliteration of the os uteri in five women, whom I had occasion to examine during life, from ten to fifteen years after cessation. It is well known that the vagina often becomes narrower and shorter, and the pampiniform plexus—a vascular contrivance to supply the organs of generation with a large amount of blood—shrivels up. The mammary glands are likewise atrophied after cessation, whereas during the change of life they are often congested and painful, if not otherwise diseased.

It will ever be a matter of surprise how so many phenomena

of health and symptoms of disease can be determined by two little oval bodies, whose structure does not appear to be complicated, but as the fact is unquestionable, it is well worth attempting to explain the varied manner in which these organs influence the system in health and disease. The ovaries influence the various parts of the body through the medium of their nerves, for as they have both ganglionic and cerebro-spinal nerves, they can react on both the ganglionic nerves and their centre, and on the cerebro-spinal nerves and their central organs. Whether the ganglionic be considered an independent system of nerves or an offshoot of the cerebro-spinal nervous system, all agree that it follows every capillary to its minutest ramifications, is vaso-motor, and governs the nutrition of all and every part of our frame. It is known that all important organs of nutritive life are supplied with ganglia and a plexus of ganglionic nerves, that they all communicate together, and with a larger plexus and more voluminous ganglia, situated at the pit of the stomach, called the solar ganglia and plexus; and before these foci of nervous matter had been noticed, Galen had called the epigastric region the lever of the forces by which the animal economy is moved. Without entering into details, which will be found in a subsequent chapter on ganglionic diseases at the change of life, I shall merely state, that while sensation and motion are intimately dependent on the cerebro-spinal system, nutrition is dependent on the ganglionic, and that there is a condensation of ganglionic nervous power in the central ganglia, which gives and receives from each viscus a variable impetus. Many pathological facts, which I shall set in order, are not to be accounted for without taking it for granted that the solar ganglia form an important centre of nerve force, capable of controlling and of disturbing the various parts of the body, by some subtle invisible fluid analogous to electricity, which I shall speak of as nervous fluid. Reasoning, then, from the facts to which I have alluded, it seems that the human frame is so constructed, that its various component organs can react upon each other in the way most conducive to health, until the age of puberty. At that time health often fails, and the whole system languishes, unless the reproductive organs come into full activity. From

puberty until the change of life, the health of woman cannot be maintained without an appropriate amount of ovarian influence. If this ovarian aura reacts healthily, it augments the power of the epigastric nervous centre, causes the functions of nutrition to be performed with increased energy, and gives an instinctive consciousness of strength. If, on the contrary, this ovarian aura be insufficient in quantity or defective in quality, it half-paralyzes the epigastric centre of ganglionic action, and uneasy sensations will be felt at the pit of the stomach,—feelings of sinking and faintness, actual fainting being sometimes induced. There is often pain, or anomalous sensations; and frequently a state of defective nutrition or chlorosis, a disease doubtless generally met with at puberty, but also of occasional occurrence during pregnancy and lactation, and which is often well marked at the change of life. If the ovarian stimulus be insufficient, it will retard the first appearance of menstruation, cause the flow to come irregularly, or for a time suspend its recurrence. If the ovarian stimulus be too strong or defective, it reacts with morbid energy on the other abdominal viscera, likewise endowed, each with its special ganglionic plexus and ganglia. It is not surprising that organs similarly endowed should sympathize, and that whether at each menstrual period, at puberty, or at the change of life, undue ovarian influence should give rise to more or less nausea and sickness, or to a perverted appetite; that it should cause the intestinal canal to secrete more gas or mucus than usual, thus determining diarrhœa; that it should force the lower part of the bowel to perspire blood; increasing the amount of water passed by the kidneys, and of the sediments contained in the urine, and rendering more abundant the amount of saline water perspired by the skin. If at each menstrual epoch, or at the beginning or cessation of the reproductive functions, the ovarian stimulus be too abundant or too energetic for the allied abdominal organs, then may also arise painful or strange sensations in the ovarian regions; for at each menstrual crisis, during puberty or the change of life, the spinal and hypogastric pains are caused by undue ovarian influence acting through the splanchnic and the spinal nerves. Some amount of pain is

perfectly consistent with the healthy performance of the menstrual crisis, with its inauguration at puberty, and with its demise at the change of life, for when the ovarian influence is defective, as in chlorosis, there is often no pain. The too abundant or too powerful ovarian action, after determining pain in the ovarian regions, causes pain, oppression, or uneasy sensations in the epigastric region, and sometimes globus hystericus; but its area of action is not confined to ganglionic nerves, or to nerves intimately blended with them, for through the medium of spinal nerves the ovarian stimulus acts on the spinal cord, and so develops its energy, that, whether at the monthly ovarian crisis, at puberty, or at the change of life, there arises frequently a tetanoid condition of the system, a state of nervous irritability, shown by an impossibility of repose, by a continued state of restlessness, by the fidgets, by what a French writer has called "impatiences organiques," or by hysterical convulsions. Or there may be numbness of some part of the skin, local anæsthesia, local paralysis, called hysterical in young women, and occasionally paraplegia or hemiplegia. The strength of the ovarian nisus, or the relative weakness of the nervous system, may be inferred from the fact of death occurring in the midst of hysterical convulsions, without any lesion being detected in the cerebro-spinal system. The ovarian influence having reached the ganglionic centre, is in communication with the brain by the pneumogastric nerves, so that at each menstrual epoch, at puberty, or at the change of life, its undue influence may be shown in some by distressing headaches, continued fretfulness, peevishness, and capriciousness, called temper, by a temporary perversion of moral feeling, or by moral insanity. In others, excessive ovarian action is manifested by motiveless high spirits or depression, by delirium, then called hysterical, and very frequently there is more or less of what I have termed pseudo-narcotism, in which case the cloud is no longer on the moral instincts, but weighs on the mental faculties, which are, for a time, in a state of misty haziness, the brain feels muddled, memory is faithless, there is an unconquerable desire to sleep during the day, even when the night has been passed in repose. This state

of the nervous system has in some cases amounted to coma and lethargy.

Having thus briefly sketched the varied phenomena which attend on the successive stages of the reproductive function, I am able to open the investigation of its terminal crisis.

To ascertain the date of cessation is a point of great importance, for it often marks the climax of much previous and subsequent suffering. In the following table I have placed side by side, the results obtained in Paris by B. de Boismont, and in London by Dr. Guy and myself. It will be seen that although the date of cessation varies from the twenty-first to the sixty-first year, yet it may generally be expected from forty to fifty. Thus, out of B. de Boismont's 181 cases, in 114 cessation took place between forty and fifty inclusively; in 330 of my 500 cases, cessation occurred during the same decennial period; and out of Professor Hannover's 312 cases of cessation in Denmark, 250 occurred during the same period of time.

TABLE I.—*Dates of the* CESSATION *of Menstruation.*

Age at Cessation.	Paris. B. de Boismont's cases.	London. Dr. Guy's cases.	London. Dr. Tilt's cases.	Total cases.
21st year	2	...	...	2
24 "	1	...	...	1
25 "				
26 "	1	...	...	1
27 "	1	1	1	3
28 "	1	1	...	2
29 "	1	...	...	1
30 "	...	1	10	11
31 "	3	...	1	4
32 "	2	...	4	6
33 "	...	2	1	3
34 "	4	1	2	7
35 "	6	3	6	15
36 "	7	1	2	10
37 "	4	5	7	16
38 "	7	5	6	18
39 "	1	7	10	18
40 "	18	33	42	93
41 "	10	24	17	51
42 "	7	24	26	57
43 "	4	23	24	51
44 "	13	24	23	60
45 "	13	45	49	107
46 "	9	34	31	74
47 "	13	25	42	80
48 "	8	38	37	83
49 "	7	25	32	64
50 "	12	37	49	98
51 "	4	14	27	45
52 "	8	13	16	37
53 "	2	8	9	19
54 "	5	2	7	14
55 "	2	1	6	9
56 "	2	2	4	8
57 "	2	1	2	5
58 "	...	...	4	4
59 "	...	...	1	1
60 "	1	...	1	2
61 "	...	...	2	2
Total,	181	400	501	1082
Average date of Menstruation.				
Years,	44.0	45.8	46.1	45.7

It will be noticed that the average date of cessation is higher in proportion to the amount of cases, that the average of the 1082 cases is forty-five years nine months, and that more women cease to menstruate in the fiftieth year than in any other, which is confirmed by Mayer's experience at Berlin, and by that of Lieven, at St. Petersburg.

What is known of the cessation date of menstruation is shown by the following table:

TABLE II.

Comparative Dates of Cessation in different Countries.

Countries.	France.		England.		Central Germany.	Denmark.	Norway	Lapland	Russia.
	Paris.	Rouen.	London.	Manchester.					
Number of Cases.	178	190	500	1586	824	312	391	34	100
Average Date of Cessation.	44.0	48.7	46.1	47.5	47.0	44.8	48.9	49.4	45.9
Observers	Brierre de Boismont.	Leudet.	Tilt.	Whitehead.	Mayer.	Hannover.	Faye and Vogt.	Vogt.	Lieven.
Sources of Information.	Traité de la Menstruation.	Paris Medical Congress.	This Work.	On Abortion and Sterility.	Paris Medical Congress.	Work on Menstruation.	Paris Medical Congress.	Paris Medical Congress.	Paris Medical Congress.

It is difficult to understand why there should be a difference of nearly five years between the dates of cessation of 312 Danish and 391 Norwegian women, but the similarity of results obtained by Professor Faye and Dr. Vogt should suggest to my friend Dr. Hannover to test the date of the ménopause in Denmark, by more extended figures.

There is nothing positively known respecting the date of cessation in tropical climates. Are we to believe the Hindoo medical student, who, out of his own circle of acquaintance, gave Dr. Webb* a list of thirteen Hindoo women in whom cessation occurred at the following very late dates?

* "Pathologica Indica," Part II, p. 279.

Years.	Cases.	Years.	Cases.
50, ...	1	63, ...	1
56, ...	2	64, ...	1
57, ...	1	65, ...	1
58, ...	1	67, ...	1
59, ...	1	68, ...	1
60, ...	1	80, ...	1

I could not match this list, from amidst those who consult me, nevertheless, a comparatively late date of cessation in India is rendered probable by the fact that Hindoo legislators place the ménopause at fifty, and in the Koran, women are only considered too old to have children after the fifty-third year of their age.

Having thus established the average age of cessation, the frequent exceptions to the rule remain to be considered, bearing in mind that it may be taken for granted that late fecundity proves late menstruation. Twice have I known the menstrual flow to continue its regular appearance up to the sixty-first year, in ladies of a remarkably strong constitution: which was the case with a lady who regularly menstruated up to the time of her death in her eighty-fourth year.

Mr. Roberton observes:—"I am able to speak confidently concerning three women who had children at advanced ages,—one in her fiftieth year, another in her fifty-first, and the third in her fifty-third year. In each of these instances the menstrua continued up to the period of conception." He also cites a case where menstruation ceased for twelve months about the fiftieth year, when it again became regular and continued so until the seventieth. Mr. Davies, my colleague at the Farringdon Dispensary, has confined a lady of her thirteenth child, at the age of fifty-three, after which there was no menstrual flow; and Dr. Davies published the case of a woman who was fifty-five when her last child was born, and who menstruated up to conception; and Dr. Meyer, of Berlin, in his remarkable paper* mentions his having ascertained that out of 6000 women, menstruation was still progressing in twenty-eight at the age of fifty, in eighteen at fifty-one, in eighteen at

* Congrés Médical International de Paris.

fifty-two, in eleven at fifty-three, in thirteen at fifty-four, in five at fifty-five, in four at fifty-six, in three at fifty-seven, in three at fifty-eight, in one at fifty-nine, in four at sixty, in four at sixty-two, and in three at the age of sixty-four, the seven last cases occurring in the upper classes. These unusually protracted dates make it appear singular that Hannover should have observed nothing similar in Denmark, for he only notes the exceptional occurrence of cessation in one case at fifty, two at fifty-one, three at fifty-two, one at fifty-three, and one at fifty-four.

Dr. Marion Sims has met with two cases of parturition at fifty-two, and a negro woman was said to be sixty, when she was confined twenty years after her last confinement.

Lamotte relates that a woman had thirty-two children, and menstruated quite regularly up to her sixty-second year. Auber attended two women, one sixty-eight and the other eighty, who for the last few years had again menstruated. The flow came regularly, lasted three or four days, and during that time they were more nervous than usual, the organs of sensation being unusually dull in apprehending their appropriate stimuli. Saxonia states that a nun, in whom the menstrual flow ceased at the usual time, experienced its return when her 100th year was attained, and it continued regular until her death, three years after. Rush mentions the case of a woman who was confined for the last time in her sixtieth year, menstruated until her eightieth, and died in her 100th year.

Haller records two cases in which women at sixty-three and seventy respectively bore children. Capuron cites the case of a lady, who after the menstrual flow had been absent for several years, saw it return at sixty-five. Three months after she miscarried, the fœtus being well formed. Meissner states that a woman who first menstruated at twenty, bore her first child at forty-seven, and the last of seven other children at sixty. Menstruation ceased and reappeared at seventy-five, continuing until ninety-eight, then stopped for five years, again to return at the advanced age of 104. In 1812 she was still alive.

I might increase the number of such cases, which are not instances of irregular flooding, but of the menstrual flow, oc-

curring regularly with its attendant symptoms, or followed by pregnancy. These facts contradict the opinion of those who assert that when the menstrual flow has once fairly ceased between forty and fifty, any blood that may afterwards flow from the womb must depend upon some undetected ulceration, but in most of the cases of late menstruation that have come under my notice, I have not found any ulceration.

The following table, extracted from the Registrar General's Report, shows that many more women than is supposed bear children late in life:

TABLE III.

Fecundity of Women at various Ages.

Ages of Mothers when their Children were born, ...	Under 20	20—25	25—30	30—35	35—40	40—45	45—50	Above 50	Total.
Children born from 1831 to 1835, ...	8301	70,924	121,781	126,808	98,950	49,660	7022	167	483,613

Thus, out of 483,613 women who became mothers from under twenty to above fifty, no less than 7022 bore children from their forty-fifth to their fiftieth year, and 167 were mothers after having passed their fiftieth year; that is to say, that 7189 women out of 483,613, or one in about sixty-seven, bore children after the time when the menstrual flow usually ceases.

The Irish fecundity table to which Dr. Routh refers in a paper on procreative power,* is equally conclusive:

TABLE IV.

Table of the Number of Marriages, and the Issue from such Marriages, occurring in the Eleven Years ending 1841, *for Women of the Ages under* 17, 46–55, *and above* 55.

Age of Husband.	Age of Wife.	No. of Marriages	Prop. of Children to 100 Marriages.	Age of Wife.	No. of Marriages	Prop. of Children to 100 Marriages.	Age of Wife.	No. of Marriages	Prop. to 100 Marriages
Under 17,	Under 17.	661	256	46 to 55.	1	0	Above 55.	1	0
17—25,		9847	262		35	51		3	0
26—35,		4066	252		145	51		12	0
36—45,		313	248		227	39		15	20
46—55,		36	205		428	22		52	10
Above 55,		18	128		295	10		136	12
Total, . . .		14,947	257		1131	26		219	12

* "London Journal of Medicine," 1850.

Thus it appears that in ten years, out of 427,977 women married in Ireland at different ages, there were no less than 1131 married between their forty-sixth and fifty-fifth year, and 219 were married after their fifty-fifth year. Those who wish for further evidence of the fact under discussion may consult the Registrar General's Seventeenth Report.

The following table shows similar results in a northern latitude:

TABLE V.

Fecundity Table for Sweden and Finland.

Age.	Annual Average Number of Deliveries.	Proportion to 100 Females living.
15 to 20	3,298	2.48
20 — 25	16,507	12.56
25 — 30	26,329	21.64
30 — 35	25,618	22.82
35 — 40	18.093	18.32
40 — 45	8,518	9.54
45 — 50	1,694	2.28
50 — 55	39	.05

In the paper referred to, Dr. Routh has published corresponding results derived from two London institutions. At the St. Pancras General Dispensary, out of 1527 women confined, the age of twelve varied from forty-six to fifty-seven. Two of the twelve were fifty-five and one fifty-seven. At the Westminster General Dispensary, out of 2509 women confined, the age of six varied from fifty-six to forty-nine. Dr. Taylor* has given the following table, drawn up by Neverman, which shows how suddenly the number of pregnancies diminishes after the forty-fifth year:

* "Medical Jurisprudence," p. 568.

TABLE VI.

Of 10,000 pregnant women, 436 or 43⅝ per 1000 were upwards of 40 years of age. Of these 436 women,

101 or $10\frac{1}{10}$	per 1000	were	in their	41st year.
113 or $11\frac{3}{10}$	"	"	42d	"
70 or 7	"	"	43d	"
58 or $5\frac{4}{5}$	"	"	44th	"
43 or $4\frac{3}{10}$	"	"	45th	"
12 or $1\frac{1}{8}$	"	"	46th	"
13 or $1\frac{3}{10}$	"	"	47th	"
8 or $\frac{4}{5}$	"	"	48th	"
6 or $\frac{3}{5}$	"	"	49th	"
9 or $\frac{9}{10}$	"	"	50th	"
1 or $\frac{1}{10}$	"	"	52d	"
1 or $\frac{1}{10}$	"	"	53d	"
1 or $\frac{1}{10}$	"	"	54th	"

Judging from many of the cases just recorded, fecundity was as remarkable as the protraction of the menstrual flow; and if so many women bore children after forty-five, it was not because they had married late, but because their ovaries had been endowed with unusual vitality. This view is supported by the experience of Mr. Roberton, who states "that in eleven women, three had a child each in the forty-ninth year, and the other eight had each a child above that age; I ascertained that the aggregate number of their children was 114—*i. e.*, ten and a fraction for each woman, a fact indicating that they must have married rather early in life. Concerning the age of marriage in two out of the eleven, I possess some little information; the one married at eighteen, had two children before she was twenty-one, and brought forth her fourteenth child in her fiftieth year; the other was married from a boarding-school at a very early age. In her fifty-third year she was delivered of her twelfth child."

Protracted menstruation also is proved by the following table:

TABLE VII.

Ages of Women dying from Childbirth in the year 1852, *in England and Wales.*

Ages.	Deaths from Metria.	Deaths from Childbirth.
15 and under 20	50	80
20 " 25	210	340
25 " 30	231	461
30 " 35	217	486
35 " 40	173	544
40 " 45	78	313
45 " 50	13	51
All Ages	972	2275

I have insisted on the frequency of pregnancy late in life, because grievous mistakes have often followed the practitioner's persuasion of its impossibility. To my knowledge, pregnancy late in life has been mistaken in three cases for an ovarian tumor, and was treated by iodine, mercurials, and tight bandaging, which caused the death of the child, and greatly compromised the mother's health. The popular belief, that parturition is more dangerous to the mother when it occurs late in life, is confirmed by Dr. Matthews Duncan, who has made out that if a woman has a large family, she only escapes the extraordinary risk to be encountered at a first confinement to encounter another extraordinary risk at a ninth or subsequent labor, and his statement is confirmed by Dr. Hugenberger of St. Petersburg.

It will be gathered from the preceding tables that the average date of the ménopause does not correspond with the last parturient efforts of woman, and Mr Whitehead has brought this out by operating on 1586 cases, and he found that while the average date of last menstruation was 47.5, the average date of the last confinement was 41.7.

What are the causes of protracted menstruation? The ovaries may become paralyzed before the time usually fixed for their atrophy, and resume their wonted energy by a sponta-

neous effort, by the shock of sudden grief, or through some impulse given to the ganglionic system, by fevers and visceral diseases. At the same time it is obvious, that a sanguineous discharge from the womb must not be accounted menstrual, unless it be repeated regularly; for fever may cause menorrhagia, as it may epistaxis. For instance, Gardanne gives a case, wherein an abundant menstrual flow is said to have come for the last time, after six months' stoppage, to a woman forty-nine years of age, during a bilious fever, in which emeto-cathartics were given. This might have been uterine hemorrhage: so might it have been in Bohnius' case, where the ingress of fever is stated to have brought on a return of menstruation in a woman eighty years old. The same remark applies to a statement lately made by Mr. Wood, of the return of the menstrual flow in a lady aged sixty-nine, in consequence of the death of a favorite son; and at sixty, to her sister, in consequence of a fright. In like manner I have three patients aged fifty-two and upwards, very much subject to heats and flushes, and in whom worry and excitement caused the womb to bleed. Such cases are open to doubt, unless the critical discharge returns regularly for a certain time, as in the following instance published by Mr. A. Brown.* A woman had not menstruated since her forty-second year, when, after suffering seven months from swelling of the liver and pains in the loins, she was critically relieved in her fifty-sixth year, by the sudden appearance of menstruation, which was repeated ten times, and perfectly re-established her health. Protracted menstruation is, however, more frequently caused by affections of the womb than of any other organ, and fibrous tumors of the womb often retard the date of cessation. Uterine polypi have the same effect, and in some of Dupuytren's cases of uterine polypi the menstrual flow lasted until the forty-ninth or fifty-sixth year; even in these cases the sanguineous discharge should not be considered menstrual unless it occurs periodically, or with periodical paroxysms. I have sometimes found that hypertrophy and ulceration of the neck of the womb, or other uterine diseases, coincided with an unusually protracted

* "London Medical Gazette," vol. xxi.

menstrual flow, and as the earlier observers had not the means of recognizing them, their cases of late cessation are, to a great extent, invalidated. I repeat that there may be uterine bleeding without menstruation, and I do not consider as cases of menstruation the case of a woman, who at seventy had an attack of apoplexy, and a red discharge from the vagina, the uterus was found full of blood, and the tubes and ovaries much injected. In another case likewise reported by Andral, a woman died at seventy-five of hemiplegia from extravasation in the left side of the cerebellum, the womb was full of blood, and its tissues intensely red.

With Dr. Dusourd, I consider ovarian activity to be commensurate with constitutional vigor, inasmuch as all those in whom I have observed the menstrual flow to be unusually prolonged, were remarkable for their strength and good health. Neither should the philosopher lose sight of the connection between the unusual prolongation of ovarian life and longevity, remarkable in several of the preceding cases, and I believe that life is longest in those women in whom puberty is retarded, as it is proved to be the longest in cold countries, where the average date of first menstruation is delayed beyond the average in temperate climates. Alexander von Humboldt has arrived at the same opinion, founding it upon extensive and comparative study of the numerous races which inhabit South America, and it may be assumed that when the ovarian nisus is healthily manifested, it indicates a corresponding healthy activity of the other functions of vegetative life; and when it is unusually prolonged, it implies a corresponding power of endurance of vegetative life, on which depends longevity, and the frequent protraction of cessation to the forty-eighth and the fifty-fourth year, which is said by Dr. Robert Cowie to occur in the Shetland Islands, corresponds with the frequent occurrence of longevity in the same islands.

Another means of judging whether in a temperate climate cessation will be retarded is the circumstance of its having first appeared later than usual. In some of the cases of very prolonged menstrual flow, it first appeared as late as twenty and twenty-two. On comparing thirty-three women who had

first menstruated from eight to eleven, with thirty-seven women in whom menstruation had been retarded from the eighteenth to the twenty-second year, I obtained the results shown in the following table:

TABLE VIII.

Date of last Menstruation in the EARLY *Menstruated and the* LATE *Menstruated.*

Years of Age at Cessation.	Cases of early Menstruation at from 8 to 11.	Cases of late Menstruation at from 18 to 22.
30	2	1
31	1	
34	1	
35	1	
37		1
38	1	
39	2	1
40	2	3
41	1	1
42	2	1
44	2	2
45	3	3
46	1	7
47	2	2
48	1	3
49	3	3
50	4	4
51	1	2
52	1	
55	1	1
58	1	2
Total, . . .	33	37
Average date of Cessation.		
Years, . . .	44.6	46.8

Two years and three months is a remarkable difference between the two averages, 45.7 being the average of the date of cessation in 1082 women.

These numbers are too small to be conclusive, but they tell

against the contrary opinion of Raciborski, who seems to have been too strongly impressed by very exceptional cases, like that cited by Descuret, of a woman who first menstruated at two years of age, married at twenty-seven, had a numerous family, and menstruated regularly up to her fifty-third year. Supposing, however, the table to be true for England, it is not so in Denmark, where Hannover found menstruation to cease soonest in those women in whom it began latest; and Dr. Mayer's figures confirm the assertion of Burdach and Mende, that the same holds good in Central Germany. Thus, while out of 722 women, 13 per cent. who first menstruated from eleven to thirteen ceased to menstruate at fifty; 11 per cent. who first menstruated from eighteen to thirty-one ceased at forty-seven.

With regard to the structural conditions, whereby in a certain number of women, the menstrual flow and fecundity are protracted to such an advanced age, it is fair to suppose that they were anatomically constituted like a lady in whom menstruation only became regular at the last years of her life, and who died at seventy-two, and in whom Drs. Bouvier and B. de Boismont found the ovaries and the whole of the generative system turgid, as in girls of fifteen to eighteen years of age; instead of being in their usual state of atrophy.

I now come to the causes of early cessation, or premature ovarian paralysis. As human life is often cut short long before the time specified by the Psalmist, so the reproductive force with which the ovaries are endowed may be extinguished long before the average date of forty-five. On careful consideration of forty-nine cases, wherein menstruation ceased suddenly from the twenty-seventh and thirty-ninth year inclusively, I was unable to detect anything peculiar to their constitution with the exception of eight, whose strength was below the average. None of the forty-nine had married too early, or were addicted to prostitution, which have been erroneously given as causes of early cessation by Meissner. They were not unusually subject to profuse menstruation, as asserted by Gardanne. They were not more than usually affected with disease of the reproductive organs, as stated by Meissner, neither did the diminished extent of the menstrual function indicate less repro-

ductive power, for the average amount of children was a little more than three in the twenty-six out of the forty-nine women who were married.

If women of the same family sometimes cease to menstruate at the same age, it may be a coincidence, but I have repeatedly known sisters to cease to menstruate at the same time of life. I attend two out of seven sisters; they all first menstruated from the tenth to the thirteenth year, and in all menstruation ceased about the fortieth year. Dr. Mayer has found, on comparing women of the lower and higher classes, that menstruation came later and ceased earlier in the lower classes, while in the upper classes menstruation came sooner and ceased later.

Out of the forty-nine cases in which the menstrual flow was suppressed from the twenty-seventh to the thirty-ninth year, in twenty-seven I found sufficient cause to explain the fact, as will be seen from the following table:

TABLE IX.

Causes of early Cessation in 27 Women.

Nature of Cause.	No. of Women.
Parturition and lactation,	3
Miscarriage,	1
A fall on the sacrum during menstrual flow,	2
Suppression of menstrual flow, from frost or intense cold,	2
Bleeding from the arm, at a menstrual period,	1
Getting wet through, during a menstrual period,	1
Violent purging, the result of medicine,	2
Cholera,	2
Rheumatic fever,	2
Bronchitis, with fever,	2
Fright,	9
Total,	27

Some of these cases deserve a few words of comment. Lucy A., aged fifty-three, had never menstruated since a miscarriage at thirty-two, and her health has been better ever since.

W. N., now fifty, a tall, stout-looking woman, had a child at

thirty-four, continued to flood for eight weeks. She suckled her child for a year, but has never menstruated since.

Elizabeth A., a woman of average strength, aged forty-seven, had a child ten years ago, suckled it eighteen months, and menstruation did not return. In such cases ovarian energy seems exhausted by parturition and lactation, and nature seizes the opportunity to put a sudden end to the menstrual function.

Julia L., a chlorotic-looking woman, aged forty-five, had no menstrual flow since she was thirty-three, when during menstruation, she missed a few steps and fell on her back. Here the ovaries were so paralyzed by a mechanical shock that they never recovered.

Emily F., a healthy-looking person, aged forty-eight, last menstruated at thirty-nine, when the menstrual flow was suddenly stopped by severe frost. She often had leucorrhœa during the two years which followed, but did not otherwise suffer. Another woman, aged thirty-four, went out shopping on the first day of menstruation, the weather being intensely cold; the flow was suddenly stopped and never returned, health remaining uninterruptedly good. In such cases cold has the same paralyzing influence as a fall, and similar effects may be produced by cholera or violent purging. Dusourd relates three cases where the menstrual flow ceased after the supervention of diarrhœa, coming about every month, and lasting for a few days; and he has known the menstrual flow to cease in three women from forty to forty-three, after an abundant hemorrhoidal flow. Fever has so powerful an effect on the viscera principally endowed with nervous energy by the ganglionic system, that one can understand why it should be a cause of ovarian paralysis.

As at puberty the menstrual flow is sometimes suddenly brought on by emotion, so fright and the sudden communication of bad news are the most frequent causes of sudden early cessation. The ovaries and womb are stunned by a nervous shock like the frog's muscles by a strong electric shock.

Ann G., aged fifty-nine; the menstrual flow ceased at thirty-nine, being suddenly suppressed by grief for the death of her husband. The same occurred at thirty-four to Maria B., now

aged fifty. Jane O., a healthy woman, had a flooding at forty-five, while witnessing an execution, and the menstrual flow never returned.

Elizabeth C., a dark-eyed, thin, sharp, and wiry old woman of seventy-one, had enjoyed excellent health until her thirtieth year, and had been nursing a child sixteen months, when her husband suddenly dropped down dead at her feet. Stunned by the blow, she let the child slip from her arms, lost her senses for a few hours, and her milk "turned to water." For a time she felt a good deal shaken, but was always able to attend to her household duties; and her health soon became as strong as usual and continued so until lately, although the menstrual flow had not appeared since her twenty-eighth year, and although the system had not been relieved by leucorrhœa, diarrhœa, piles, or by systematic treatment. A woman had been quite regular up to the age of thirty, when she threw a dead rat on the fire, thinking it was a coal; she retched for hours; for four years there was no menstrual flow, and after that an occasional show, at irregular times.

Eliza S., aged fifty-two, had been regular from eighteen to thirty-nine, when she was bled at a menstrual period for rheumatic pains in the shoulders. Immediately after being bled she vomited for an hour, had intense perspirations, but never menstruated again.

Ovarian tumors often cause early cessation of the menstrual flow. Thus, out of fifteen cases of ovarian tumors operated on by Dr. W. Atlee, of Philadelphia, some referred to young women, but in most cases the amount of the menstrual flow was diminished, and cessation occurred in four at thirty, thirty-nine, forty, and forty-two. I have seen internal metritis cause cessation at twenty-nine; but I do not agree with Scanzoni, that premature cessation is to be expected as the ordinary result of internal metritis, neither does my experience agree with that of Dr. Emmet, who thinks that early cessation is caused by dysmenorrhœa, partly obstructive and partly inflammatory; but I have repeatedly known cessation to occur about thirty, when it had been habitually scanty, as if the system found it too great an effort to continue the flow.

Diagnosis of Cessation.—Every well-marked condition of the constitution has its peculiar physiognomy, and even at the beginning of the change of life there is generally something in the appearance which leads me to suspect what is taking place. The physiognomy at such periods indicates debility and suffering, which cannot be accounted for by disease; or there may be the drowsy look, or the dull, stupid astonishment of one seeking to rouse herself so as to answer a question. In several of my worst cerebral cases, there was the same permanent knitting of brows expressive of constant anxiety. An unusual development of hair on the chin and upper lip generally coincides with cessation; so does a sallow complexion; there is also an unusual power of generating caloric, indicated by the habit of throwing off clothing and opening doors and windows even in winter, to the great annoyance of other members of the family. In other respects the appearance of women at the change of life varies according to the type they affect.

Women at the change of life present three types—1st. The Plethoric. 2d. The Chlorotic. 3d. The Nervous.

1st. The Plethoric type is unmistakable, with its turgid tissues, its over-florid countenance in a state of perspiration, its anxious expression, or half-intoxicated appearance. The pulse is often full and bounding, though it may be weak and thready in florid and stout women.

2d. While in some the change of life increases the proportion of globules in the blood, it diminishes them in others, and thus chlorosis is produced. The Chlorotic type is recognizable by the sallow or semi-chlorotic skin, the weak pulse, the arterial murmurs, and various symptoms of debility. Even on the blanched face, faint flushes will bring out perspiration.

3d. All women are unusually nervous at the change of life, but some present a well-marked nervous physiognomy without plethora or chlorosis. The over-anxious look, the brimful eye, the terror-struck expression, as if fearing to see some frightful objects, and the face bedewed with perspiration, are not uncommonly met with.

When the menstrual flow has been for many months absent

or irregular, too scanty, or too abundant, in women answering to the above description, I look upon cessation as probable, whatever may be the age, unless the absence of the menstrual flow can be satisfactorily explained by lactation, or pregnancy. In the absence of all other signs, the change of life is to be suspected when, for the first time, towards the forty-fifth year, the menstrual flow comes at irregular intervals.

Cessation may be confounded with I. Chlorosis. II. Inflammation of the Womb. III. Uterine Polypi. IV. Uterine Fibrous Tumors. V. Uterine Hydatids. VI. Uterine Cancer. VII. Pregnancy. I shall briefly illustrate these assertions by recording the mistakes which have occurred to myself or others.

I. Case 1.—*Chlorosis mistaken for cessation.*—Annie W., aged thirty-three, and married, had an anæmic hue of countenance. The menstrual flow first came at thirteen; had been regular and without pain until twenty-two, when she married, and had one child at twenty-four. There had been a gradual diminution of the menstrual flow for the previous year, with intense debility, epigastric faintness, and drenching perspirations, and a loud *bruit de souffle* in the carotids. Was it a case of chlorosis in a married woman, or chlorosis occurring at cessation? I inferred the latter from the *gradual* failing of the menstrual flow, and the pertinacity of the flushes and perspirations.

A camphor mixture, a belladonna plaster to the pit of the stomach, and sulphate of iron in pills, cured the patient, and when I saw her again three years afterwards her health was good, but there had been neither pregnancy nor return of the menstrual flow.

II. Case 2.—*Ulceration of the neck of the womb mistaken for cessation.*—Mrs. J., a delicate-looking lady, with light hair, and gray eyes, was forty-seven. The menstrual flow came at seventeen, without much disturbance. She married at twenty-five, and had three children, the last seven years ago, when her health failed, and the menstrual flow became irregular as to time and quantity, being sometimes very scanty,

and at others so abundant as to confine her to the bed or sofa for ten days. There were frequent bearing-down pains, often followed by leucorrhœa. For the last year there had been no menstrual flow, but always a little leucorrhœa, which every month became very abundant. She became nervous, irritable, and was sometimes troubled with flushes and perspirations. She thought the change of life had occurred, and medical advisers confirmed her opinion; but struck with the unusual persistence of leucorrhœa, ever since her last confinement, I advised a further examination, and found the neck of the womb three times its usual size, though little pain was given by pressure. The os uteri was patulous, rough, and extensively ulcerated. This was first treated by the application of the solid nitrate of silver every fourth day, and then by iodine exhibited internally and applied to the surface of the womb, which in six months was restored to a healthy condition, but the menstrual flow did not return. Eight years afterwards, when I again saw this lady, I learned that a few weeks after I had ceased my attendance, she was taken poorly in the usual way, and that the menstrual flow had appeared monthly ever since. Thus the menstrual flow had been prematurely stopped by the debilitated state of the frame and by the chronic uterine inflammation. That once cured, and the system having gained strength, the ovarian impulse became strong enough to induce the healthy uterine discharge.

Phœbe B. The menstrual flow gradually stopped at thirty-one, after suckling, and as it remained absent for a year, cessation was supposed to have taken place. On examination, however, I found ulceration of the neck of the womb; that being cured by surgical treatment, the menstrual flow went on as usual. In such cases, the error of diagnosis would be prevented by the surgical examination of the patient. In like manner, I have repeatedly known frequent flooding, recurring for years, to be attributed to the change of life, because the patients were about forty-five years of age; whereas, if the practitioners had taken the trouble to make a digital examination they would have found the flooding explained by soft hypertrophy of the cervix or uterine polypus.

III. Case 3.—*Uterine polypus mistaken for cessation.*—Mrs. P., a thin lady of moderate stature, with dark hair, hazel eyes, and a blanched countenance, consulted me when forty-two years of age. The menstrual flow came at seventeen, and was regular until twenty-two, when she married. She had one child, and menstruation continued regularly for several years; she then became subject to a red discharge, sometimes slight, at others very abundant. She was very weak, had palpitations on the slightest exertion, but no headaches, hysteria, flushes, or perspirations. Her medical man called the case one of premature change of life, but had he made an examination, he would have found a polypus the size of a hen's egg hanging from the cavity of the womb, by a pedicle about as thick as the little finger. I removed the polypus, and the menstrual flow returned, and continued regular for five years afterwards, and I have seen several similar cases, although, as a rule, uterine polypi retard cessation.

IV. Case 4.—*Fibrous tumor of the womb during the change of life supposed to be pregnancy.*—Mary B., aged forty-seven, unmarried, a tall, stout woman, of a sanguine temperament, dark hair, and a florid face. Menstruation first appeared at fifteen, and was regular, and very abundant up to the fortieth year. For the last seven years the flow was always irregular, and had often amounted to a flooding, with intense bearing-down pains. During the same time, she had been subject to frequent flushes and sweats, and to much pseudo-narcotism. Now her eyes look heavy and bewildered, her head feels giddy and stupid, she is afraid of falling; there are considerable abdominal enlargement, vesical tenesmus, and morning sickness. On examination, I found the womb much enlarged, more so on one side than on the other, owing to a fibrous tumor of the womb. Subsequently the menses were suppressed for four months, and as the abdomen had increased in size, she consulted one of my colleagues at the Dispensary, who, after examination, pronounced her pregnant. Distressed at an opinion which implied what she knew to be impossible, she again came to me, and I was able to confirm my former opinion. The result proved that I was right, for, soon after,

menstruation returned, and continued to do so at irrègular intervals for the following year. In this case, the age of the patient, the prolonged irregularity of the menstrual flow, the persistency of pseudo-narcotism, of the flushes and perspirations, made it probable that these symptoms were produced by the change of life.

The sanguineous discharge caused by fibrous tumors and polypi, and the flooding they determine, are often confounded with the menstrual discharge and with the flooding of cessation, and this may be correct if the flooding be periodical. In a case of fibrous tumor, which I shall hereafter relate, flooding lasted for eight years without intermission; but there is no ascertaining whether this was caused by the change of life.

V. The following case puzzled me exceedingly:

CASE 5.—*Uterine hydatids supposed to be the change of life.* —Anne H., a tall, delicate-looking woman, with light hair and blue eyes, was thirty-nine when she first consulted me at the Paddington Dispensary, June 17th, 1850. The menstrual flow first appeared at fifteen, with great pain. She married at twenty, had six children, and was regular up to the last year, since which time the flow came at two, three, five, or eight weeks' interval, with greater pain, and with nervous fits, in which, though conscious, she would remain from six to eight hours in a powerless and speechless state. On examination, I found nothing the matter with the womb, so I imagined the change of life was approaching, and treated her accordingly, but without affording much relief. The menstrual flow stopped for three months, up to which period nothing had caused me to alter my diagnosis; but in December flooding came on, and I have seldom witnessed greater sufferings than she endured for a year, flooding frequently occurring, with intense abdominal pains and hysterical fits. The womb was patulous, but not ulcerated, and its body was not much enlarged. I gave opium and ergot of rye in repeated doses for a long time with decided benefit, for on May 10th, 1851, the menstrual flow appeared at the proper time, and without much pain. The abdomen was much swollen. After walking home, on June

23d, dreadful forcing pains brought away from the vagina about a pint of sticky, rose-colored water, without smell. This was followed by a sanguineous discharge, lasting for several days. A digital examination was very painful, but I ascertained that the body of the womb was anteverted, much enlarged, and so high that it was difficult to reach the os uteri. I gave opium enemata, which relieved the pains; alum injections were used, but when they stopped the flow, the pains returned, which were only relieved by flooding. To obtain parish relief, it became necessary that the patient should be attended by Mr. Howlett; but I learned that, after very violent pain, half a pint of glutinous liquid was again passed from the vagina on July 5th, after which she continued to lose blood. It sometimes dribbled, at others came as a flooding. When the uterine discharge stopped for two or three days, the pains became excruciating, notwithstanding the exhibition of sedatives inwardly and outwardly; and this state of things continued until I was sent for to see the patient on December 6th, when, after labor pains, she brought away a large mass of hydatids, which well explained the frequent floodings and the patient's protracted sufferings. Ergot of rye induced bearing-down pains, and brought away dark, offensively-smelling blood. Opium relieved the sufferings; the patient recovered, and had another child a year after.

Uterine hydatids is a rare disease, generally occurring earlier in life, and its diagnosis is often very obscure. The enlarged womb, the continued flooding without ulceration of its neck, alternated with the limpid or rose-colored glutinous discharge—the best sign of uterine hydatids—was absent in the early part of this case. The diagnosis of uterine hydatids being clearly established, it would have been better to have dilated the cervix and to have brought on the expulsion of the hydatids, and to thereby save the patient six months' suffering.

VI. The floodings of cancer are not unfrequently considered indications of the change of life, particularly when they occur in young women presenting a healthy appearance—an error which can only be prevented by an examination.

VII. Pregnancy occurring late in life is often taken for cessation, the more so as, at whatever age, it is not unfrequently accompanied by the flushes, perspirations, and many of the nervous symptoms which characterize cessation. Under these circumstances it is better to give a very guarded opinion. Thus De la Motte relates, that a lady, for fear of having children, would not marry before fifty-one; and when she became pregnant, all the symptoms were considered to depend on the change of life. It much more frequently occurs, however, that the first symptoms of the change of life are mistaken for pregnancy. This is sometimes the effect of imagination; for many women have such a dislike to becoming old that, if married, they would rather persuade themselves they are with child; and they indulge this persuasion, until, like Harvey's widow, all hope vanishes in wind. Sometimes, however, the patient's belief in pregnancy is founded on data which puzzle the faculty. The menstrual flow stops, the abdomen gradually enlarges, and women, who have had children, are convinced they feel the moving of the child, the breasts swell and distil a milky fluid, there is sickness and impulsive desires; if a flooding takes place, the symptoms abate, but may again recur, to be again relieved by flooding, and these floodings of cessation are looked upon as miscarriages. B. de Boismont relates three cases of this description, and Fodéré two. The following are instances that have occurred in my own practice:

Case 6.—*Cessation mistaken for pregnancy.*—Mary C., married, aged forty-five, a tall, delicate-looking woman, with blue eyes and dark hair, thinks herself pregnant, and has been told so by several practitioners. The menstrual flow came at eleven, and was attended by little disturbance both before and after marriage. She married at twenty-seven, but she never conceived. For a year the menstrual flow has been either abundant, with large clots, or very pale, and for the last six months it has been altogether absent, the abdomen gradually enlarging, the breasts becoming swollen and sore, with leucorrhœa and hysterical sensations in the throat. On examination, I found the abdomen enlarged, but without the centrally situated, uniformly round tumor of a pregnant womb. The

womb was small, with a virgin orifice. That the patient was not pregnant I felt convinced, and I inferred the change of life from the long continuance of menstrual irregularities, the continued epigastric faintness, the flushes and sweats. My usual treatment relieved the patient; for many successive months she had an abundant vaginal mucous discharge, which was not interfered with. When I last saw the patient she was fifty, and there had been no return of the menstrual flow.

Case 7.—*Cessation supposed to be pregnancy.*—Sarah B., a tall, thin woman, of a sanguine temperament, says she is thirty-five, but looks forty, applied at the Farringdon Dispensary for a lying-in-letter, on May 7, 1851. The flow first appeared at fourteen, was unattended by pain. She married at eighteen, has had five children, but has never been well since her last confinement two years ago. Hypogastric pains were habitual, the menstrual flow irregular, for the last six times it had the appearance of dirty water, and ceased entirely seven months back, when the abdomen enlarged, and she now feels a fluttering similar to what she felt when pregnant. The breasts are swollen and discharge moisture, and the nipples are surrounded by a dark circle interspersed with a few pseudo-follicles. Notwithstanding these signs of pregnancy, and the patient's assertions, I did not think her pregnant; for there was no solid umbilical tumor, no softening of the neck of the womb; and the irregularities of the menstrual flow, and the appearance it last assumed, coupled with a great liability to flushes and perspirations for the last three months, were my reasons for thinking the change of life had occurred, and I ascertained that I was right upon inquiry several years after.

I have notes of three similar cases.

In the preceding cases, I believe that connection taking place during the change of life, induced a nervous condition of the ovaries and womb, capable of determining most of the symptoms of pregnancy; and when the abdominal swelling, the nausea, the enlarged breasts persist for months, the supposition of pregnancy might be easily admitted, and the rightful heir to an estate might be defrauded without the possibility of detection, if the woman had already borne children, unless

an investigation were made soon after the supposed event. Gooch has noticed another class of cases simulating pregnancy occurring at the change of life. The uterus is torpid, the intestines are flatulent, and the omentum and abdominal parietes have grown very fat, women having then, what Baillie called, "a double chin in the belly." The most notorious blunder of this description was in the case of Joanna Southcott, who, although sixty-four, was thought pregnant by many medical men. The walls of her abdomen were coated with four inches of fat, and the omentum was one lump of fat, and four times the usual size. It is evident that if women marry about the time of cessation, and are fat, and anxious to have children, they may have most of the subjective symptoms of pregnancy —morning sickness, painful breasts, the sensation of something moving in the abdomen, so that it is impossible to affirm the contrary, unless after examination, when the body of the womb will be found of the usual size and the cervix, hard as in its unimpregnated state. I have known women led to believe themselves pregnant on account of an enormous and rapid deposit of fat in the abdomen and breasts only.

Dusourd has met with several cases of uterine exfoliation at the change of life, the membrane being passed without flooding, but with great pain; and this might lead to belief in conception. I have always observed the exfoliation of the uterine mucous membrane to occur in much younger women, but in the first case of the kind recorded, Morgagni distinctly states, that the woman continued to exfoliate the mucous membrane of the womb, up to the cessation of menstruation.

In other women, unmarried or married, where no such membrane can be detected, the solid constituents of the blood unite, and come away as an ovoid "mole" in the midst of parturient pains. Then the womb really enlarges, and is able to cause all the sympathetic disturbance of pregnancy, as in the following case:

CASE 8.—*Cessation and spurious pregnancy mistaken for pregnancy.*—Five years ago I was consulted by a lady who moved in good society, was forty-five, unmarried, stout, and of a florid complexion. The menstrual flow came at fourteen, had

been regular and with little disturbance until the previous two years, when it became irregular, being sometimes very scanty, at others abundant and containing large well-formed clots coming away with intense abdominal pains. There had been no menstrual flow for six months previous to my being consulted, and at that time the abdomen had gradually attained a size sufficient to attract attention; her appetite was capricious and there was morning sickness, which circumstances led to ill-natured comments from some malicious acquaintances who spread about the report that the lady was in the family way, which report soon reached the ears of a gentleman to whom she had long been engaged. On making a careful examination, I found the womb much enlarged, but still it was not so large as it would have been had the patient been six months pregnant. The neck of the womb was shorter than usual, but not soft as it generally feels in the sixth month of pregnancy. The breasts were swollen, the nipples surrounded by a darker circle than habitual; but there were no follicles. Taking these circumstances into consideration, and bearing in mind that ever since the menstrual flow had been irregular, the patient had been constantly troubled by flushes and perspirations, I said that the lady was suffering from the symptoms of the change of life, complicated by chronic enlargement of the womb. A course of purgatives, mild tonics, and sedatives somewhat relieved the sickness and nervous symptoms, but the size of the patient seemed rather to increase than diminish. Two months after I was first consulted, or eight months after the menstrual flow had first stopped, I was sent for in the middle of the night, and found the patient in pains resembling labor pains, and after these had lasted several hours, a substance was passed about the size of a Seville orange. Its external surface was rough, in part coated with well-organized fibrin, and on being cut open it was found to contain limpid serum. The walls of this hæmatic cyst varied in thickness from two to five lines. Its internal surface had no lining membrane; and microscopical inspection confirmed the belief in the fibrinous nature of the cyst. The passing of this singular body was followed for several weeks by a sero-sanguinolent discharge, with considerable pain, and by intense

mental distress. On making an examination six weeks after this body was passed, I found that the womb had returned to its normal size; the mind was long in recovering tranquillity, for the engagement was broken off, valued friendships had cooled down to stiff formalities, notwithstanding my emphatic declaration that the blood cyst passed by the patient could not be the result of conception. When I last saw the lady she was forty-nine, and there had been no return of the menstrual flow.

I believe this kind of spurious pregnancy is most likely to occur in women who for the first time experience the matrimonial stimulus, at the beginning of the change of life. I have met with several cases of this description; one was a lady who married at forty-seven, after the first indication of the change of life. Another was a lady of forty-five, who after being a widow for twelve years, married again when the menstrual flow had become very irregular. Soon after marriage all the usual symptoms of pregnancy showed themselves, the womb seemed four or five times its usual size, and after remaining so for five months, a mass of half-organized fibrin was passed, and the patient recovered, but the menstrual flow continued irregular. Dusourd mentions the case of a woman, at the change of life, who thought herself pregnant, when on stooping, she felt herself wetted by a serous fluid coming from the womb, then the abdomen subsided as well as the swelling of the breasts. It stands to reason that a uterine or ovarian tumor at the change of life, may be an additional reason for supposing pregnancy.

The signs of pregnancy are, of course, obscure during the first few months, but then, judgment can be deferred. If, at a later period, mistakes are made, it is because all the circumstances of the case are not taken into consideration, or because one is not permitted to ascertain their existence. Thus, in the case of Joanna Southcott, the medical men who believed her pregnant were not allowed to make a vaginal examination; but even without that opportunity Mr. Sims was convinced that the impostor was not pregnant, from the state of her breasts and the absence of any umbilical prominence. In cases simulating pregnancy, the neck of the womb does not feel softened and puffy, the vagina is not livid. The patient states that the ab-

dominal swelling began at the navel, and did not rise from the pubis; the movements felt in the abdomen are accompanied by ill-defined depressions, instead of well-marked elevations. Pressure, cold, and the succussion of the body, do not reproduce the movements as they do when a child is in the womb. The navel is depressed instead of being salient, and there are ill-circumscribed hardnesses instead of a regular ovoid central mass, but no placental murmur or fœtal tic-tac; although there may be gurgling sounds in the intestines; and the follicular development of the breasts is imperfect. The diagnosis of cessation being thus established, I proceed with my inquiry.

Having ascertained the average date of last menstruation, I have a fixed point whereby to calculate the amount of time before and after which the health of women is more or less unsettled. The length of the dodging time varies, like the prodromata of first menstruation, from a few months to six or seven years. Out of my 500 tabulated cases, there was no dodging time in the 137 women in whom cessation was sudden; 275 thought the dodging time had lasted during the periods indicated in the following table:

TABLE X.
LENGTH *of Dodging Time.*

TIME.	CASES.	TIME.	CASES.
Months.		Years.	
1	2	2	52
2	3	3	25
3	9	4	9
4	4	5	4
5	5	6	6
6	32	7	5
7	4	8	3
8	11	9	1
9	3	12	1
10	9	14	1
11		18	1
12	60		
18	15		108
			157
	157	Total,..	265

Average Length of Dodging Time.

Years, ... 2.2.

The average duration of the dodging time would be two years and three months; but this would give an incorrect idea of its length, for, on cross-questioning patients, I have generally found that for a few months before the menstrual flow became irregular, other changes had taken place, either the quantity had gradually diminished, or was sometimes scanty, at others profuse. Frequently the quality of the discharge had altered, and had been, for months observed to be more serous, of a paler color, or like brown or green water. I therefore consider that ovarian influence begins to fail in most women, from two to three years before forty-six, or about the forty-fourth year.

There are, likewise, no positive means of measuring the length of time which elapses between the cessation of menstruation and the re-establishment of health, because the resettlement of the constitution is brought about insensibly, and varies extremely in different individuals; but from the study of 383 cases, I conclude that, in general, when three or four years have

elapsed since cessation, women are no longer liable to the floodings, the sweats, or to the distressing nervous symptoms, whether cerebral or ganglionic. I have, however, repeatedly known manifest symptoms of the change of life endure for many years, for twelve years in one instance, and with little abatement. When the cessation of menstruation is to bring into activity the seeds of complaints which have been long dormant in the system, it generally does so in the four years which follow cessation.

Having ascertained the average date of cessation, and taken into account exceptions to the rule, I give the following table, showing the duration of the menstrual function:

TABLE XI.

DURATION *of the Menstrual Function.*

Number of Years.	Number of Cases. B. de Boismont.	Number of Cases. Dr. Tilt.	Number of Years.	Number of Cases. B. de Boismont.	Number of Cases Dr. Tilt.
5	1		30	13	36
6	1		31	13	33
8	1		32	9	38
11	1	1	33	9	35
13		1	34	7	49
15		3	35	4	33
16	4	1	36	10	26
17	4	2	37	6	16
18	1	4	38	5	15
19	3	1	39	2	15
20	3	3	40	7	6
21	4	6	41	1	4
22	3	11	42	3	7
23	12	11	43	1	5
24	8	10	44	1	3
25	8	22	45		1
26	11	11	46		1
27	7	25	47		3
28	6	29	48	1	
29	7	33			
	85	174		92	326
				85	174
			Total,	177	500
Average duration of Menstrual Function, ...			Yrs.	28.93	31.33

These cases were collected under similar circumstances in Paris and in London; and I account for B. de Boismont having obtained so short an average duration of the menstrual function, from his having operated on so small a number of cases. The average duration of the menstrual function is therefore from thirty to thirty-two years, which is also the average duration of female fecundity, and that of each successive generation, three facts which are interdependent.

The papers in the Medical International Congress of Paris, and Dr. Hannover's excellent opuscule on Menstruation, have enabled me to construct the following table; and I am at a loss to understand how there can be more than four years between the duration of the menstrual function in Denmark and in Norway.

TABLE XII.

Comparative average DURATION *of* MENSTRUATION.

Countries.	France.	England.		Denmark.	Norway.	Russia.
		London.	Man. chester.			
Number of Cases,	178	500	69	312	391	100
Average Duration,	29.1	31.8	31.2	27.9	32	31
Observers,	Brierre de Boismont.	Tilt.	White-head.	Hanno-ver.	Faye and Vogt.	Lieven.

With regard to the duration of menstruation in India we have nothing but the crude beliefs of travellers, and of physicians, who were too lazy or too busy to count.

The annexed table confirms the unproved assertions of B. de Boismont in France, Drs. Guy in London, Frank at Milan, and Dusourd in the south of France, that the duration of menstruation is longest in those who have menstruated earliest, although cessation is sometimes delayed in those who menstruate very late in life, as it has been demonstrated at page 48.

TABLE XIII.

Influence of EARLY AND LATE *Menstruation on the* DURATION OF THE MENSTRUAL FUNCTION.

Years elapsing between first and last Menstruation.	Cases of first Menstruation at from 10 to 12 Years of Age.	Cases of first Menstruation at from 17 to 19 Years of Age.	Years elapsing between first and last Menstruation.	Cases of first Menstruation at from 10 to 12 Years of Age.	Cases of first Menstruation at from 17 to 19 Years of Age.
12		1	31	5	14
13		1	32	5	5
15		1	33	6	6
17		1	34	5	3
18	1		35	5	1
19		1	36	5	
20	2		37	3	
21	3		38	4	1
22	1	3	39	4	2
23	1	9	40	3	
24	1	2	41	1	
25		4	42	3	1
26		1	43	2	
27	1	9	44	1	
28	6	10	45	3	
29	3	4	47	1	
30	1	3			
	20	55		56	33
				20	55
			Total, . .	76	88
Average Duration of Menstrual Function, ...			Yrs.,	34.29	28.78

Thus while the general average duration of the menstrual function is thirty-two years, its average duration increased to thirty-four years and three months in the early menstruated; decreased to twenty years and seven months in the late menstruated; and there is the striking difference of five years and six months between duration of the reproductive life of those who menstruate at an early or late period of youth. This law holds good in Denmark, as will be seen from the following table, extracted from Dr. Hannover's work:

TABLE XIV.

DURATION OF MENSTRUATION *according to the age at which it begins.*

Dates of first Menstruation.	FAIR.			DARK.			TOTALS.		
	No. of Cases.	Dates of Cessation.	Duration of Menstruation.	No. of cases.	Dates of Cessation.	Duration of Menstruation.	No. of Cases.	Dates of Cessation.	Duration of Menstruation.
12	3	49.67	37.67	2	45.00	33.00	5	47.80	35.80
13	12	45.08	32.08	6	47.50	34.50	18	45.89	32 89
14	23	44.74	30.74	27	45.19	31.19	50	44.98	30.98
15	20	45.30	30.30	14	45.93	30.93	34	45.56	30.56
16	15	44.80	28.80	23	45.35	29.35	38	45.13	29.13
17	17	42.65	25.65	19	48 32	26.32	36	43 00	26.00
18	29	45.28	27.28	20	44.50	26.50	49	44 96	26.96
19	14	44.57	25.57	19	44.95	25.95	33	44.79	25.79
20	12	42 58	22.58	16	47.44	27.44	28	45.36	25.36
21	3	42.00	21.00	7	45 00	24.00	10	44.10	23 10
22	2	45.00	23.00	2	42.00	20.00	4	43.50	21.50
23	3	44.33	21.33	2	42.00	20.00	8	44 33	21.33
24	1	35.00	11.00	3	41.00	17.00	4	39.50	15.50
Total,	154	44.51	27.81	158	45.12	28.13	312	44.82	27.97

Is fecundity possible during the change of life? After the forty-sixth year the chance of fecundity suddenly diminishes, becoming less and less every year, but it is possible so long as the menstrual flow appears, however irregularly. I know of two instances in which conception occurred during the change of life. One was a single lady, forty-seven years of age, in whom the menstrual flow had been very irregular for the previous two years, with that general failure of health which so often indicates cessation. The belief that impregnation was impossible at this period led her to permit liberties which were followed by pregnancy and the birth of a child. This case is the more remarkable as connection only occurred once, seventeen days after a flooding which lasted for ten days, a fact difficult to reconcile with the ovulation theory.

Is fecundity possible after cessation? This question admits of being answered in the affirmative, because ovulation is not tantamount to menstruation. The ovaries may induce most of

the symptoms of menstruation, and they may shed ovules without the womb discharging blood. Women sometimes conceive during lactation without the menstrual flow having returned; and as, in some very rare cases, conception has taken place before first menstruation, so I believe it possible after cessation in very rare cases. Mr. Pearson, of Staleybridge, has published the case of a woman who, at the age of forty-seven, was delivered of her tenth child, eighteen months after the cessation of the menstrual flow. In answer to my inquiry, Mr. Pearson informed me that between her two last confinements, three years and four months had elapsed, and that, after suckling the child, she had been regular several months previous to the cessation of the menstrual flow, for which no cause could be detected. This woman suckled her last child and has not menstruated since. Forty-seven is no unusual date of childbirth; but the fact of conception taking place after menstruation had been absent nine months, is very singular. As an instance of the eccentricities which characterize the generative function, I may mention that I know a lady who was married at eighteen; both herself and her husband enjoyed habitual good health, but conception never took place until the lady was forty-eight, when she bore a child. It would have been the opinion of every medical man that all chance of family had passed, as in another case reported by Schmidt, where a well-formed female, married at nineteen, did not bear a child until she had reached her fiftieth year.

Having ascertained the date of cessation, I shall proceed to enumerate the various modes in which the menstrual flow may cease.

TABLE XV.

Terminations of the Menstrual Flow in 637 Women.

Modes of Termination.	No. of Cases.
By the gradual diminution of the menstrual flow, .	171
By the sudden stoppage of the usual menstrual flow,	94
By the sudden stoppage and a terminal flooding, .	43
By a terminal flooding, ...	82
By a succession of floodings, ...	56
By alternate copious or scanty menstrual flow, . .	36
At irregular intervals, longer than twenty-one days,	99
At irregular intervals, shorter than twenty-one days,	33
At irregular intervals, alternately longer and shorter than twenty-one days, ...	23
Total, ...	637

When the menstrual flow appeared at irregularly prolonged intervals, it was said to have occurred about every second, third, fourth, fifth, or sixth month, and sometimes at longer intervals, the longest being sixteen months. When it appeared at irregularly contracted periods, it was said to have occurred at about one or two weeks' interval.

The duration of the flow at each menstrual epoch was less and less in the one hundred and seventy-one women in whom there was a gradual diminution of the menstrual flow. When the mode of termination was erratic, the duration of each menstrual period was also irregular. Flooding continued either for a longer or a shorter time than that usually allotted to the menstrual flow; but I have generally observed that, during the first part of the dodging time, the menstrual period was often prolonged to eight, ten, or fifteen days. As this may, however, be caused by some disease of the womb, an examination is necessary. During the latter part of the dodging time the menstrual flow became less and less till it lasted only a day, or was a "mere show." With regard to its quality during this period, it was said to be sometimes blacker than usual, more clotty or sero-sanguinolent, or to be like cinder-dust and water, or dirty green water, like the latter part of the lochial discharge.

Many physiologists maintain, not only that menstruation is

always the effect of ovarian action, but that each menstrual flow is caused by the ovary shedding an ovule, and, under pain of great inconsistency, they must explain in the same way all its varied terminations. In their opinion, the emerging of an ovule from the ovary, causes the floodings of cessation or sero-sanguinolent discharges, no matter whether they occur every week or every six months. I am not obliged to adopt this explanation, for while granting the frequent coincidence of ovulation and menstruation, I have always held that the menstrual flow may occur without ovulation, just as ovulation may occur without menstruation. The more I observe, the more I am struck by facts which cannot harmonize with the ovulation theory. I have patients in whom any unusual nervous emotion or over-exertion will bring on the menstrual flow with the usual menstrual symptoms, although they may have only just recovered from this discharge. How can it be supposed that an ovule can be ripened, and the dense ovarian envelope suddenly perforated, by the fatigue of a dinner party, by hearing disagreeable news, or by an altercation with a servant? The laws of ovulation are as yet imperfectly known, but I believe that it proceeds as regularly, inevitably, and uninterruptedly as nutrition; whereas the menstrual function shifts its periodicities, returning about the fourteenth or the twenty-first day after the last epoch, whether it came at a right or a wrong time. This sudden shifting of periodic action is the special attribute of the nervous system, shows the menstrual flow to be impelled by nervous influence, and explains how a strong emotion may repel the menstrual flow or alter the time of its appearance. That sudden emotion should cause the uterine surface to perspire is only a repetition of the well-known effects of emotion on other parts.

Obesity.—The evident effect of the change of life is to remodel the female frame, so that health may be made consistent with the absence of an habitual drain. An unusual intensity of that force which presides over nutrition is shown by its being able in many women to use up the retained blood, so as to strengthen the tissues of the frame, in the same way that it improves their outward appearance. In others, the nutritive force stores up fat for future emergencies, and when cessation

has actually taken place, the accumulation of fat is similar to that which occurs in animals from whom the ovaries have been removed in early life. I have seen the sudden growth of fat coincide with great improvement in health, but Dr. G. Bedford goes too far when he states "that those who became fat-bellied were not troubled with nervous symptoms." If the vital force is not able to turn to good account the superabundant blood, and cannot maintain an efficient control over the vaso-motor nerves, a host of nervous symptoms arise and the balance of circulation is disturbed, so as to lead to erratic fluctuations, misdirections of blood, and to congestions or discharges from various organs. This occurs generally during the first part of the change of life, when women rather decrease in size than otherwise, even if they were to grow fat in the latter part. Thus out of 383 women in whom there had been no menstrual flow for five years, 121 had grown stouter than before, 71 had retained the same size, and 90 had become thinner; in other words, only one-fourth of the 383 had become thinner than usual five years after cessation. Wishing to know whether continued illness during the change of life had any effect on the greater or less tendency to become stout, I divided the 383 women into three classes, according as they had suffered much, little, or not at all, and I found that the proportions of the stout and thin were about the same, and that if those who suffered considerably during the dodging time had then become thinner, nutrition became unusually active in the latter part of the change of life. Three out of the 383 became suddenly fat at cessation, but this *embonpoint* was no indication of strength. Although the mammary glands become atrophied at the change of life, they often seem to retain their former size from the deposit of fat in their vicinity, and thus become pendulous. Fothergill has observed that women are more likely to grow stout in whom menstruation has suddenly ceased before the usual time, unless it be caused by some internal complaint. I have known this to occur several times, as in the following instance, which may help the diagnosis of early cessation.

CASE 8.—*Sudden embonpoint a sign of cessation.*—Eliza L., aged thirty-two. The menstrual flow appeared at nine, and came regularly with a moderate amount of headache and

pseudo-narcotism. She married at twenty-seven, but never conceived, and was regular until the menstrual flow suddenly ceased at thirty, after a fit in which she was unconscious for many hours. When a child at school, she used to faint away, and was with difficulty brought to her senses. She frequently fainted before marriage, but since then no fainting fits had occurred until two years ago, when, after unusual exertion, she remained unconscious for five hours. A year ago she had another fainting fit, and for the last two years she has been much troubled with giddiness, headache, and pseudo-narcotism. She now complains of not being able to see, "as if from a skin before the eyes." She is habitually troubled with epigastric pain, or uneasy sensations at the pit of the stomach, and she has grown immensely stout. Ten years afterwards I ascertained that there had been no return of menstruation.

As for thirty-two years it had been habitual for woman to lose about 3 oz. of blood every month, so it would have been indeed singular, if there did not exist some well-contrived compensating discharges acting as waste-gates to protect the system, until health could be permanently re-established by striking new balances in the allotment of blood to the various parts. The compensating agencies may be thus classed:

I. A larger consumption of carbon by the lungs.

II. An unusual amount of urinary deposits.

III. Increased perspiration.

IV. Abundant mucous flows.

V. Hemorrhages from various organs.

Some of these compensating actions proceed permanently, as from the surface of the lungs and skin; others occur irregularly; but in a certain number of cases the compensating action recurs periodically, assuming the monthly type, the type of the function which is falling into disuse.

TABLE XVI.

Monthly Occurrences after Cessation in 53 *out of* 500 *Women.*

Nature of the Occurrence.	No. of Cases.
Lumbo-abdominal pains,	15
Leucorrhœa,	12
Headache and pseudo-narcotism,	7
Diarrhœa,	5
Entorrhagia,	2
Bleeding piles,	1
Hysterical symptoms,	2
Hysterical oppression, or asthma,	2
Great depression of strength,	1
Sweats,	2
Dyspepsia,	1
Stomatitis,	1
Swelled gums,	1
Swelled legs for three days,	1
Total,	53

I. RELIEF AFFORDED BY RESPIRATION.—The balance between the respiratory and the menstrual function is forcibly shown by the fact that, at all periods of life, whenever menstruation is diminished or suppressed, more carbon is consumed per hour by the lungs, and less when the menstrual flow has been re-established. Andral and Gavarret found that, in both sexes, from eight years of age to puberty, there was an augmentation in the quantity of carbonic acid gas excreted by the lungs; that whenever menstruation takes place in women, they still continue to excrete the same quantity of carbonic acid as before; while in man, at the same age, the quantity goes on increasing until he has reached the middle period of life, after which he is said to secrete less and less. From experiments made on twenty-one women, it appears that during the whole of the time comprised between the first and last menstruation, the strongest and healthiest only excreted per hour a quantity of carbonic acid representing grammes 6.4, or the same quantity as before puberty, while men excreted grammes 7.8 per hour before their fifteenth year, and 11.3 per hour from

fifteen to forty years of age. After cessation of the flow, the lungs more largely excrete carbonic acid; for in five women aged from thirty-eight to forty-nine, and who had ceased to menstruate, the quantity of carbon consumed per hour rose from grammes 6.4 to 8.4. Women likewise excrete more carbonic acid from the lungs during pregnancy and amenorrhœa, which may help to explain how the seeds of consumption may be developed under these conditions.

II. Relief obtained by the increased deposits in the urine.—The majority of women notice that, during the dodging time, the urine, instead of being transparent, is unusually loaded with sediments, and this persists for weeks, and often recurs during that period. These sediments consist of lithates and phosphates, and, as in febrile affections, they indicate an effort of nature to relieve the system, and point to the utility of alkalies.

III. Relief obtained by increased secretions from the skin.—The importance of the relief afforded by the skin may be gathered from the subjoined table:

Table XVII.

Cutaneous Exhalations in 300 *out of* 500 *Women.*

	No. of Cases.
Perspirations attendant on flushes, . .	201
Perspirations occurring monthly, . .	2
Sweats, ...	84
Cold perspirations, ...	13
Total, . .	300

With the exception of the few cases in which the perspirations were cold and clammy, this exhalation is associated with an increased production of heat, and with that irregular distribution of it which is called "flushes." These occurred to 244 women out of 500; fourteen others were troubled with "dry flushes." The flushes determine the perspirations, and, as they constitute the most important and habitual safety-

valve of the system at the change of life, it is worth while studying them.

It must have struck many, that at the change of life most women have the power of generating a more than usual amount of heat; they often want less clothing, and even in winter leave their doors and windows wide open. Sometimes, however, instead of being regularly distributed, this caloric bursts forth as flushes, women feel as if something started from the epigastric region, spreading over the chest, and then over the face, which becomes suffused and hot. I have heard women compare their sensations to burning steam rising from the pit of the stomach. These flushes may be considered as cases of pathological blushing, depending on partial paralysis of the vaso-motor nerves. They sometimes come after a chill, or a momentary sensation of shivering, or after sinking and faintness at the pit of the stomach, but oftener without these sensations. If the flushes do not terminate in a gentle moisture of the skin, women call them "dry heats." The flushes may last two or three minutes, but it will often take a quarter of an hour to carry off the effects of each wave of heat that is wafted to the surface. The number of flushes occurring in the course of the day varies extremely. Their spontaneous repetition five or six times an hour, either by day or night, is not uncommon to women at the dodging time. Some months after cessation they frequently occur only seven or eight times in the day. This may be the case for years after cessation, and even in extreme old age, under the influence of worry or ill-health, without, however, having the intensity which renders them so distressing at the change of life. The recurrence of flushes so late in life is not to be wondered at, for women can blush at sixty or seventy years of age.

The face and chest generally suffer most from flushes, but the whole of the skin may be affected, and the hands and nails may feel like fire, the pulse being often weak and slow. Robust women, of a sanguine temperament, are more troubled with flushes, confirming Sir J. Ross's assertion, that the sanguine temperament has a peculiar power of generating heat, denied to the pale and sallow. All molecular action generates heat, and while this action incessantly proceeds in living

bodies they generate heat as permanent and continuous as their nutrition, beginning with life to cease only with it. The quantity and quality of this heat varies with the quantity and quality of the blood, which is the fuel of the animal combustion proceeding in the breadth and depth of our tissues, so that if the blood is in a healthy condition the heat is physiological, if on the contrary, it is the heat of fever; but how is heat collected? and what are the laws of its distribution? At times it will burst forth in fitful paroxysms; at times, as in intermittent fevers, these ebullitions of heat follow a rhythmical march, and depend on diseased action of the vaso-motor nerves, which hold the bloodvessels in their web-like grasp. One feels cold before dinner; a few mouthfuls of solid food are taken and sensations of warmth are produced, not to be explained by the assimilation of yet undigested food; that is *nervous* heat. When the food turns into chyle, passes into the blood and becomes the pabulum of the chemical actions of nutrition, there is a marked increase in the amount of *chemical* heat. Blushing exemplifies nervous heat. The mental portion of our being first receives an impression, and instantaneously communicates it to the emotional; then follows the sudden reaction on the epigastric ganglia; a momentary loss of power takes place there, during which the skin is somewhat paler and colder than usual, there may be an imperceptible sigh, a glow is felt at the precordial region, a sudden something seems to rush forth from the epigastrium, swift as lightning, and then wave after wave of blood is poured in burning streams to the whole surface, or only to the neck and face, which appear to blaze with living blood. The heat passes off, and the blood retreats from the capillaries, resuming its slower course, unless the emotional feelings become once more aroused. Thus, in the physiological phenomena of blushing, heat is evolved by the reaction of emotion on the voluminous ganglia and ganglionic nerves situated at the pit of the stomach; what this nervous centre does under the influence of emotion it also does *spontaneously*, causing the heats or flushes to which women are subject at the menstrual periods, during pregnancy, and lactation, but chiefly at the change of life; in fact, whenever the functions of the ganglionic nervous system are dis-

turbed. This confirms the assertions of the oldest physiologists, for Hippocrates noted shivering and an unusual development of caloric to be a sign of conception, Galen considered the reproductive organs to be a source of caloric, and Brongniart discovered that even in plants, reproduction is attended by an appreciable increase of their usual temperature.

It was well known that any great depression of nervous power paralyzed the vaso-motor nerves of the skin, causing it to sweat, but we owe to Claude Bernard the establishment of the fact that while the section of the sensory and motor nerves is not followed by any increase of heat, on the contrary, the division of the nerve by which the superior and inferior cervical ganglia communicate, by preventing the influence of the great sympathetic nerve from proceeding to its central ganglia, developed great heat in the capillaries above the point of section of the ganglionic nerve. Dr. H. Jones found that the division of a sympathetic nerve causes the bloodvessels within its range of distribution to dilate, the pulsation of the arteries to become more energetic, and the temperature to rise as much as 10° and 15°. When the sympathetic nerve is divided on one side of a horse's neck, that side of the face and neck becomes bathed in sweat. Something similar occurs at the change of life; the demise of ovarian activity half paralyzes the ganglionic system and the bloodvessels, thus leading to a greater development of heat, and to its irregular emission from the surface. Flushing, like a fit of ague, has a period of concentration, a hot stage, and one of perspiration; but as in ague there is often no first stage, so flushing frequently comes first, and often, without any previous congestion of the capillaries, perspiration is seen continually oozing out of the skin, where it stays until it is wiped away or rolls off. Why continued perspirations are so frequently met with at the change of life, and how they preserve women from worse evils, cannot be answered without some inquiry into the physiology of the skin.

With regard to the extent of the surface operated upon by nature, the entire surface of the body being estimated as over ten square feet, it has been calculated that there are 70,000,000 pores through which perspiration flows, besides the openings

by which the sebaceous glands emit their lubricating products. Lavoisier estimated that, in twenty-four hours, twenty ounces of perspiration were lost by the skin. Dr. Southwood Smith has shown that a robust man, working hard in an intense heat, may lose five pounds of his weight in an hour, so that the emaciation of those who perspire much is to be understood, as well as the *embonpoint* of those who perspire little.

Long ago Sanctorius established that "insensible perspiration alone discharges much more than all the other evacuations put together." Valentin found that his average hourly quantity of perspiration amounted to 463.3 grains, and that by walking up and down hill, to sweat copiously, more than four times this quantity was excreted, or 2048.8 grains. The average proportion of water in the human blood is 78 per cent., so that sweating gets rid of its redundant portion; and with regard to the other components of perspiration, Dr. Favre, of Paris, obtained from a healthy man 14 litres or 28 lbs. of perspiration, which he found to be thus composed:

TABLE XVIII.

		Pour 14 litres.	Pour 10,000 grammes.
		Grammes.	Grammes.
Solubles dans l'eau.	Chlorure de sodium, . .	31,327	22,305
	Chlorure de potassium, . .	3,412	2,437
	Sulfates alcalins, . . .	0,161	0,115
	Phosphates alcalins, . .	Trace	Trace
	Albuminates alcalins, . .	0,070	0,050
Solubles dans l'eau acidulée.	Phosphates alcalino-terrenes,	Trace	Trace
	Débris d'epiderme, . .	Trace	Trace
	Lactates alcalins, . . .	4,440	3,171
	Sudorates alcalins, . .	21,873	15,623
	Urée, ...	0,599	0,428
	Matières grasses, . . .	0,191	0,177
	Eau, ...	13,938,027	9,955,737

Dr. Favre draws the following conclusions from his researches:

1. That the materials of perspiration are almost entirely soluble in water.

2. That chloride of sodium constitutes the chief solid constituent of perspiration, the alkaline sulphates and phosphates being in very small proportion. In this respect perspiration differs much from urine, as will be seen from the following analysis of equal quantities of each:

		Perspiration 14 litres.		Urine 14 litres.
Chlorides,	grammes	34,639	grammes	57,018
Sulphates,	"	0,160	"	21,709
Phosphates,	"	Trace	"	5,381

3. Lactic acid, combined with alkalies, exists in the perspiration. It would be worth while ascertaining whether its quantity be augmented or not in the acid perspirations of lying-in women, in the sweats of over-lactation, or in those of the change of life.

4. Sudoric acid combined with alkalies, a hitherto unnoticed component of perspiration, is one of its principal elements. The composition of this acid is somewhat similar to that of urea, which is not normally found in perspiration; but when perspiration is stopped, as in the experiments of Seguin and Anselmino, the kidneys may transform sudoric acid into uric, and excrete it as urate of ammonia.

5. The existence of urea in perspiration completes the analogy of this fluid with urine.

6. Perspiration taken at different times from the same person did not vary in composition, but when the fluid taken during the first half-hour of the experiment is compared with that taken during the second or third half-hour, a larger quantity of mineral salts is found to be expelled during the latter periods. The proportion of water to the other components of perspiration does not seem to vary.

At the change of life the quantity of perspiration is often evidently increased, but we do not know how far its various components may be altered in amount.

As the skin is the most easily moved of all the safety-valves of the system, it is most frequently influenced by the change of life; while the small proportion of solid removed from the blood by sweat explains why this forms an ineffectual crisis,

the necessity for which is ever recurring, unless other changes have been effected. The critical nature of the perspirations occurring at the change of life, is shown by their appearance after sudden suppression of the menstrual flow, after diarrhœa or leucorrhœa. Thus in Eliza C., aged sixty, the menstrual flow suddenly ceased at forty-three, after getting her feet wet; and the perspirations were often so intense that the bedclothes could be wrung. Mary M., aged fifty-five; the menstrual flow came at nineteen and left at thirty by a flooding; she has ever since been subject to flushes and perspirations, by which her health has been preserved. After cessation the perspirations generally diminish, though I have noticed drenching ones to return five years after, in consequence of great anxiety, and twenty-nine years after, in a strong healthy old woman of sixty-seven. The perspirations do not always cover the whole body, but are limited to certain portions. Two patients always wear flannel at the pit of the stomach, because they perspire so much there, and there only, that their clothes become saturated. Like Tissot, I have seen gentle perspirations converted into sweats for a few days every month.

IV. Relief afforded by mucous flows.—The following table shows the frequency of mucous flows at the change of life:

Table XIX.

Frequency of Mucous Discharges amongst 500 *Women at the Change of Life.*

Nature of Mucous Flow.	No. of Cases.
Leucorrhœa at irregular intervals,	146
Monthly leucorrhœa,	12
Repeated vomiting of mucus,	31
Water-brash,	5
Frequent diarrhœa,	45
Monthly diarrhœa,	5
Total,	244

These mucous discharges must be considered as taking the place of the menstrual flow, for they were usually preceded

by the same symptoms, particularly when they came periodically, a fact already noticed by B. de Boismont. The critical nature of these discharges shows that they may require to be restrained, though not stopped. Of 260 women in whom the menstrual function had ceased, 143 had never been subject to leucorrhœa; of the remaining 117—

The vaginal secretion was increased at cessation in	77	cases.
It was diminished in	24	"
It remained stationary in	16	"

With regard to periodical leucorrhœa. In one case this occurred regularly every month for a year, for eighteen months in another, in several for two years, and in one for seven years. Most of these cases occurred to women in whom the menstrual flow had suddenly ceased.

V. Relief afforded by hemorrhages.—The extent to which women are relieved by hemorrhages is shown by the following table:

Table XX.

Comparative Frequency of Hemorrhages at the Change of Life amongst 500 Women.

Varieties of Hemorrhage.	No. of Cases.
Terminal menorrhagia,	82
Successive attacks of menorrhagia,	56
Bleeding piles,	24
Entorrhagia,	20
Epistaxis,	12
Hæmoptysis,	8
Cerebral hemorrrhage and apoplexy,	6
Hæmatemesis,	4
Hæmaturia,	1
Bursting of varicose veins,	3
Bleeding from external auditory canal,	4
Cutaneous ecchymosis,	3
Bleeding from a temporal vein,	1
Total,	208

Vicarious menstruation is rare at the change of life, but I have known a bloody discharge from the nipples to occur

every month, for five years after the menstrual flow had ceased; and in another case, a sero-sanguinolent discharge came from the nipples at irregular periods, during the two years that followed the ménopause. Dr. Semple has recorded the case of a woman, aged eighty, who, every other month, bled from the nose, or menstruated as in youth. These various hemorrhages are more or less successfully critical; the floodings at the change of life prevent more serious illness, and afford time for the gradual readjustment of the system. Successive floodings occur as often as the frame is overloaded by blood, returning at longer intervals and to a less amount.

Having thus concluded my study of the change of life, in a physiological point of view, I shall be able to point out briefly in the following chapters the special bearings of the change of life on general pathology.

PART II.

GENERAL PATHOLOGY

OF

THE CHANGE OF LIFE.

CHAPTER III.

GENERAL PRINCIPLES OF PATHOLOGY AT THE CHANGE OF LIFE.

A REFERENCE to the works written on diseases of the change of life by Gardanne and Dr. Menville would show the reader, that they consider as diseases of the critical time all which may afflict a woman after her forty-sixth year. This is perfectly absurd, for at any period of life we are liable to many diseases that are not caused by it, and as women grow old they are liable to the diseases of old age, for both sexes suffer alike from that wear and tear of life which impairs the structure of the heart and arteries, and indeed of most organs. I call "diseases of the change of life," such as occur for the first time, or recur with great aggravation during that period, variable as it is in each individual, but generally comprising the three years previous to, and the five years subsequent to, cessation.

The affections of the change of life sometimes come on before any marked irregularities in the menstrual flow: thus a tall, portly lady, aged fifty, is still regular, but for the last few months she has suffered from burning flushes, and her hands often become scarlet to the tips of her fingers. Some have merely flushes and slight perspirations for about three to five years after cessation, at the end of which time severe symptoms occur, and I attribute them to the change of life, because they are exactly similar to symptoms frequently supervening as the immediate result of the ménopause. Sometimes diseases of the change of life occur from the sudden interruption of the heats and flushes which had hitherto proceeded uninterruptedly; at other times the skin continues to act as the safety-valve of the system, until the health breaks down under the aggression of some mental or physical shock. In some,

the advent of disease frequently coincides with an imperfect menstrual nisus, indicated by abdominal pains and a menstrual flow, which, although very slight in quantity, and recurring three or five years after cessation, clearly indicates an effort of menstruation. Gout, rheumatism, or nervous affections, first occurring at the change of life, may continue, more or less till the end of life.

It is well known that, at some time or other of life, each organic apparatus becomes a normal or abnormal focus of action for the general circulation; for instance, the genital organs at puberty and cessation. Each well-marked period has its own particular stock of pathological calamities, and if the diseases common to one epoch do not cease at the beginning of the next, they generally continue during the whole period, or in other words, critical times are *perfect*, leading to the renewal of health, or *imperfect* and determining a succession of discharges which should not be suddenly suppressed. The change of life not only determines some diseases for the first time, but finding also the germs of others, such as gout, cancer, &c., it gives them an additional impulse. In the absence of trustworthy information, I have endeavored to obtain a correct bead-roll of the infirmities entailed by the change of life, and have set down very minutely whatever could be detected of morbid in 500 women who sought advice for diseases of the change of life. The following table, therefore, gives the comparative degree of frequency of morbid symptoms at the change of life, and it will show the reader, at a glance, what are the actual morbid liabilities of this epoch.

Table XXI.

Relative frequency of Morbid Liabilities at the Change of Life in 500 *Women.*

Nervous irritability,	459	Perspirations,	201
Flushes,	287	Leucorrhœa,	146
Pseudo-narcotism,	277	Hysterical state,	146
Dorsal pain,	226	Flooding once or repeatedly,	138
Gangliopathy and faintness,	220	Sick headache,	92
Headache,	208	Sweats,	84
Abdominal pain,	205	Piles, not bleeding,	62

Biliousness, obstinate,	55	Intercostal neuralgia,	6
Gangliopathy, or strange epigastric sensations,	49	Paraplegia,	6
Phosphatic and lithic urine,	49	Jaundice,	6
Diarrhœa, irregular,	45	Apoplexy and hemiplegia,	6
Debility, intense and long continued,	41	Supposed pregnancy,	6
Chloro-anæmia,	40	Colics, habitual for years,	6
Dyspepsia,	37	Nettlerash,	5
Remittent menstruation,	38	Ovarian pain, constant,	5
Vomiting, repeated,	31	Waterbrash,	5
Abdomen much swollen,	26	Epilepsy, increased,	5
Fainting away repeatedly,	25	Prolapsus of womb,	5
Piles, bleeding,	24	Cancer of womb,	4
Constipation, obstinate,	23	Inflammation of vagina,	4
Entorrhagia,	20	Bronchitis,	4
Œdematous legs,	19	Inability to retain urine,	4
Undetermined cutaneous eruptions,	18	Laughing and crying fits, only since cessation,	4
Globus hystericus, only since cessation,	17	Labia, repeated inflammation of,	4
Regular monthly pains without menstrual flow,	16	Numbness, pricking and loss of sensation in arms and hands,	4
Insanity,	16	Uterine fibrous tumors,	4
Dry flushes,	14	Hemorrhage from ears, increased,	4
Mammary irritation and swelling,	14	Prolonged fits of unconsciousness,	4
Perspirations, cold,	13	Vomiting of blood,	4
Leucorrhœa, monthly,	12	Polypus of womb,	4
Epistaxis,	12	Erysipelas,	4
Inflammation, or ulceration of the neck of the womb,	11	Sciatica,	4
Deafness,	11	Epilepsy, brought on,	3
Follicular inflammation of the vulva,	10	Delirium,	3
Difficulty and pain in passing urine,	9	Pus in motions,	3
Hysterical asthma,	8	Cutaneous ecchymosis,	3
Intense hysterical flatulence,	8	Prurigo,	3
Hæmoptysis,	8	Puffed face,	3
Monthly headaches,	7	Inflammation of legs, with great distension of veins,	3
Rheumatism of joints,	7	Eczema,	3
Ulcerated leg,	7	Ovarian tumors,	3
Diarrhœa, from three to six times daily for years,	7	Aching under nails,	3
		Inflamed rectum,	3
		Hysterical fits, only since cessation,	3
		Hemicrania,	3

Consumption aggravated,	3	Hæmaturia,	1
Bleeding from varicose veins of leg—in one case three times,	3	Monthly failure of strength,	1
Eczema increased,	2	" hysteria,	1
Monthly blood in motions for six months,	2	Hysterical paralysis of arms,	1
Boils in seat,	2	Falling-off of all the nails,	1
Aortic pulsation,	2	Peritonitis,	1
Legs burning and painful,	2	Chronic otorrhœa,	1
Intensely hot hands,	2	Inflamed eyes,	1
Abscess in arm-pits,	2	Toothache,	1
" fingers,	2	Morbus cordis,	1
" neck,	2	Shingles,	1
Gout,	2	Herpes circinatus,	1
Peeling of nails,	2	Mammary cancer,	1
Erectile tumor of the meatus urinarius,	2	Varicose veins brought on,	1
Brow ague increased,	2	" aggravated,	1
" brought on,	1	Bleeding from frontal vein,	1
		Limpid secretion from breast, for four years,	1

In my first edition, I stated that the real diseases of the change of life were the morbid exaggeration of some phenomena natural to cessation. Thus, as flooding occurs as a natural phenomenon at cessation, it may be attended by circumstances which may constitute it a disease. As increased perspiration is a natural phenomenon of cessation, so it may occur to a morbid amount under the form of continued sweating. The mild forms of gangliopathy are frequent accompaniments of cessation; therefore, the severer forms of the complaint may be expected. Cessation is almost always attended by slight and varied cerebral disturbance; therefore, severe nervous affections may frequently be expected. The foregoing table admirably confirms the views I have long entertained, and it shows that the *real* diseases of the change of life are the first twenty-five on the above list: they were the *common* complaints of this critical period, whose occurrence has been so frequent that they may be predicted; prevision being the only criterion of science, since it permits prevention. After the first twenty-five, the frequency of other diseases falls below five per cent., for they either form special varieties of the more common complaints already enumerated, or, like cancer and gout, they may occur at other times besides the change

of life. Sometimes, also, by the singularity of their nature and by the rarity of their occurrence, they are evidently shown to be personal contingencies, indicating how the impetus of morbid action was most felt by the weakest organ. The table likewise shows that the diseases to be really feared at the change of life are not so much cancer and other organic diseases of the ovaries and womb, with which women continually frighten themselves, as the neuralgic affections of the cerebro-spinal and ganglionic systems, and that gastro-intestinal affections are more to be feared than floodings.

From the foregoing table it is clear that functional diseases of the nervous system are frequently met with. The table does not so clearly show the frequent occurrence of debility; it is marked as the only disease in forty-one cases, but in a less degree it accompanies chlorosis in forty cases, and the two hundred and twenty cases of epigastric faintness, and was indeed rarely absent in all cases; so I conclude that diseases of cessation are characterized by debility. This loss of strength causes diseases of cessation to be generally chronic, and contrary to what occurs in childhood, pathological movements slacken pace. Malignant disease that at the age of thirty would have killed the patient in three years, may last longer. There is a chance of ovarian tumors remaining in abeyance which at twenty-five would have quickly galloped through their course. Ulceration of the womb takes longer to cure. The eschar made by nitrate of silver may take twelve days instead of four before it comes away from the womb, and the eschar made by the acid nitrate of mercury three weeks instead of one; hence the *prognosis* of diseases of cessation should be guarded, as in chronic disease.

Prognosis.—The prognosis of diseases at the ménopause is in general satisfactory, unless it be question of malignant diseases, very voluminous fibroid or ovarian tumors, and when the crisis so paralyzes the ganglionic centres that the patients cannot recover strength, and continue for years to lead a life of which every act is stamped with debility, not to be accounted for by organic disease.

Before sketching my theory of diseases at the ménopause, I shall briefly pass in review their causes, a correct estimation

of which is indispensable to understand the pathology of this critical period, and these causes are:

I. Weakness of constitution.—II. Temperament.—III. Constitutional disorders.—IV. Uterine affections.—V. Unusual suffering at puberty and at menstrual periods. VI. Sudden cessation.—VII. Disuse or abuse of the reproductive organs.—VIII. Social position.

I. Weakness of constitution.—The best way to avoid the dangers of this critical time is to meet its approach with a healthy constitution. A marked want of strength prevents the regular succession of the vital phenomena by which all critical periods are carried through; and as the change of life is marked by debility, when this is grafted on constitutional weakness, loss of power will be of long duration, sometimes with a tendency to faint, to chlorosis, to erratic nervous disorders, and all complaints remain chronic because there is not stamina enough to carry them through their stages.

II. Temperament.—I have stated that women of decidedly lymphatic temperament often derived marked benefit from the change of life. Their colder nature is less liable to be disturbed by bilious and nervous disorders, while the blood that was wont to be eliminated is turned to the improvement of the frame. Women of a sanguine temperament are naturally most liable to plethora, and therefore to floodings, hemorrhages, and apoplexy; but if they are most subject to dangerous diseases, they are most amenable to treatment, and speedily improve by active measures when judiciously applied. The preceding table shows a decided tendency of women to bilious and gastro-intestinal affections at the change of life; these affections being severe in women of a bilious temperament, as Gardanne remarked. Calomel and blue pill may long be given for an habitually torpid liver with little benefit, unless combined with the free use of alkalies, or the taking of mineral waters. Women are more liable to insanity, if the nervous be associated with the bilious temperament, as in some of my worst cases. Women of a nervous temperament suffer much more than others, particularly during the dodging time; they

are as liable to flooding as the plethoric, without being so amenable to treatment. The floodings of the nervous are the result of nervous erethism; in them simple things bring on inordinate reactions, and the common functions of life are performed with eccentricities without number. Such women seldom recover health unless they gain flesh.

III. CONSTITUTIONAL DISEASES.—It is evident that all constitutional affections will be increased by the change of life, and that an impulse will be given to cancer, gout, or consumption. These complaints, in their turn, aggravate the ordinary symptoms of the ménopause.

IV. UTERINE DISEASE.—For a long time after cessation, the womb is congested every month, as is proved by the frequency of monthly abdominal pains and of leucorrhœa. This state of congestion, without the usual adequate relief, is eminently calculated to give rise to congestion and irritability of the womb, and I believe inflammatory affections of the neck of the womb, during the dodging time, to occur more frequently than is represented in the last table. Should cancer impend, morbid irritability and congestion of the womb at the change of life increases the liability to that disease.

V. UNUSUAL SUFFERING AT PUBERTY AND MENSTRUAL ECCENTRICITIES.—The following table shows at a glance the morbid liabilities of puberty compared with those of the change of life; explains to a certain extent the occurrence of other complaints at those periods only, and how the perils of cessation may be inferred and measured by those which have attended puberty:

Table XXII.

Comparative Morbid Liabilities at Puberty and at Cessation.

Diseases.	Puberty.	Cessation.
Headache,	Frequent,	Frequent.
Sick headache,	Frequent,	Frequent.
Pseudo-narcotism,	Frequent;	Frequent.
Minor forms of hysteria,	Frequent,	Frequent.
Hysterical attacks,	Rare,	Rare.
Delirium,	Very rare,	Very rare.
Irregular temperand mild forms of moral insanity,	Frequent,	Frequent.
Epilepsy,	Frequent,	Very rare.
Gangliopathy,	Mild forms frequent,	Severe and mild forms frequent.
Fainting,	Common,	Uncommon.
Chlorosis,	Very frequent,	Not uncommon.
Lumbo-abdominal neuralgia,	Very frequent,	Very frequent.
Neuralgia of limbs,	Very frequent,	Not frequent.
Mammary neuralgia,	Not uncommon,	Not uncommon.
Flooding,	Rare,	Common.
Epistaxis,	Frequent,	Uncommon.
Piles,	Unobserved,	Frequent.
Leucorrhœa,	Frequent,	Frequent.
Cutaneous eruptions,	Frequent,	Rare.
Gout, its irregular forms,	Sometimes observed,	Not unfrequent.
Rickets,	Not uncommon,	Not noticed by me, but by B. de Boismont, and Gendrin.
Spinal deviations,	Very frequent,	Very rare.

Other diseases which may have preceded first menstruation may likewise be expected to precede its cessation; thus Alibert informed me that he had observed some cutaneous eruptions to appear twice only in life, viz.: before the first appearance of the monthly flow, and at its cessation. B. de Boismont, and others, likewise notice the appearance of hysteria and epilepsy before these two important epochs, the patient's life having been free from these diseases during the intervening period. Sir H. Marsh frequently noticed that women, in whom the establishment of puberty had been preceded by repeated epistaxis, experienced the same accident as a prominent symptom of cessation. In my own practice,

I have several times seen puberty and cessation preceded and attended by an abundant eruption of boils, by long-continued otorrhœa, frequently by continued diarrhœa, and still oftener by a great amount of pseudo-narcotism and hysteria in cases where there was little or none, while the function was regular, during childbearing, or lactation.

Spinal deformity slightly developed at puberty may become very marked at cessation, as in a case given by B. de Boismont, where a lady, comparatively straight, became deformed at the change of life, and I have published a similar case in which the pain attending internal metritis was so great that I could never get my patient to lie down flat, and she always slept in a crouching posture. The fact of the menstrual periods having often been unusually painful, is a reason to fear that the change of life will be fraught with unusual suffering, and the same applies to those in whom the menstrual flow has been very irregular, and liable to deviations. Thus B. de Boismont relates of two women, in whom the critical discharge took place from the mouth, even after they had borne children; that at the change of life, one became rickety, the other had ascites. In some, the liability to disease at this period might be referred to the predominance of a nervous temperament; in others, it depends on hidden peculiarities, which render the performance of the various acts of the reproductive function calamitous through life.

VI. Sudden stoppage of the menstrual flow.—It was logical to suppose that a drain, lasting for thirty-two years, could not suddenly cease without causing serious illness; and Meissner, like many others, attributes to this cause the most disastrous effects; incorrectly, however, for I have not noted sudden cessation as frequent in those who suffered most at the change of life. Thus, in 383 women in whom the menstrual flow had ceased, 223 had suffered much, 121 little, and thirty-nine not at all. Sudden cessation occurred in each class in the following proportion: Fifty-five out of the 223 who suffered most, thirty-one out of the 121 who suffered little, and twenty-three out of the thirty-nine cases who did not suffer; so that while sudden cessation only occurred in

about one-fourth of the severest sufferers, it occurred in about two-thirds of those who did not suffer at all. On studying the thirty-nine cases, I was struck by their presenting a singular absence of all menstrual disorders. In many the menstrual flow began suddenly, continued regularly through life without disturbance, and ended suddenly.

The current belief in the dangers of sudden cessation is grounded on some isolated cases in which it proved dangerous, owing to the action of other causes: thus, in two plethoric subjects, hemiplegia was induced; but alone it will not cause diseases of cessation, because the system is equally suddenly relieved by some critical discharge, and most frequently by well-sustained perspirations.

VII. Disuse or abuse of the reproductive organs.—Gardanne and other writers countenance the popular prejudice that the unmarried are most liable to flooding, to cancer, to ovarian and uterine tumors at the change of life, but there is no truth in the assertion. The single pass through this period without more trouble than the married, and, so far as I can ascertain, suffer less than other women. Gardanne likewise asserts that prostitutes suffer much at this epoch, an assertion utterly groundless, for Mr. Acton tells us they do not carry on their infamous pursuit for more than three years, on an average; so that they have seceded from the ranks of infamy, long before the change of life. I have occasionally traced an aggravation of diseases of cessation to sexual intercourse, and to women marrying while the change was progressing, I have repeatedly known it to be followed by flooding, by ovario-uterine irritation or inflammation. In one case a sensible lady, whose family was not tainted by insanity, had a flooding on the wedding night, very violent abdominal pains during the following days, and went out of her mind for many months.

VIII. Social position.—I believe with Dusourd, whose practice lay in an agricultural district in the south of France, that peasant women suffer little at this period. They belong to the *genus inirritabile*, and are therefore little liable to nervous disorders. Their health is generally good when the change of life comes on; flooding is frequent, but effectually

critical, and they take little heed of the flushes and perspirations which annoy the spoiled daughters of civilization. The poor of large towns suffer much at this epoch. The necessity for working hard, the anxieties of poverty, the impossibility of escaping the annoyances of children, even for a few hours in the day, increase the sufferings of the poor at the change of life. Certain occupations have a similar effect; thus, Auber says that washerwomen suffer more than others, on account of the vicissitudes of temperature to which they are exposed. The close, damp, and heated rooms in which bookfolders, catgut makers, and others are obliged to work, increase the sufferings of many; but by a fortunate compensation, the necessity for working hard prevents and cures the nervous affections which so frequently assail the rich at this period; for luxury is the hot-bed of nervous affections, they grow there in profusion, and run into such strange eccentricities, that pathologists have given up the hope of completing their catalogue. Of what use is leisure to practice all the appliances of hygiene, without the resolution to use them? Many of the poor are not forced to work in atmospheres so injurious as those of the heated ball-rooms frequented by the wealthy.

In going through my numerous cases, to discover why some women suffer so much and others so little at this period, I come to the conclusion that it does not so much depend upon the strength, original or acquired, that the system enjoys, and which is *constitution;* nor on the visible predominance of one set of organs over the other, which is *temperament.* Neither does it depend on the menstrual flow ceasing early or late, nor on women being single or married, rich or poor, but on a peculiar susceptibility of the nervous system—a condition which, though hidden from the microscope, is evident from the manner in which it responds to the reproductive and all other stimuli. Women who suffered much at the change of life had often suffered much at puberty and at menstrual periods; while these had seldom been attended with distressing symptoms in women who suffered moderately at cessation; and amongst the thirty-nine cases where there was no suffering, there was a similar immunity at puberty and the menstrual epochs. I, therefore, conclude that the diseases of the change

of life, like those of puberty, are principally to be ascribed to the nervous system being unable to tolerate the stimulus imparted to it by the reproductive organs, for when the nervous system is well-tempered, this stimulus acts as an improver instead of a disturber of health. Vital acts, however, are never found cut and squared with mathematical precision; there are, therefore, exceptions to this rule, and I have had patients who suffered much at cessation, whose previous good health had been uninterrupted. These remarks are a fit introduction to what I have to say respecting the theory of the production of diseases at the change of life; for of what use is a long enumeration of medical facts unless it lead to a sound theory, explaining their production and preventing their occurrence? Stones only cumber the ground till the architect puts them in place.

Blood Theory.—The more abundant quantity of blood, or its defective qualities, will account for congestions of organs, for hemorrhages, and for other flows, and for thirty-two years the womb is a powerful centre of attraction, causing it once a month to be the focus of blood-currents from all parts of the body. A strong mental or pathological perturbation sometimes so divides the blood-currents, that while a portion is directed to the womb, the rest is sent into some weak organ, which becomes congested, if unable to throw the blood off from its surface. The same occurs during the change of life. Part of the blood is still every month directed towards the womb, which is thereby congested, while disease may be induced by the monthly current setting in towards a weak organ. After three or four ounces of blood have been retained for a few months, plethora may be induced, if the nutritive force is unable to use the blood to strengthen the interior framework, or to produce fat. Plethora once induced, the system is oppressed and rebels; and if constitutional strength be equal to the task, it throws off the blood, but if strength be below par, the blood stagnates in congested tissues.

Nerve Theory.—It is, however, unreasonable to attribute to plethora most of the cerebro-spinal and ganglionic affections of the change of life. Thus formerly, when women suffered from headache, giddiness, drowsiness, and dulness of intellect, they

used to be bled, cupped, or leeched; but though this nervous condition, which I call pseudo-narcotism, may coexist with plethora, it is not proportionate to it, and may often be found in women who have become chlorotic at cessation, as well as in those whose amount of blood is well apportioned to the wants of the system. To explain, therefore, the occurrence of all the diseases of the change of life, it is necessary to take into consideration the morbid condition of the ganglionic nervous system during the first and second parts of this period. The condition of the ganglionic system cannot be materially altered without inducing cerebral disturbance, which must be admitted before the diseases of women can be understood. In searching how it is that ovarian disturbance induces morbid action, its effects on the female economy should be studied, not only in the menstrual phenomena, but also in the continuous action of the ovaries on the system. The results of this influence, when morbidly exerted, are often evident long before the menstrual flow, and long after cessation. When a girl of ten years of age is, more or less, in a constant state of pseudo-narcotism, without any sign of the well-recognized forms of cerebral or gastric disease, the premature morbid influence of the ovaries on the cerebral system is manifest, and Landouzy has rightly submitted that the ovaries may also produce hysteria, long before the appearance of the first menstrual flow or the comprehension of sexual ideas. I have seen girls affected with pseudo-narcotism eight years previous to first menstruation, and women to suffer severely from it ten years after cessation. When, therefore, I do not find it explained at the change of life, by gastric, hepatic, or well-known cerebral disease, I consider it indicative of perverted ganglionic influence, the most frequent result of disturbed ovarian action, not only at puberty and cessation, but at each menstrual period and during pregnancy and lactation. This perversion of ganglionic nervous power at the change of life is the result of increased ovarian irritability during the subsidence of specific ovarian functions. In many women, the excessive ovarian irritability, made evident by so many symptoms, reacts on the pelvic ganglia, and thereby on the ganglionic nervous centre. In many, ovarian life is not extinguished, and the ovarian and

uterine ganglia are not condemned to inaction, without the abdominal federation of ganglia and plexus, feeling more or less paralyzed by the want of that specific influence which had ruled the system for thirty-two years. Then occur irregular manifestations of nervous energy and the ataxic nervous symptoms, which Sydenham dilates on, when treating of hysteria. Then occur all sorts of erratic nervous pains, as well as the anomalous symptoms referred to the pit of the stomach, and the cerebral disorders of which I shall fully treat.

I have stated, that out of 383 women in whom the menstrual flow had ceased, 223 suffered much, 121 little, and 39 not at all; yet I do not consider that the proportion of 39 to 383, or ten per cent., gives a fair idea of the manner in which the change of life tells upon women, for the non-sufferers having nothing to complain of, seldom come under medical notice. The most frequent forms of disease at the change of life may be gathered from the following table; but the reader will bear in mind that I have been consulted in many unusually severe cases, on account of my being known to have given particular attention to the subject.

TABLE XXIII.

Nature of the Affections of 500 *Women at the change of Life.*

Nature of Disorder.	Number of Cases.
Diseases of ganglionic system, ...	406
Diseases of the cerebro-spinal system, ...	1272
Diseases of nerves, ...	487
Diseases of the reproductive organs, ...	463
Gastro-intestinal affections, ...	354
Cutaneous affections, ...	705
Various affections, ...	43
Total, ...	3730

Each of these divisions will form the subject of a separate chapter, and if the aggregate of suffering puts on a formidable appearance, the reader must bear in mind that in this table, flushing, perspiration, and other slight symptoms count as well as cancer, and that many women were suffering at the same time in many and various ways.

CHAPTER IV.

PRINCIPLES OF TREATMENT AT THE CHANGE OF LIFE.

THE natural history of the reproductive function has enabled me to state in the preceding chapters what complaints are to be expected at the change of life, and will also point out the principles that should govern their treatment.

If nature bled, in different ways, 208 women out of 500, it evidently shows that this spontaneous effort of a hidden force to relieve the system may deserve imitation. If 326 out of 500 suffered from sinking at the pit of the stomach, from fainting, debility, and chlorosis, it shows that stimulants and strengthening treatment must be as indispensable at the change of life as at puberty. If 75 out of 500 had frequent diarrhœa or constipation at this period, it shows that purgatives may often be of great service. If 285 out of 500 had unusual perspirations or sweating, it is a positive proof of the utility of sudorifics at this epoch. If 134 out of 500 suffered continually from biliousness, jaundice, waterbrash, vomiting, and dyspepsia, it is clear that alkalies will be often useful. If in 277 out of 500 the nervous system was actually steeped in a more or less intense state of stupor, it suggests the great utility of sedatives. If, in many, the organ most prone to disease through life suffered most at this period, does it not show the necessity of discovering this weak organ from the patient's previous history, so as to give it protection? If some form of disease of the reproductive organs frequently prevents the change of life taking place after the healthy pattern that I have described, does this not explain that the cure of any such disease is the first step to the recovery of health at the change of life? In all cases the main indications are: 1. To cure local disease. 2. To restrain abnormal dis-

charges. 3. To correct inordinate or irregular nervous action. 4. To strengthen the patient's constitution.

In exhibiting remedies at this period, it is necessary to guard against a prejudice firmly rooted in the minds of many, that the change of life is synonymous with old age, for the principles of treatment applicable to diseases of old age will not always suit those of the change of life. Then, as at puberty, there may be vital energy, but latent and oppressed, so that bleeding and lowering measures sometimes develop an unexpected amount of strength. I thoroughly believe in the efficacy of the modes of treatment thus suggested by the study of natural phenomena, and many cases recorded in this work will show, how, by following the suggestions of nature, I have been able, in a few days, to relieve patients who had been suffering for years. With the exception of those afflicted with cancer or structural diseases, there are few incurable cases, though many, satisfied with a first instalment of recovered health, will not allow a perfect recovery to be made. They would rather bear their accustomed evils than submit to the tedium of following out a systematic plan; they oppose the stubbornness of prejudice to advice founded on fully proved facts, and then talk of the "deplorable inefficacy of medicine," when, in fact, *they will not take the trouble to be cured.*

Bleeding.—The *natural history* of menstruation informs me that at its cessation, nature has sought relief by hemorrhages from different parts of the body in 208 women out of 500. As they are often benefited by the loss of blood, the natural process is evidently worthy of imitation, and it has been extensively copied by illustrious medical men of former times, and by Tissot, Hufeland, and Meissner; nevertheless so little does present practice imitate nature, that only five of my 500 patients have been bled, and ten cupped. Fothergill and Heberden thought that sudden deaths had greatly increased in England since bleeding, at the spring and fall, had gone out of fashion; and whatever may be the truth of this assertion, I am convinced that the sufferings of some women are aggravated from bleeding being so seldom resorted to; notwithstanding its being commended by the facility of

understanding that the well-timed subtraction of a small quantity of blood from women accustomed for more than thirty-two years to bleed periodically, is the best means of preventing or curing some of the diseases originating in the cessation of menstruation, until the blood can be safely disposed of. Bleeding went out of fashion, because the profession was vividly impressed with the recollection of the excesses to which, at different times, it has been carried, and I shall not discuss the question in its general bearings, as I have done so in my "Handbook of Uterine Therapeutics." I will merely remark, that lately, venesection in well-defined cases has been advocated by good pathologists, like Dr. Handfield Jones and Dr. Richardson. To those who still retain a horror of this remedy, I will only observe that, supposing the constitution of *man* has so changed from what it was, that it be now damaged by taking from him ten or twelve ounces of blood, when a prey to acute disease, I can answer for *woman* often bearing with benefit very large losses of blood; and as a redundancy of blood, of which nature has not yet found means of disposing, is a cause of disease at cessation, it follows that bleeding, so often effected by nature, at this period of life, should not be neglected by those who pride themselves on understanding and on imitating her proceedings.

Plethora sometimes exists with apparent weakness, which may be relieved by bleeding; so that in seeking to determine the utility of this measure, it is well to be guided by the state of pulse at the temples and at the heart, as well as at the radial artery, bearing in mind that, should there be much emaciation, the temporal and radial arteries would be brought nearer to the surface, and give a first impression of vigor where none exists. While the effects of bleeding are admirable in many patients of a plethoric type, they would be very detrimental to those who are chlorotic and nervous.

Characteristic nervous symptoms of the change of life are headache, giddiness, heaviness, and drowsiness. I have drawn attention to these symptoms as of frequent occurrence at puberty, during pregnancy and lactation; and I find that whatever may be the period of their supervention, they are often considered indicative of a determination of blood to the

head. The same symptoms, with headache and giddiness, have been lately considered as indications for bleeding by Columbat and Auber; and though in England similar mistakes are prevented because nobody bleeds, yet the fashion will change again ere long, and then will occur the danger of mistaking functional cerebral disease for plethora. The following cases will, to a certain extent, exemplify the discrimination required to treat patients suffering under similar symptoms:

Case 10.—In 1844, the rage for bleeding, again developed in France by the passionate advocacy of Broussais, had subsided in Paris; but it was still possible to test the ill effects of this pernicious system. About that time I was consulted by a lady, aged fifty-one, tall, thin, with a pallid complexion, dark hair and eyes. She had first menstruated at fifteen; the function had never been interrupted except by three pregnancies; it subsided gradually, and cessation occurred at the age of forty-eight. For some months she felt no inconvenience, but afterwards she was much troubled by headache, giddiness, flushes, and perspirations. An eminent French physician, ordered her to be bled to ten ounces; a slight improvement followed, but the same symptoms soon returned, which were again interpreted as signs of plethora, and other ten ounces were taken from the arm. This second bleeding made the patient worse; and when I saw her, the marked ill effects of the treatment were very evident, so I gave anodynes, mild purgatives, wine, and a more strengthening diet. The patient rapidly improved, and in subsequent relapses derived benefit from the same kind of treatment.

Case 11.—In 1850, I was consulted by a lady, aged fifty-three, of middle stature, sanguine complexion, brown hair, and hazel eyes. She menstruated abundantly for the first time in her thirteenth year, and she had since been regular, the discharge being usually abundant. While the function was ceasing, she was twice seized with flooding, and was much better for it. Menstruation ceased at fifty-one, and was soon followed by diarrhœa, which came on at irregular intervals, but did not interfere with appetite and strength. When that supplementary discharge subsided, heaviness of

the head, with giddiness, came on, together with flushes of heat and drenching perspirations. For these distressing symptoms she had consulted several medical men, and had taken quinine, acetate of lead, and gallic acid, but without benefit. I ordered her to be bled to twelve ounces, and the vertigo, flushes, and perspirations abated considerably. The bowels were kept open by Seidlitz powders; several glasses of effervescing lemonade were taken in the course of the day, and a tepid bath, for an hour, every week. Meat once a day, no beer nor porter, one glass of sherry at dinner, and increased exercise in the open air. In a month all the painful symptoms had disappeared, and the patient remained well for several subsequent months, when, without any apparent cause, the same symptoms broke out again. I ordered six ounces of blood to be withdrawn, and prescribed the former treatment, with similar good effect.

The symptoms experienced by both these patients were similar, but their constitutions were very different. The first shows that, when nervous people are bled to excess, there arises a state which often closely resembles the threatenings of disease in the vital organs, relieved in other temperaments by bleeding. In the last case the patient was of a strong constitution, accustomed to lose considerable quantities of blood, and relieved by the occurrence. The vigor of the circulation was well proved, by the strong impulse of both heart and pulse, instead of the flaccid condition of both in the first patient. The one was relieved by sedatives and a strengthening diet, the other principally by bleeding; and I have seen bleeding remove these symptoms when it was not indicated by a strong constitution, but by the previously-contracted habit of losing a considerable quantity of blood; as in women of a slender make and slight delicate appearance, and in those whose nervous susceptibility is great, in whom we must admit a tendency to hemorrhage.

At first, sufficient blood should be taken away from a plethoric woman to make a decided impression on the system, for nature frequently adopts this plan, insomuch that 138 women out of 500 were flooded at the change of life; but when the indication to bleed recurs, it is better to bleed in

progressively smaller quantities, and at progressively longer intervals. Tissot mentions a case, in which he thought right to bleed for three years, after which the patient recovered her health. Hufeland used to bleed three times in the first year after cessation, twice in the second year, and once in the third. I sometimes follow a somewhat similar plan, which is a daguerreotype of a natural process, for in 171 women out of 500, the menstrual flow ceased naturally, that is, by a gradually smaller amount of discharge, occurring irregularly every two, three, four, five, or six months. In 53 cases out of my 500, there was a marked return of monthly phenomena after cessation. In such cases it would be judicious to bleed before the accustomed monthly occurrence.

The effects of the bleeding should be aided by judicious regimen; for, doubtless, the necessity for bleeding, even plethoric women, would be considerably diminished, if it were not so difficult to persuade them to break through accustomed habits, and if they would consent, for a time, to diminish the quantity of their food, and refrain from what may be otherwise prejudicial in their mode of life.

Local Depletion.—When prejudice interferes with bleeding, a few leeches behind each ear, or cupping at the nape of the neck or between the shoulders, may be resorted to. If piles have formerly had a tendency to bleed, leeches may be applied to the anus; they will also be sometimes useful if there be habitual congestion or inflammation of the womb, though I was surprised to find Dr. Ashwell advocate bleeding the womb by leeches as the best mode of depletion at the change of life, for leeches are generally applied to the womb so as to determine blood to that organ; and to apply them at this period, except under peculiar circumstances, would be likely to prolong what nature wants to curtail. To check the determination of blood to the womb is clearly indicated at the change of life; and even in cases of uterine inflammation I seldom apply leeches, for I find that repeated small general bleedings are more effectual in checking that monthly turgescence of the womb which may take place long after cessation.

Purgatives.—Diarrhœa relieved fifty-two out of 500 women at the change of life. These bear witness to the utility of

purgatives, as well as the thirty-seven who were subject to dyspepsia, the twenty-three who were troubled with obstinate constipation, the fifty-five in whom biliousness was a prominent ailment, and the six who had jaundice once or more frequently. The utility of purgatives at cessation is further shown by the very intimate sympathy which I have proved* to exist between the generative and intestinal canals, and which is indicated by the relaxation of bowels which generally attends the menstrual flow. Purgatives constitute one of the most convenient local depletions by which the system can be habitually relieved; their employment, therefore, at the ménopause, fully deserves the confidence which the profession has long accorded to the practice, and the sanction which Fothergill has given to it; indeed the utility of purgatives has become so much a matter of popular, as well as of medical belief, that both patient and medical attendant too often confide in these alone, to the neglect of other important means. I might give numerous cases in proof of the utility of diarrhœa, but I will merely state the following.

Case 12.—Catharine M., aged fifty-three, tall, thin, and pale, menstruated very abundantly at fifteen years of age, was regular from the first, and continued so for three or four days every three or four weeks, with so little suffering that "she never felt them come nor go." She married at thirty-three, miscarried three times, and bore five children, the last at forty-seven; and menstruation, which had been irregular a year previous to conception, never returned after that event. The patient was generally relaxed during the menstrual epochs. During her last pregnancy, and after her confinement, she frequently had three or four stools a day, without pain or loss of appetite, and since then, diarrhœa came on every three or four weeks, with flushes and drenching perspirations. For the last twelve months she was relieved six or seven times a day, until lately, when this had only occurred once in two days, and she has suffered much from heat, flatus, nausea, oppression at the pit of the stomach, and want of appetite; her

* "On Uterine and Ovarian Inflammation, and on Diseases of Menstruation." 8d edition.

tongue being always clean and healthy. When the action of the bowels became freer, the patient got well.

When diarrhœa occurs at the change of life, it is generally at irregular intervals; it may, however, appear with the regularity of the menstrual function, as in the instance of a lady, forty-five years of age, in whom, at the accustomed time, diarrhœa came on when the menstrual flow was due. The diarrhœa lasted three days, and gave relief, although it was not followed by the menstrual flow, which never returned, and was thus replaced by the recurrence of diarrhœa every month for a year, and with great benefit to the patient. I have known the cessation of menstruation to have been followed for five years by an habitual looseness of bowels, occurring two or three times a day, generally without colics. The patient enjoyed good health during that time, and is now a stout and tolerably healthy woman. Dr. Day notices the salutary effects of diarrhœa, consisting of watery evacuations, taking place without apparent cause every three or four months after the cessation of menstruation; and he mentions the case of a lady, eighty-seven years of age, in whom this had happened with great advantage for the last thirty years. Instead of giving drastics it is more prudent to prescribe the frequent use of the milder opening medicines, which may diminish by degrees abdominal plethora, the more so as it may be many months before the constitution can settle down. The cooling saline purgatives serve this purpose, such as the soluble cream of tartar, cream of tartar lemonade, citrate of magnesia, Seidlitz powders, artificial Cheltenham salts, or Epsom salts in small quantities, Pullna and Friedrichshall water, a wineglassful being taken on rising from bed. I occasionally prescribe the soap and Barbadoes aloes pill of the British Pharmacopœia, ordering five or ten grains to be taken with the first mouthful of food at dinner.

Sulphur is generally classed amongst purgative remedies, because such is its visible action; but it owes its chief value, in diseases of cessation, to another action, much more difficult to understand, and which has long rendered it so valuable, both in hemorrhoidal affections, where there is an undue activity of the intestinal capillaries, and in skin diseases,

morbid phenomena that may be expected at the change of life. Sometimes I administer the flower of sulphur alone, or else to each ounce of it I add four drachms of calcined magnesia; at others, I prescribe equal parts of borax and sulphur, one to two scruples of these powders to be taken at night in a little milk, which generally acts mildly: and such combinations are very valuable when a continued action is required. Thus taken in small quantities, and now and then left off, I have not heard sulphur objected to by patients on account of its determining any peculiar smell. A remedy called the Chelsea Pensioner, of which Dr. Paris has given the following formula, agrees well with some. Of guaiacum resin, one drachm; of powdered rhubarb, two drachms; of cream of tartar and of flower of sulphur, an ounce of each; one nutmeg finely powdered, and the whole made into an electuary with one pound of clarified honey: a large spoonful to be taken at night.

ALKALIES AND DIURETICS.—In healthy women, the monthly ovarian crisis generally produces *critical* deposits in the urine, for most women remark their water to be "muddy" a day or two before or during the menstrual flow. During the dodging time and after cessation, this turbid state was noticed in forty-nine out of my 500 cases, to last for weeks, to disappear and to return again. This is sufficient to indicate the utility of alkaline preparations; their utility will be likewise apparent in the thirty-seven cases of dyspepsia, the thirty-one of vomiting, the five of waterbrash, the fifty-five of biliousness, and the six of jaundice. Dr. Parkes has shown that the action of liquor potassæ on healthy subjects varies, according to whether it be taken before or after meals. If taken after meals, the liquor potassæ acts as an antacid. It combines with the hydrochloric or lactic acid, and passes into the circulation without increasing the water, the solids, or the sulphuric acid of the urine, improving digestion and also the state of the blood. If, on the contrary, liquor potassæ be taken before meals, it has the power of reducing *embonpoint*. From thirty to ninety minutes after the liquor potassæ has entered the circulation, there is an increased flow of slightly acid urine, which contains the whole of the potash and organic matter, and a relatively large proportion of sulphuric acid. In other words,

an albuminous compound either in the blood itself or in the textures becomes oxidized; its sulphur, under the form of sulphuric acid, unites with the potash, and possibly with the changed protein compound, and is eliminated by the kidneys. The amount of albumen or fibrin thus destroyed by a few doses of liquor potassæ is doubtless small, but as the remedy can be taken for a considerable time, and its oxidizing effects can be assisted by exercise and by copious draughts of water, there is a possibility of removing superfluous matter from a patient without risk. At all events some women who became very stout after cessation, and who derived little benefit from measures advised to relieve the sweats and nervous symptoms of this period, rapidly improved, when, by large doses of liquor potassæ, they had been disencumbered of a superabundant amount of fat.

Dr. Shearman has drawn attention to the fact of the urine being saccharine in some of the forms of ganglionic disease, to be treated of hereafter, and which he considers dependent on neuralgia of the vagus nerve, and he places as much confidence as I do in alkalies, for he gives 3j doses of liquor potassæ to determine an alkaline condition of the blood, to reduce the sugar in the urine, and bring it back to its normal state of acidity. In many diseases of cessation, alkaline medicines are required as antacids and blood improvers; and I frequently order a tablespoonful of a six oz. mixture, containing, amongst other ingredients, two drachms of liquor potassæ, to be taken half an hour after meals. Unless there be much flatulence, or the weather be cold, an effervescing draught is a convenient way of giving alkalies; and borax, acetate of potash, and nitrate of potash may be added when the object is to act on the kidneys.

Mineral Acids.—The frequent occurrence, at the change of life, of dyspepsia, biliary derangement, and debility, makes it often desirable to give mineral acids, and I prescribe thirty drops of the diluted nitro-muriatic acid in distilled water or other vehicle; and sulphuric acid is useful whenever the functions of the skin are disturbed.

SEDATIVES.—The 227 women out of 500 who suffered from pseudo-narcotism, the 226 who were troubled with dorsal

pains, the 205 distressed by hypogastric pains, the 208 subject to headaches, the 146 presenting the minor forms of hysteria, the 49 distressed by epigastric pains, the 16 in whom insanity occurred, and many others who suffered from less frequent nervous affections, are all witnesses to the efficacy of sedative medicines, in relieving the many forms of nervousness unavoidable at the change of life. The utility to be derived from sedatives in diseases of old age has been so admirably pointed out by one who has thrown considerable light on their difficult study, that I avail myself of Sir H. Holland's remarks, which apply forcibly to diseases of the change of life.

"The manner of employing opium in modern practice might, until very lately, be cited among the many examples of perverse changes of fashion as to particular remedies and methods of treatment. The fear of confining the bowels and checking the secretions, constantly present to the mind of the practitioner, readily imbued the patient with the same alarm; and thus far prevented the adequate use of a medicine having power of mitigating pain, of relieving spasm, of procuring sleep, of producing perspiration, and occasionally even of aiding the natural action of the bowels, by obviating the disordered actions which interfere with it. I speak of this as having been, because it is certain that opiates are again more largely employed, since the introduction of morphia as a common preparation has furnished new methods of administering the remedy, and revived attention to the principles of its action. Yet even now it may be affirmed that there exists a distrust, both as to the frequency and extent of its use, not warranted by facts, and injurious in various ways to our success in the treatment of disease. This is the more singular, seeing the boldness of our practice in other points, that we have in the sleep produced a sort of limit and safeguard to its effects, and that we possess remedies of easy application for all injurious symptoms that can arise. To the insufficiency, indeed, of the quantities given, may be attributed, in some part the comparative disregard into which the remedy fell during a certain period. Half a dose might disturb and distress the night which a full dose would have made one of

perfect rest, or perplex the aspect of symptoms which a larger quantity would have alleviated or removed.

"Yet medical experience does but follow common observation in recognizing the inestimable value of sleep in sickness, of the suspension of pain, and the check to all disordered actions thereby obtained. For pain and sleeplessness, though strictly but symptoms of other ailments, may often, in practice, be viewed as disorders in themselves, the removal of which is essential to the success of our general treatment. How frequently do we see a nervous restlessness come over the patient, the consequence of protracted sickness or other causes, retarding cure by preventing the due effect of remedies, and receiving no relief itself from the means employed for the disease. In such cases, the physician is not to submit himself to names or technicalities. The regular course of treatment must be suspended until the hindrance is removed; and even seeming contradictions to this course may safely be admitted for the attainment of the object. Here opium is the most certain and powerful of the aids we possess; and its use is not to be measured timidly by tables of doses, but by fulfilment of the purpose for which it is given. A repetition of small quantities will often fail, which, concentrated into a single dose, would safely effect all we require."

These remarks are in every way applicable to diseases of the change of life; for sedatives, by assuaging the acuteness of pain, lull excited action to a slower rate of progress, and to a more subdued tone, for the bloodvessels serve under the vaso-motor nerves; and sedatives, by restraining the heart's action, diminish the momentum of the blood. Moreover the principal source of cerebral disturbance at the change of life is, that irregular stimulus of the reproductive organs, which are no longer relieved by the menstrual flow; indeed some of my patients have been driven to the verge of insanity by ovario-uterine irritation; and in proportion as this was assuaged by the systematic exhibition of sedatives, cerebral disturbance abated. Those most benefited by sedatives are the nervous and chlorotic, in whom there is often action without power—action requiring to be restrained until the system has gathered strength; and as the tolerance for a remedy is

generally in direct proportion to the possibility of its being required, it will be found that the thin, weak, and nervous are most sensitive to the action of sedatives, and can be brought to tolerate the largest doses. Those of the plethoric type bear the solanaceous sedatives better than opium, unless this be given with ipecacuanha and purgatives; and calomel or blue pill should be combined with the sedatives when the liver is out of order. It stands to reason that at the ménopause sedatives may be administered by the mouth, by means of hypodermic injections, and by topical application to the disturbing seat of morbid action. Opium and belladonna plasters, and, better still, those made by incorporating morphia and atropia with glycerine ointment, according to the method explained in my "Handbook of Uterine Therapeutics," are singularly useful to quell the epigastric pains that women suffer from so much, and which play so important a part in the nervous affections of women. The precept of applying the sedative as near as possible to the suffering nerves explains the speedy and beneficial results that often follow the exhibition of suppositories or medicated injections, by the vagina or the rectum, when the reproductive organs are diseased. Even in cases where there are no abdominal or lumbar pains, I sometimes order sedatives by the rectum, with the greatest benefit. In some cases of nervous irritability, where there is a great tendency to headache, delirium, pseudo-narcotism, or any state approximating to insanity, they are most useful; for at the change of life all those distressing conditions of the mind do not depend upon idiopathic cerebral disease, but on the perverse reaction, on the brain, of some anomalous ovarian influence transmitted through the ganglionic nerves, and by assuaging the pain, irritation, and undue influence of the reproductive organs, sedatives, thus given, allay the disturbed action of the ganglionic nerves, and thereby cure cerebral affections.

With regard to the special indications for sedatives, to avoid repetitions, I shall refer the reader to the following chapters, in which the treatment of each disease is given, and to my "Handbook of Uterine Therapeutics and of Diseases

of Women." I will not, however, dismiss the subject of sedatives without a general survey of their relative value.

To relieve the slighter forms of cerebral and ganglionic disturbance there is nothing like henbane, for it is almost always more or less effectual, and produces no untoward effects, even if continued for a long time. I have less experience of conium, but believe it to be almost as useful. Indian hemp, when it agrees, and it often does, has the great advantage of not producing constipation or heating the system. Belladonna and atropia act admirably in suppositories or plasters, but I rarely give them by the mouth. Concerning the utility of opium and its numerous components I cannot speak too highly, whether as a topical agent or as the means of influencing the whole system. I first try Dover's powder, and then morphia, beginning of course with small doses, and much as I deprecate its continued use in large doses, I have not hesitated to sanction the daily taking of two and three grains of acetate of morphia, for several years, when I found that nothing else could quell sickness, diminish ovario-uterine pain, cure hysteria, and render bearable an existence otherwise intolerable. Such cases are very rare, but they must be allowed the benefit of the habitual use of exceptionally large doses of morphia.

Hydrocyanic acid in large doses is only suitable when strength is above par, but in small doses I occasionally find it to be better borne than other sedatives by nervous women. Although Dr. Physick exaggerates when he says that "camphor was made for women, with whom it always agrees, while it always disagrees with men," it is a very valuable remedy. The subtle fumes seem to spread like an aura over the nervous system, stimulating it to increased action, causing the capillaries to eliminate with the perspiration whatever oppressed the nerves, whether it be a liquid, gaseous, or an electroid fluid with which they were overcharged. The effect of this is a subsidence of pain, an increase of strength, and sometimes a sensation of lightness. Camphor seems to correct the toxic influence which the reproductive system has on the brain of some women, and its anaphrodisiac properties have been often shown in priapism and nymphomania. It abates the sexual sting by acting on the cerebro-spinal nerves of the external

organs of generation, not on the testicle or ovary. The testimony of Raspail on this point is of great value, and he says, that habitual large doses did not prevent conception nor induce impotence. Camphor may therefore be useful in appeasing the excitement of the organs of generation at the change of life, if it be given in sufficiently large doses. Lupulin has likewise a strong anaphrodisiac action. Castor, ambergris, musk, and sumbul are nervine stimulants that are often useful, castor being the one I most frequently give, and I find it is the principal ingredient of Crollius's Uterine Elixir. Chloral will, I believe, be invaluable in nervous diseases of women; its uniform action, without causing constipation, or nausea, or depression, recommends its adoption. In some cases of perverted cerebral innervation the inhalation of chloroform, or of a mixture of chloroform and ether, may be usefully carried to the verge of unconsciousness. I cannot dismiss this subject without repeating a hope expressed in successive editions, that sedatives may be more systematically used at the change of life than is now the case, so as to enable women to withstand the over-exciting effects of the present civilization on the nervous system, and to deaden the reproductive stimulus, which only lingers on to disturb health.

SUDORIFICS.—In some countries the polite question on meeting a friend is not, "How do you do?" but "How do you perspire?" This might apply to women at the change of life, for the 201 out of 500 who had continual perspirations, and the eighty-four who were for a long time repeatedly sweated, show the utility of sudorifics. Indeed, for one woman who is for a time relieved by a critical exhalation of blood from the womb, twenty, or more, derive permanent benefit from long-continued critical cutaneous exhalation, so I wonder that the utility of perspiration, and the advantages to be derived from sudorifics, have not been more insisted on, especially as their action is exerted on an immense surface, and followed by the exhalation of a large quantity of water, salts, and animal matter. That the perspirations of this period have not passed quite unnoticed is evident from Siebold mentioning a case of sudden cessation, followed by abundant perspiration. Tissot also alludes to the fact, that when intermittents were frequent,

he sometimes saw menstruation finish by an intermittent fever, which, by greatly augmenting the perspirations, relieved the patient of the other infirmities which so often attend this critical change. For proof of the utility of perspirations in many affections at the change of life, I refer to many cases in this work. Siebold's case reminds me of one in which the menstrual flow left suddenly at forty; since then she never suffered, but had constant and gentle perspirations up to the fifty-fifth year of her age. Eliza S., aged fifty-two, lost the menstrual flow suddenly at forty-two, after venesection during a menstrual period; since then she has had constant gentle perspiration, but no suffering. On the other hand, whenever women suffer more than usual from distressing sensations referred to the pit of the stomach, and from a considerable amount of cerebral disturbance, it will frequently be ascertained that the skin is habitually dry. There are "dry flushes," in which the skin is not relieved by perspiration. In such cases, profuse perspiration, whether an effort of nature or the effect of medicine, brings speedy relief. To induce perspiration, I sometimes begin with an emetic; more frequently a tablespoonful of acetate of ammonia given repeatedly, the patient being in bed, is useful: when there is no tendency to cerebral congestion, I have given vapor baths, though I generally prefer the more permanent gentle perspiration brought on by a cooling regimen, by warm baths and sulphur, of which I give one or two scruples once or twice a day.

Baths.—The 287 women who suffered much from repeated flushes, the eighty-four who were habitually sweated, and the forty-two who presented various cutaneous affections, bear witness to the utility of baths. A warm bath is a very simple thing, but it acts in many ways: 1. It removes from the skin the saline deposits and other secretions left there by continued perspiration. 2. The veins of the skin absorb a certain amount of water, which allays cutaneous irritation and dilutes the blood. 3. The warm bath is a gigantic poultice, applying its warmth to all the peripheric expansions of the nervous system. In some hidden way the warm bath is a positive corrective of nervous irritability, and a sedative to the nervous system; and when it is considered that this gigantic poultice is perfectly

manageable; that the temperature may be increased or lowered according to the patient's feelings and the practitioner's discrimination; that while the patient is in warm or tepid water, cold applications may be made to the head, and a stream of cold water directed to the abdomen through a vulcanized India-rubber tube, so as to quell local congestion, it is not surprising that the greatest men have, at various times, vaunted the utility to be derived from baths in nervous affections, and that, lately, they have been revived in France for the treatment of mental diseases. As a general rule, I tell my patients to take a warm bath every week, and to stop in the water for an hour.

The prejudice against baths, except as a means of cleanliness, is so great in England that I am afraid of asking patients to do more, but when I wish to obtain the full sedative effects of baths, I direct highly nervous patients to take them, heated to about 93°, and to remain in one, two, or three hours, having warm water added at times, so as to maintain a grateful temperature. A greater sedative effect will be obtained by letting the water gradually cool down to 90°, or even lower, and the amount of water absorbed will be to a certain extent proportionate to the low temperature of the bath.

MINERAL WATERS.—Cold sea-bathing is out of the question at the change of life. I have not advised warm sea-baths, but several patients have tried them without deriving benefit, while others have thought themselves worse for their use. Gardanne states, that the effects of mineral waters are rather disadvantageous than otherwise; but he does not say how or where they are taken, and it stands to reason that if there be truth in what I have just stated respecting the value of sulphur, alkalies, purgatives, and steel, in the treatment of diseases at the change of life, these remedies must be likewise useful when combined in mineral waters to be taken internally or used as baths, the more so as these mineral agents exist in a state of combination with other substances so as to be inimitable by our chemistry. Besides this important consideration, the total freedom from domestic cares, the complete change of air; food, habits, and scenery, must enhance the value of mineral waters. Sulphurous waters may be good, not only in cutaneous affections, but in many

cases of congestion of the internal organs, and in anomalous ganglionic neuralgia, alkaline waters like Vichy or Ems, cannot be overrated in cases of obstinate biliousness, dyspepsia, vomiting, and gout. The saline waters of Homburg and Kissingen serve in cases of dyspepsia and obstinate constipation. Chalybeate waters, like Schwalbach and Tunbridge Wells, are useful in chronic debility, chlorosis, and in the after part of the treatment of many of the gastro-intestinal affections. Hot sulphurous baths, like those of Aix in Savoy or Harrogate, may be made serviceable in the cure of rheumatic affections, lumbo-abdominal neuralgia, local paralysis, paraplegia, and in most neuralgic affections. To whichever of these watering-places the patient may be told to proceed, she should never begin a course without consulting one of the resident medical men, who will be best able, by local knowledge, to advise her respecting the kind of mineral water to be taken, as well as the best mode of its administration in her case.

Issues.—I should not mention these if Dr. F. Churchill had not expressed his agreement with Fothergill, as regards the utility of applying issues and blisters to those who, in early life, have been relieved from cutaneous or other disorders by the establishment of the menstrual flow. He says, "I have repeatedly tried caustic issues, or perpetual blisters, and with the greatest advantage. They certainly aid the action of the remedies already mentioned, and, I think, prevent the recurrence of those irregular congestions which Dr. Fothergill has described." Gardanne and B. de Boismont likewise speak confidently on the utility of issues in preventing disease at the change of life, but I agree with Dr. Ashwell that they are seldom necessary, except when cutaneous eruptions are troublesome, and have been so in youth.

In perusing this work the reader will bear in mind that the 500 women of whom I have traced the varied modes of suffering at the change of life only constitute a minority when compared to those who pass through the change with little or no suffering. Well-regulated hygienic habits are all they require to assist the silent operation of natural laws, and I shall therefore treat of hygiene in the next chapter.

CHAPTER V.

PRINCIPLES OF HYGIENE OF THE CHANGE OF LIFE.

As at puberty, from the total ignorance in which it is still thought right to leave young women, so at the change of life, women often suffer, from ignorance of what is to occur, or from exaggerated notions of the perils that await them. It would be well if they were made to understand that, if in tolerable health, provided they will conform to judicious rules of hygiene, they have only blessings to expect from this critical period. The change of life may be dangerous for those who are always ailing, for habitual sufferers at the menstrual periods, and for those affected with uterine diseases; and according as the sufferings of women were protracted, previous to the healthy establishment of the periodical flow, so may they expect its cessation to be attended by a corresponding period and intensity of suffering. Women should know, that unless they be pregnant or nursing, great irregularities in the monthly appearance, or its prolonged absence, coinciding with sensations of sinking at the pit of the stomach, with flushes and perspirations—even though their age may only be between thirty and forty—may, in general, be considered as warnings of cessation, particularly if they are accompanied by a corresponding amount of pseudo-narcotism. This knowledge would prevent cessation being considered in the light of temporary suppression, and forcing medicines and purgatives being taken without the sanction of medical advice. If, on the first indication of the change of life, women who are in fair health sought advice, carefully followed a regimen, and pursued a line of life in harmony with the physiological processes on which this change depends, I believe that almost all disease would be prevented; but as it is the end

of a natural function, it is thought right to leave it to nature; no additional precautions are taken, and advice is sought for when the mischief is done. It is, then, well worth while to place on record the rules of hygiene best calculated to prevent and to cure the diseases of the change of life, referring these rules to the great functions of the human economy.

Hygiene of the Reproductive Organs.—I have shown that there is something more or less anomalous and morbid in the reproductive organs and their action on the system during the first half of the change of life, and that in the latter part of this period these organs have a tendency to become atrophied. Can there be a clearer indication that until after the ménopause, their hitherto appropriate stimulus interferes with a natural process? Hence it is unreasonable to marry during this unsettled period. Experience, moreover, teaches me, that even in those who have been long married, connection at the change of life is a cause of uterine disorders, and that these have frequently occurred in women marrying during this epoch. I admit with some physiologists, that, as a flickering flame gives a final blaze, so in some women, sexual desire is strongest when the reproductive power is about to be extinguished: this, however, is not the rule, for I have been repeatedly made aware that a distaste for connection was the first sign of an approaching change. I therefore believe a marked increase of sexual impulse at the change of life to be generally an anomalous if not a morbid impulse, depending upon either neuralgic or inflammatory affections of the genital organs, thus corroborating B. de Boismont's assertion, that "whenever sexual impulse is first felt at the change of life, some morbid ovario-uterine condition will be found to explain it in nineteen out of twenty cases." At all events, I deem it imprudent for women to marry at this epoch without having obtained the sanction of a medical adviser. If this had been done in cases that have come under my observation, flooding would not have followed marriage, slight uterine disease would not have been considerably aggravated, the march of undetected cancer would not have been hastened, and others would not have become insane, as in the following case:

CASE 13.—Mrs. B. was fifty-one when she consulted me; she had been all her life an intelligent, active, and determined woman, eccentric but not nervous; and when about fifty, and during the dodging time, she married. In the wedding night she had severe abdominal pain, and flooded to a great extent during the following days, and then her mind became affected, with occasional melancholy fits and suicidal tendencies. It was remarkable how her mind was infected with doubt; she could not make up her mind to anything, and was always doubting about right and wrong. When I first saw her she had not slept for a fortnight, and had sensations of burning in the breasts and the lower part of the abdomen, menstruation being irregular, scanty, and dark-colored. I gave morphia internally, ordered a succession of belladonna plasters to the pit of the stomach, effervescing draughts and warm baths. She got very much better in a fortnight, and was well in about six months, menstruation having ceased. This occurred in 1847, and since then there has been no return, notwithstanding the long illnesses and the deaths of her husband and mother.

The following case also shows how women sometimes seek to stay the inexorable hand of time by protracting the regular appearance of the sign of womanhood; but should they succeed in bringing on the flow, it arises from a diseased state of the womb, and can give no hope of progeny.

CASE 14.—Some years ago I was consulted by a lady, aged forty-eight, who, when about twenty-five, formed a strong attachment, but family circumstances prevented a union taking place, till fortune smiled upon the parties, and the lady married at forty-five. The discharge had proceeded regularly as to time, quantity and symptoms, up to the period of marriage, but subsequently it never reappeared. As this sudden cessation coincided with gastric symptoms, with a distension of the abdomen, and, above all, with a great anxiety for children, the patient was considered pregnant, and carefully watched for many months. When the illusion was destroyed, the lady became disconsolate; and, punctilious in her notions respecting honor, she brooded over the possibility of her husband supposing that the

courses had stopped previous to her marriage. After a minute investigation, I intimated my conviction that health was perfect, and that the monthly flow had ceased. About a year afterwards, I was asked to see her again, and learned that, having consulted some one else, she had taken steel, purgatives, and large doses of savine, until she had a terrific flooding. She subsequently had a continued sanguinoid discharge for several months, and other symptoms of inflammation of the body of the womb, which was most likely caused by injudicious treatment, as well as by marrying when the change was impending.

The preceding remarks are not uncalled for, since it appears from the Registrar-General's report, that in 1851, 982 spinsters and 2375 widows married from the forty-fifth to the fifty-fifth year. If 3357 English women, every year, do what seems to me injudicious, it is that human beings are not governed by physiological considerations, and that women marry to better themselves, or to show that they could have married before, if they had liked; while others, like besieged fortresses, surrender at last for the sake of quiet and peace. When menstruation is well over, there is no reason why women should not marry, although marriage will render them more liable than they would otherwise have been to vaginitis and the milder forms of cervical inflammation.

External irritation is susceptible of being greatly alleviated or cured by lotions of water, or of linseed tea, tepid or cold; ten to twenty grains of acetate of lead, in a pint of spring water, may also be used three times a day. Vaginal injections and enemata, with tepid or cold water, are beneficial in allaying irritation, and the following puff powder may be freely used after washing:

Camphor, carefully powdered, . . .	ʒvi.
Acetate of lead, ...	ʒi.
Starch, ...	ʒij.
Essential oil of bitter almonds, . . .	♏x.

The tepid bath at 92° to 95°, prolonged for an hour, once or twice a week, will be very useful. Repose will permit these measures to have their full effect, so it would be well to recline on the sofa for several hours in the course of the day.

Hygiene of the Digestive Functions.—Having shown that the debility often experienced at the change of life depends upon a shock felt by the nervous system, or upon the frame being oppressed by an overplus of blood of which there is no longer a monthly drain, it is rational that from the very first appearance of the irregularities which characterize this epoch, women should curtail, rather than augment, the amount of food and stimulants to which they have been accustomed. When in the family-way or nursing, or so long as the menstrual flow remains regular and abundant, many women can, without inconvenience, take meat three times a day, and beer and wine at both luncheon and dinner; but when the surplus blood, produced by high feeding, can neither be well employed nor regularly ejected, it increases all the sufferings of the change of life, and either prevents or diminishes the efficacy of remedial measures. I should be ashamed of insisting on anything so self-evident, if I were not often consulted by plethoric patients, to whom generous diet had been recommended to relieve the nervous symptoms of which they complained. Some had disregarded the advice because they found high living increased their suffering and their sleeplessness; whereas when living rather low they slept better and suffered less. To women of this type, do these observations apply, and their breakfast should consist of toast or bread and butter, with tea, coffee, or cocoa; they should take but *one* dinner in the day, at whatever hour may suit, but, should it be late, a slight luncheon of bread and butter, cake, or biscuits, with a glass of lemonade, ginger-beer, or soda water, may be taken. Their dinner should be a plain meal; fish, and white meats, such as fowl or veal, in preference to beef or mutton; more of the crust than the crumb of the bread, and jellies and ice in preference to puddings. If, on the contrary, all sorts of farinaceous food, pastry, and cakes, be indulged in, the natural consequence will be a desire to prolong sleep, a distaste for exercise, congestions, bleedings, inflammations, and apoplexy, or they will become distressingly stout. It would be better for both stout and thin to make their principal meal at the fashionable luncheon hour of two o'clock, in order that their last meal may be light, which can well be managed, even if the usages of society

should require a lady's presence at an eight o'clock dinner table.

Two or three cups of tea, with dry toast or bread and butter, may be taken if the dinner hour be early, and a cup of sago, arrowroot, or something equally light, for supper; but those who dine late should avoid suppers. Ripe fruits and vegetables may be indulged in, to any amount not interfering with digestion. While those who have a tendency to become fat require different food, sleep, and exercise to those who continue thin at cessation, both should beware of giving way to those sensations of internal sinking and exhaustion to which all are equally subject, and not to seek *too often* a comfort for languor, weakness, or nervousness, in wine, cordials, and spirits, by which a temporary support only can be obtained at the expense of an increase in the faintness, flushes, perspirations, and nervous symptoms.

The system requires soothing by medicines and regimen, rather than stimulating by spirits; and I have known instances of women who, by a misinterpretation of their sufferings, have gradually so increased their usual consumption of wine or brandy, as to induce habits of intoxication. One or two glasses of sherry, claret, or champagne, is an average allowance, either alone or combined with seltzer water; but some have been obliged to discontinue even this small quantity, on account of its affecting the head. Effervescing draughts, such as effervescing lemonade, ginger-beer, &c., are well indicated; coffee should be made weak or avoided, as it is decidedly more heating than tea, and tea should be used in moderation. Patients have prolonged their sufferings by ringing at every hour of the day for tea; for ten or twelve cups of strong tea in the twenty-four hours tell injuriously on the nervous system. Some women of the plethoric type would do well to abstain, for a time, not only from wine and coffee, but also from pepper and spices. Owing to an increase of fat in the omentum and lining of the abdominal walls, as well as to frequent flatulence, the abdomen often becomes very protuberant or pendulous, in which case a light, elastic abdominal belt gives great comfort.

When women are thin, weak, and semi-chlorotic they require more food and stimulants; but although they bear them with-

out inconvenience, or with positive benefit, they should seek advice, for such a state implies the want of medicine.

Hygiene of the Cutaneous Functions.—With a view of preserving health the bath should be used at least every week by those who are at the change of life, and more frequently by those who have profuse perspirations. The water should be sufficiently warm to impart a grateful sensation, from 92° to 94°, the patient remaining in it half an hour or an hour; and if there be any tendency to headache, the head should be sponged with cold water. A cosmetic bath may be made by taking two lbs. of barley, or bean flour, or meal, eight lbs. of bran, and a few handfuls of borage leaves, and boiling these ingredients in a sufficient quantity of water. This both cleans and softens the skin. Long-continued gentle friction of any painful part by a warm affectionate hand is often of great use. While watching in Eastern countries the long-continued and gentle rubbing of the limbs and soles of the feet of the rich by their attendants, I could not help thinking that the benefit might be less due to the mechanical friction than to some kind of influence on the nervous expansions with which the skin is so abundantly supplied. Rubbing until the skin glows, or the actual grooming of the human body, may be very useful to improve the health of scrofulous children, or chlorotic girls, but it is not adapted for women at this period of life. At cessation the vicarious functions of the skin are so important as to require its being covered as much as possible; and when there is a great tendency to perspiration, flannel should be worn immediately over the chemise, and over the nightdress in winter, when the patient perspires profusely in bed, otherwise she may be chilled by any change of posture.

Hygiene of the Muscular System.—Exercise is extremely useful at the change of life, for three reasons. 1st. It relieves the congestion of the internal organs, transferring the blood from them to the limbs, and if the late-hour exercises of civilized life are dangerous to all, particularly to the sanguine, gentle, regular, and long-continued exercise in the cool of the day is very beneficial. 2d. It has a depletive effect, causing the skin to perspire more, and the kidneys to excrete more urea. Dr. Leyman found that, by substituting violent

for moderate exercise, the relative quantity of urea in the urine varied from 32½ to 45½; and Mr. Simon found that after two hours' violent exercise, the quantity of urea in the urine passed afterwards, was double that contained in the morning urine. This may be one of the reasons why some plethoric patients derive benefit from exercise carried to a certain degree of fatigue, as recommended by Auber. 3d. Exercise acts by exhausting those redundant energies which, however little understood, when unemployed, produce the fidgets, nervousness, temper, hysteria—a sliding scale which so imperceptibly leads to more serious mental disorders that its successive stages pass unnoticed, until the unforeseen climax demands strict inquiry into the patient's previous state.

The observations relative to exercise apply more particularly to walking; driving in an open carriage is likewise good, but horse exercise should be left off till after cessation; indeed, its utility in favoring the menstrual flow sufficiently points to the discontinuance of the practice during the time preceding and following the change, for then it is likely to cause flooding, piles, and leucorrhœa. It will be obvious that the preceding remarks do not apply when the change is characterized by intense constitutional debility. Walking is often then an utter impossibility, and should only be gradually attempted, and riding is out of the question.

Hygiene of the Nervous System.—It cannot be too often repeated that nervousness, under every shade and type, may be anticipated at this period, and should be prevented by suiting the habits of life to the changes progressing. It is therefore sufficient to mention that the sufferings of this epoch will be increased by frequenting balls, routs, operas; for, in addition to the numerous excitements to be there encountered, hot and impure air must be breathed. The precepts already given bear indirectly on the abatement of nervousness; but I can show how susceptible the nervous system is to the danger of sudden bad news, or to any powerful impression, by taking my examples from the lower orders, whose nervous system is less excitable than that of their more favored sisters.

M. N. was well and regular up to fifty, when she went

to see a neighbor's child, who was severely burnt, and a dreadful flooding was the consequence. Hearing suddenly of the death of her husband brought on a severe flooding in S. L. In A. B. the menstrual flow suddenly stopped at forty-five, on her first acquiring the conviction that her husband was insane; and in several instances, has the news of the sudden death of a husband caused early and sudden cessation. Perhaps the most curious effect of the mind on the body, at this period, was lately published in a French journal. A highly nervous lady, aged forty-eight, had ceased to menstruate four years, when she attended a sister during a protracted and painful labor. A few hours after it was over, she was herself taken with similar pains, which produced flooding for several days. Three days after this ceased, the breasts swelled, and a milky fluid came from the nipples. B. de Boismont and others have likewise seen flooding, at cessation produced by strong emotion, or a sudden fit of anger.

Sleep should not be too freely indulged in by those who belong to the plethoric type; thin and nervous women, on the contrary, may be encouraged to take as much as nature will give them, even a siesta after meals may be allowed, as sleep is for them the best restorative, and an anti-spasmodic of heroic force. In obstinate sleeplessness depending upon nervous irritation, a warm bath, before bedtime, is often as serviceable at the change of life as in infancy. More than once, in cases of great insomnia, I have had the patient wrapped in cotton-wool, from head to foot, which gave comfort, warmth, and sound sleep.

With regard to the more serious mental disorders, which cannot be altogether separated from insanity, it will often devolve on the medical man to explain to the patient's relatives, that the system may be, for a time, unhinged; that harsh conduct would aggravate the already too distressing symptoms; and that it would be cruel to consider as confirmed insanity the strangeness of temper, the fitfulness of spirits, the perversion of character, which, after a few weeks or months of treatment, may considerably abate or entirely disappear. The temporary avoidance of those to whom an

aversion may be held, following the instinct of the patient so far as frequenting society is concerned, encouraging any inclination for particular occupations, are all points of great importance; for manual labor cuts off the heart from its too engrossing objects of delight, and if it is so useful, in cases of confirmed insanity, how much more so it must be to diminish the tendency to climacteric mental derangement.

Being able now, as years accumulate, to appeal to a large experience of the dangers that attend puberty and the change of life, I am at a loss to know which crisis most requires judicious management, or the intelligent sympathy of friends, and the habitual support of some stronger mind, in whom faith is placed. It is certainly surprising that a stout lady, in excellent bodily health, eating heartily, and taking half a bottle of wine a day, should be put out by trifles, be low-spirited and fretful on the slightest mental exertion, and be laid up with a severe attack of cerebral neuralgia if the exertion be persevered in; but such cases are not unfrequently met with, and they may last one, two, or more years, after which the patient gradually recovers her right tone of mind. Premature efforts to resume the usual active habits of life increase the frequency and severity of these attacks of cerebral neuralgia, and compromise the chance of ultimate recovery. I know a lady, of a good constitution, though somewhat nervous all through life, and who, just as menstruation was ceasing, lost a dear sister, and then a dearer husband. Her mental energy and power of action were completely prostrated, but as she continued to look well and eat heartily, those around her could not understand that she was unable to fulfil the duties of her station, and repeatedly urged her to exertion; although every fresh effort was followed by a breakdown. More frequent attacks of cerebral neuralgia made her silly for a time, and she never quite recovered her former healthy state of mind. Attention to the regular action of the bowels, a purgative every two or three weeks, mild sedatives, change and travelling, are the best means that I can devise to tide over the mental dangers of this period.

Travelling is a great strengthener of the nervous system, for it places the patient in entirely new circumstances, every one

of which makes a fresh call on her attention, solicits her interests, captivates her faculties, and completely leads her from trains of thought, to which she had been long enchained. In addition to this, the exercise of various kinds which is willingly taken gives increased vigor to the muscles of the body, and therefore to the brain itself; the mind is often consoled by the probability of recovering health by an agreeable residence at some watering-place; it feels under the guidance of medical authority, and resumes peace and tranquillity. Indeed, all that has been said in praise of baths, exercise, and the advantage of a light-hearted cultivation of the pleasures of nature, rather than of those of society, by women at the change of life, will clearly point out how their combination may be made serviceable for the cure and prevention of disease at this epoch. Those blessed with ample fortunes can easily avail themselves of this provision safely to get over this critical period, and remodel their constitution so that it may endure for many years, and I have elsewhere stated the great advantages that may be obtained from the judicious use of mineral waters.

Mental and Moral Hygiene.—I have already said that during the change of life, the nervous system is so unhinged that the management of the mental and moral faculties often taxes the ingenuity of the medical confidant. The study of the patient's character will teach him what occupation or pursuit is most likely to engross her mind, and effectually replace those of former times. If he be not prepared to take the part of divine, moralist, and philosopher, without ceasing to be a physician, his medicines will often be of little use. It cannot be wondered at, that the full conviction that age has stamped them with its first irrevocable seal, should cast a gloom over the imagination; but a well-trained mind will soon adapt itself to a new state, and take some comfort from the knowledge that this epoch proclaims an immunity from the perils of childbearing, and the tedious annoyances of a monthly restraint.

The natural good sense of many will show them how the notion that after this period little remains to console women for the anxieties and troubles of life, is a *pagan* idea, suited to the position allotted to women in Greece and Rome, where

they were seldom considered worth more than to amuse men and to bring forth children; a condition inapplicable to women after their social emancipation by the doctrines of Christianity. They should be shown that the importance of their position after the great change, may be inferred by the length of life allotted to them after its occurrence, and the singular immunity from disease which is generally observed after that period. They should be reminded that many intimate sources of pleasure are attached to every age, although it would be unfair to ask for one period the pleasures allotted to another.

"Qui n'a pas l'esprit de son âge,
De son âge a tout le malheur."

Besides this vast improvement in health, it must not be thought that the change of life implies the loss of all personal attractions. There is a beauty about childhood that seldom makes a vain appeal for fostering care; the beauty of youth fascinates; that of mature age excites admiration; but in many women there is for long after the change of life an autumnal majesty so blended with amiability, that it charms all who approach within its magic circle. To those fired with ambition, it may be safely said, that the home government of society, from the highest to the lowest of our social strata, offers a wide field of employment to women after this period of life. Many never think of cultivating their minds until they find their influence fading with their charms, and then set about acquiring a less perishable empire, and employ this period of freedom in literary pursuits. Others govern with discretion that circle of society, limited or extensive, in which they have been placed; becoming the guides, the supports, and mainstays of both sexes in the difficulties of life. Indeed, it would not be too much to say, that the discordant elements of society can never be blended without the authority willingly conceded to the combined influence of age and sex. It is a matter of history how society has been modified by the drawing-rooms of Mme. Lambert, Mme. de Tencin, Mme. du Deffand. Those acquainted with French society in our own time will remember the reign of the late Mme. Recamier over a large circle of talented friends; and during my residence in Paris, I have myself fre-

quently witnessed the benign influence of Mme. Swetchine* prompting the eminent men who gathered around her to what was great and noble; guiding many women in the difficult paths of life; healing wounds caused by inexperience; and making many bless her still, for the happiness they now enjoy. This brings me to the noblest motive to be offered to the laudable ambition of women,—that of doing the greatest amount of good, to the greatest number of their fellow-creatures. Time dulls the eye, robs the cheek of its bloom, delves furrows in the forehead, but cannot quell the seraphic fire burning in the heart of women, prompting them to deeds of charity, and to heal the deep and ever-breaking-out wounds which afflict society. Those who have attained their sunset without having been granted the anxious though desirable vicissitudes of wedded life, even if destitute of relatives, or unfortunate in friendship, may still find in the various forms of unmerited affliction which fill our country cottages, or the hovels of our populous cities, that whereon to expend a warmth of feeling, an energy of self-sacrifice, which the sophisticated state of society has not permitted to flow into their natural and more grateful channels. Why then should women, sensible in everything else, be sometimes unable to accept their new position, and, instead of kind and charitable, become, at this period, peevish, harsh, and dismal, viewing everything through a jaundiced veil?

The most distressing appeals to medical sympathy, are made by those who, when unnerved by the change of life, find themselves alone in the world, bereft, when most needed, of the solace of filial piety, or the supporting sympathy of conjugal affection. One can only at first respond to such appeals with a sympathizing look and a silent pressure of the hand; but should tears burst their bonds, lightening the suffering spirit of half its load, sweeping away sorrow, disquietude, and doubt, then it may be hinted that time steals even sorrows from the heart, doubtless because they are sweeter than joy, and that

* Since these lines were written in the Second Edition, Mme. Swetchine is dead; Cte. de Falloux has published her works, which have been translated into English, and her "Pensées Choisies" have been beautifully illuminated by my friend Miss Simpson.

after a brief period nothing will remain but the clear, calm, and grateful remembrance of past goodness, where it was once thought that impassioned love and ever-devoted tenderness must be eternal. Here again the best mode of affording relief, is to discover some kind of occupation capable of engrossing the sufferer's attention, such as music, gardening, the education of a relative or of an adopted child, or the management of a school, or some other charity. The continued friction of social duties will, in time, rub off the asperities of character, and restore peace and tranquillity to the troubled spirit. Every effort should be made, in such a case, to prevent brooding and self-absorption, for the mind may gaze so long upon itself and its inner workings that the moral vision may become affected with the same kind of disorder which befalls the bodily eye when fixed too long on one color; surrounding objects then lose their real appearance, to shine only with unnatural tints.

PART III.

SPECIAL PATHOLOGY

OF

THE CHANGE OF LIFE.

CHAPTER VI.

DISEASES OF THE GANGLIONIC NERVOUS SYSTEM.

TABLE XXIV.

Liability to Diseases of the Ganglionic Nervous System, in 500 Women at the Change of Life.

Epigastric faintness and sinking, ...	220
Epigastric pain or anomalous sensations, . . .	49
Fainting or leipothymia, ...	25
Fainting off, for the first time in life, ...	3
Prolonged and intense debility, ...	41
Monthly depression of strength, ...	1
Chlorosis, ...	40
Palpitations, ...	16
Aortic pulsation, ...	2
Hysterical asthma, ...	7
Monthly hysterical asthma, ...	2
	406

Thus 406 instances of ganglionic suffering were divided amongst the 500 women who suffered more or less from diseases of the ganglionic system; many of them suffering in more ways than one. At the same time the liability to these affections decreases as women advance in age; epigastric pain is then seldom intense, but there frequently remains a liability to fainting, and to sinking sensations at the pit of the stomach.

The volume of the brain, its complicated and regular structure, show it to be contrived for important ends, and although the relation existing between the intellectual faculties and the structure of the brain cannot be comprehended, it must be admitted. It is far different with respect to the ganglionic

nervous system, and indeed it is incomprehensible that so much vital force, for good or for evil, should be centralized in little irregular lumps of nervous matter, and in sundry tangled skeins of nerves, the geography of which, like that of the polar regions, is differently mapped out by successive observers; but though incomprehensible, it is no less certain that these knots of nervous matter, and these tangled skeins of nerves, control the bloodvessels, and are indissolubly connected with the supreme power which guides the processes of healthy or diseased nutrition. This is proved by the writings of Winslow, Bichat, Reil, Wilson, Brachet, Philip, Broussais, and Lobstein, besides the recent writers quoted in the following pages. Whether, with Bichat, anatomists look upon the ganglionic nervous system as independent, or with Haller, as an offshoot of the cerebro-spinal system, the ganglia contain every variety of nerve tissue, and must still be considered as little brains, each having its special range of power, deriving sensitiveness from the sensory nerves, which proceed to every ganglion, by means of which nerves the brain becomes cognizant of morbid ganglionic impressions. With Müller, I consider the ganglia to be the source of the energies of the sympathetic nerves, and the fountains from which the ganglionic nerves draw the constant, gradual galvanoid current by which the capillaries throughout the frame are enabled to do their work. It, moreover, appears that each separate ganglion sends its contingent of nervous influence to the central ganglia, and that the force with which the ganglionic nervous system is endowed, is centralized in the epigastric region as the intellectual faculties are in the brain. Discordant as medical theories generally are, it is singular how often the importance of considering vital force as centralized in this epigastric centre has been prominently asserted; Galen and Fernellius called it the principal lever of the human forces; Van Helmont there placed his *Archæus*, Wrisberg and Lobstein treated of it as *the cerebrum abdominale;* Hunter called it the sensitive centre, and the centre of sympathies; and Bichat, Broussais, &c., considered it the prime conductor of nervous influence. The importance of this region as a centre of power, is even shown by the erroneous theories which made some medical men place the seat of

sensibility in the diaphragm, and by the popular belief that the human passions are centred in the præcordia, whereas they merely react upon it, as stimulants when the passions are exhilarating, or as depressants when they are of a contrary nature.

Nevertheless, the ganglionic nervous system, in a pathological point of view, is looked upon as a *terra incognita;* and its diseases are neglected or very incompletely considered in systematic works on pathology, and are scarcely better treated in books on nervous diseases—a neglect partly due to the wild theories that have been broached respecting the ganglionic nervous system by fanciful writers. Thus, notwithstanding Lobstein's classic work, Georget, writing in 1836, affirmed, that nothing is known about the diseases of the solar plexus, or the ganglionic system of nerves, and a little later, Sir H. Holland stated "that the ganglionic system, and the various nerves of organic life, are still only partially known to us in their proper actions, and yet more obscurely in their intricate connections with the nervous powers of animal life;" and that, "a less definite influence of the system of organic life, as one of the causes of exhaustion, is the only morbid liability of this all-pervading nervous system." It is not surprising, however, that the pathology of the ganglionic system should have been hitherto imperfectly considered, since its physiology is full of desiderata; but the experiments performed by Claude Bernard, and the inference drawn from them by Brown-Séquard, that the bloodvessels were paralyzed by the section of their ganglionic or vaso-motor nerves, have given a physiological basis to the study of the diseases of the ganglionic nervous system. These experiments establish the fact that the partial paralysis of the ganglionic nerves leads to the congestion or to the inflammation of the tissues within the area of their distribution, and the controlling influence of the semilunar ganglia over the bloodvessels of the abdominal viscera is shown by the experiments of Samuel, who found their extirpation in dogs, cats, and rabbits to give rise to an extraordinary amount of hyperæmia of the intestinal mucous membrane.

Besides controlling circulation, it would seem as if the

ganglionic system furnished to the human frame a nervous influence that plays the part of steam in the steam-engine, the unconscious nerve force giving to the cerebro-spinal system a power, of which the human mind has the full consciousness. At all events, any one who will take a comprehensive view of the various stages of the reproductive process in women, will be struck with the fact that frequent prostration of strength is a predominant symptom even when women are healthy. At every recurring menstrual period, at the cessation of menstruation, after connection, parturition, and during lactation, there is felt, more or less, a loss of energy;—so it seems as if woman could not pass through any of the stages of that function which serves to communicate life, without the momentary loss of some portion of her own vital energy, reminding one of those animals who die when once they have transmitted life to others.

Et quasi cursores vitæ lampada tradunt.

A glance at the preceding table will show that debility of variable intensity is the constant characteristic of all the complaints which I attribute to the diseased action of the ganglionic system, and Dr. Handfield Jones,* who has seriously taken in hand the study of ganglionic affections, has well pointed out that, however painful may be cerebro-spinal neuralgia, it does not induce syncope or leipothymia, which are apt to accompany the irritation of any of the sympathetic plexuses. Debility is, of course, often met without our being able to trace its origin to any particular part of the body; but debility is so intense when disease of the central ganglia is evident, and so constant an attendant upon every form of gangliopathy, that we may consider debility as its main symptom. The same remark applies to chlorosis, and still more forcibly to leipothymia and syncope.

Gangliopathy.—I give this name to a condition in which more or less debility is associated with paralysis, hyperæsthesia or dysæsthesia of the solar plexus and the central ganglia of the sympathetic system. Gangliopathy has often

* "Functional Nervous Diseases."

been described as cardialgia, gastralgia, and gastrodynia, but these names should be restricted to neuralgic states of the stomach. Gangliopathy has been written of, as neurosis of the vagus, as leipothymia, as sinking dyspepsia, as hysterical asthma, and one of my cases had been called by other practitioners *a nervous affection of the diaphragm*. Women frequently complain of *chest pains*, or of *spasms*, *inward spasms*, or *inward hysterics*.

The effects of a moderate blow to the pit of the stomach will explain what I mean by gangliopathy being attended by paralysis. For instances of perverted ganglionic action, I refer practitioners to the most prominent symptoms of overlactation; but, as I am drawing attention to a disease that has been to a great extent overlooked, I shall begin by giving cases that illustrate the various forms of gangliopathy, and I prefer to use a term that localizes the disease without specifying its nature, because I think the present state of science seldom warrants a more definite expression.

CASE 15.—*Ganglionic hyperæsthesia.*—Miss C. was forty-eight, tall, stout, with dark hair and a flushed face. The menstrual flow came regularly from thirteen to forty-seven, but afterwards irregularly, being often a mere show. This patient was never nervous or hysterical; she complains of pain at the pit of the stomach, which first appeared when the menstrual flow became irregular, and says that now she is never without uneasy sensations at the epigastric region, which do not generally interfere with the current occupations of the day, though often paroxysms of acute pain occur, especially at night, when they suddenly awaken her from a sound sleep. The pain then experienced is described as a "tearing pain," and after it has lasted from ten to twenty minutes, a ropy mucus comes from the mouth, by expuition, without eructations. When the intensity of the pain has abated, the patient lies prostrate for hours, conscious, but incapable of exertion. Sometimes she faints away, and after a bad attack was forced to keep her bed a day or two. During the last six months, flushes and perspirations have been abundant. The tongue was clean, digestion good, and no trace of tumor at the pit of the stomach. I recommended 6 oz. of blood to be taken from

the arm, 2 tablespoonfuls of a comp. camph. mixture before, and 10 grs. of carb. of soda after meals; 2 comp. col. pills and 10 grs. of Dover's powder on alternate nights, and a mustard or a linseed poultice to be applied to the pit of the stomach every night. The camphorated mixture that I often give in similar cases is composed of 3 drachms of tincture of castor, 6 drachms of tincture of hyoscyamus, and 5 oz. of camphor julep. After continuing this for a month, the paroxysms came only once a week, instead of almost every night; I then ordered a warm bath to be taken for two hours every other night, just before going to bed; alternate belladonna and opium plasters, changing them every week, and a scruple of sulphur once a day. This was persisted in for six weeks, and then left off, because there had been no paroxysms for ten days. When the patient left town, I advised her to take the mixture now and then, as well as the pills and the comp. sulphur powder, and to have 2 or 3 oz. of blood withdrawn from the arm at intervals of three and six months. This case seems to me best accounted for, by admitting a neuralgic affection of the ganglionic nervous centre, for the stomach performed all its functions healthily, and there was no sign of cerebral disorder, neither did this affection obscure the comprehension of its true nature by awakening other nervous disorders. It caused no hysteria, no pseudo-narcotism, not even headache. This neuralgia of the ganglionic centre was well characterized by the paroxysmal character of the pain, and by the state of exhaustion and faintness it determined.

Case 16.—*Ganglionic hyperæsthesia.*—Mrs. K., aged forty-two, consulted me, July 5th, 1855. This lady is stout, of an average height, with dark hair and eyes, a swarthy complexion, and has all her life been subject to bilious complaints. The menstrual flow first appeared, with frequent fits of fainting, at twelve. It continued regular, and was often accompanied by brow-ague. She married at twenty-seven, but never conceived. In 1848, after having been a year at Ceylon, she was first taken with excruciating pains in the dorsal region of the spine, and in the abdomen, which pains always came on at night. She improved under a mercurial treatment, had the Bombay fever the following year, but came home recruited by the long sea-

voyage. Four years after her return, the menstrual flow became irregular, and now she never passes more than "a little green water" for one day. Since the menstrual flow became irregular, she has been always ailing; was once under Mr. Keate for an hysterical affection of the shoulder-joint and paralysis of the arm, and has often had attacks similar to those she had at Ceylon. She stated, that every night she was awoke by an acute, "gnawing, hot pain" about the fifth dorsal vertebra. This pain encircled the right side, reached the pit of the stomach, where it centred and kept tearing and gnawing her for about two hours. The patient very graphically described the sudden coming of the attack—"as if the thing called pain played a thumping overture upon her." She has learned to relieve these attacks by laudanum; in their absence, she is very often troubled with a burning pain at the pit of the stomach; and of late, when this was intense, she has often fainted several times a day. This lady, though stout and healthy-looking, is endowed with great nervous irritability, increased by anxiety for a very nervous husband. She feels every change in the weather, and suffers acutely when there is thunder in the air. She is often heavy, stupid, drowsy, and forgetful: very low-spirited, thinks she is going out of her mind, and is often tempted to commit suicide. For the last two years she has been much troubled with flushes, but without perspirations; and circulation is inactive, for her fingers are cold and blue, even on a warm summer's day. The pulse is small, the tongue slightly furred. July 5th.—I prescribed the comp. camph. mixture before meals, carbonate of soda after; 6 grs. of blue pill, and 2 of ext. of hyoscyamus every other night, 10 grs. of Dover's powder every night, a scruple of the sulphur and borax powder once a day, and warm baths twice a week. July 18th.—Decided improvement followed the sound sleep which came when the treatment had been followed for a few days; the paroxysms of neuralgia were no longer periodical, and she had only had two since the 10th. I continued the same treatment, but also ordered two belladonna plasters, one to the epigastrium, the other to the painful part of the spine, which were to be renewed every week. Aug. 15th.—The patient being very bilious, I ordered 3 grs. of

calomel every other night, and a black draught in the morning; the mixture, the soda, and the Dover's powders were continued. She was salivated by two of the pills. Sept. 19th.—The paroxysms of pain returned again every night; so I ordered the sixth of a grain of acetate of morphia to be taken in a mixture, every two hours, until sleep was induced. This procured fourteen hours of sound sleep, and the attacks only occurred at long intervals. When I last saw the patient, I advised her to take the c. camph. mixture and the Dover's powder occasionally, to take, every night, half a drachm of equal parts of sulphur and magnesia, and to induce sleep by acetate of morphia whenever an attack was imminent. One point to be remarked in this case is, that the frequent flushes were dry and burning, whereas gentle perspirations coincided with the improvement in the symptoms, and their persistence affords the greatest chance of immunity from worse symptoms. This patient had been fearfully nervous all her life without ever having presented any decided form of hysteria, so varied are the states of nervous suffering, for many of which there is no name.

In other cases, it is not from intense pain that the patient suffers, but from annoying and singular ganglionic sensations, and as these do not depend upon any organic affection of the heart or the aorta, and coincide with other nervous symptoms of cessation, it seems fair to ascribe them to some morbid condition of the ganglionic nervous centre.

Case 17.—*Ganglionic dysæsthesia.*—Sarah B., tall, stout, and healthy-looking, with brown hair, and hazel eyes, was forty-seven when she came to the Paddington Dispensary, Sept. 8th, 1849. The menstrual flow first appeared at seventeen, was always regular, and accompanied by pseudo-narcotism. She married at twenty-five, had two children; and the menstrual flow left suddenly, without known cause, at forty-four. Since then, she has been entirely free from lumbo-abdominal pains, but has suffered much from nervous symptoms. There has been no headache, but a heavy, stupid feeling in the head, with drowsiness in the day, after sleeping well at night, and a forgetfulness of familiar things. She has also been nervous, desponding, and low-spirited; often shedding tears, and complaining of strange sensations

in the throat. Ever since cessation, she has been distressed by a fluttering at the pit of the stomach, "as if something were perpetually swinging within her." It becomes worse after meals, generally abates when she lies down, is seldom felt when in bed, but begins so soon as she rises. When turning the corner of a street, this sensation makes her feel afraid of losing her centre of gravity and overbalancing herself; and when she has it in bed, she feels "as if a tub were rolling to and fro within her," and then "the head goes too," as "if something rose from the pit of the stomach to the head, making it feel giddy and bewildered." Since cessation, she has been troubled by burning flushes, without perspirations; and there is sometimes a good deal of pudendal irritation. There was no organic disease of the heart, aortic pulsation, or obstinate dyspeptic condition, to explain this singular symptom; but it would be illogical to deny the patient's statement because her sensations could not be explained; she has consulted many practitioners, and had been told "it was all nonsense." Sept. 8th.—I ordered the comp. camph. mixture before meals, and on going to bed; carb. of soda after meals; a large opium plaster to the pit of the stomach; and a small teaspoonful of sulphur and carbonate of magnesia every night. September 15th.—She was better; I ordered a saturnine lotion for the pudendal irritation, and 10 grs. of Dover's powder to be taken every night. Oct. 6th.—Instead of perspirations, a papular eruption has appeared on the shoulders. She feels rather worse than better, but the same remedies were ordered, with the addition of 2 comp. col. pills, to be taken occasionally. Oct. 20th.—All the cerebral symptoms have vanished. She is much better, and can now bustle about; but the swinging sensation in the epigastric region still remains. The improvement coincided with gentle, well-sustained perspirations. I ordered the mixture and soda as before, but discontinued the sulphur and Dover's powders; prescribing, instead, sulphur, 2 oz.; borax, 1 oz.; Dover's powder, 1 drachm, 2 scruples of the powder to be taken in a little milk at night. A blister was ordered to the pit of the stomach. Nov. 6th. —She looks cool and comfortable, much stronger, and quite

like another person. Though less troubled by the swinging sensation, it still exists. The blister did no good, so I ordered a rotation of belladonna and opium plasters, each to be worn a week on the epigastric region, and the mixture and comp. sulphur powders to be continued. Nov. 23.—The patient was discharged cured; she felt comfortable and happy at having lost the epigastric sensations.

Case 18.—*Ganglionic dysæsthesia.*—Sarah J., an average-sized woman, with dark-brown hair, gray eyes, and a semi-chlorotic complexion, came to the Farringdon Dispensary, February 25th, 1853, being then forty-six, and unmarried. The menstrual flow appeared at sixteen, and continued regular, without any nervous or other symptoms, except that, for two or three days, it was almost always preceded by the eructation of acid mucus. Flooding came on seven months ago, without any known cause, and the menstrual flow has since appeared every six or eight weeks, varying in quantity, and being accompanied by abdominal bearing-down pains, and severe headaches, although she has brought up much less acid mucus. She has suffered from lowness of spirits, involuntary tears, choking sensations, gasping for breath, and a sensation of fluttering at the pit of the stomach, which she compares to a steam-engine pumping up something from the stomach to the head, inducing headache and giddiness. These sensations are not always felt, coming on when she lies down, so she sleeps propped up in bed. The attack seldom lasts more than half an hour, but the night is restless, and the following day she sleeps a good deal in her arm-chair. I could detect no disease of the heart, no aortic pulsation, slight signs of gastric disorder, and this patient had no flushes or perspirations. I ordered the comp. camph. mixt. before, and the carb. of soda after meals, 10 grs. of Dover's powder at night, a scruple of the sulphur and borax powder twice a day, a belladonna plaster to the pit of the stomach, and 2 comp. col. pills to be taken occasionally. This treatment was continued three months, and completely cured the symptoms. The patient then became regular, and continued so for six months, when the menstrual flow ceased suddenly. She was then much troubled by great debility,

headache, giddiness: and for the last year, has been subject to flushes and perspirations, but the epigastric annoyance has not returned.

CASE 19.—*Ganglionic paralysis.*—A widow lady, aged fifty-four, was regular until forty-one, when the menstrual flow ceased suddenly from being frightened at a revolutionary tumult at Athens. She then became subject to headache and bilious vomiting, which abated on her return to England in 1851. In 1855, the habit of vomiting completely ceased, but was succeeded by an overpowering sensation of faintness at the pit of the stomach. This sensation so exhausted her strength that she was confined for days to her bed. This complaint had been called "a nervous affection of the diaphragm," and aperients, tonics, and stimulants, with blisters to the pit of the stomach, were tried ineffectually until combined with sedatives, given as in the previous cases, which relieved this patient, notwithstanding ever-recurring domestic annoyances. In 1859 she wrote to say that she had recovered her health, and was able to take very active exercise.

The same treatment was successful, in similar cases, which occurred in Dispensary practice, and if these anomalous symptoms only occurred in those who have plenty of time to watch the coming of each new pain, and to nurse it until it has taken root in the nervous system, I should lay little stress on such cases; but when they occur in the sturdiest of Eve's daughters, hard-working women without imagination, I look upon the symptoms as indicative of local disease, and not of mental delusion. A strong-looking washerwoman, aged forty-seven, mentioned that, after the menstrual flow had ceased for six months she was, for the first time in her life, obliged to give up work, because slight exertion caused great pain at the pit of the stomach, with fainting fits often prolonged for three-quarters of an hour. Mrs. W. ceased at fifty-six, and is now fifty-nine. After mental excitement, during the last year, she has been subject to aching pains at the pit of the stomach. She sleeps well until five A.M., and then arise epigastric sensations, as if something were turning in the stomach. This is followed by palpitations. She has no dyspepsia, but feels nervous, frightened, cannot cry, and, like the Wandering Jew,—

"she must march on." Belladonna plasters entirely removed the epigastric sensations in a month. Phœbe M., aged fifty-six, has been unusually weak for the last five years, ever since cessation. She says she is troubled with "inward hysterics," and "faint heats." There is no aortic pulsation to be detected, but the least thing is said to bring on a violent abdominal beating, and causes her to pass two or three liquid stools, with blood from the bowels, or from piles. At times she loses her sight, and cannot sleep. Flushes are generally preceded by heat, pain, or faintness, at the epigastric region, and the sensations have been described by patients as "a ball of fire," or "gnawing, tearing pain," relieved by pressure, and prompting the sufferer to turn on her stomach to press the painful region. Whoever has seen patients suffering from lead colic will recognize similar symptoms.

Many patients, similarly affected, complain of the epigastric region being "all of a boil," and that any sudden impression sets the stomach "all of a flutter," with great subsequent weakness. Dr. Brown, of Newcastle, has met with a case of emotional insanity, in which the patient had the sensation of a bright flash of lightning in the epigastrium, and three other lunatics complained of darkness in the same region.

In the following cases the difficulty of breathing from a reflex spasmodic contraction of the diaphragm and intercostal muscles was a predominant symptom. The following case was published by Dr. Marrotte (*Gaz. des Hôp.* 1854), under the title of "*Spasme simultané de la glotte et du diaphragme.*"

Case 20.—*Gangliopathy and hysterical asthma.*—A woman, aged forty-four, entered the Hospital of "la Pitié." The menstrual flow came at seventeen, with disturbance of health, and at twenty-three she had frequent menstrual irregularities; became nervous, had agonizing sensations at the epigastrium, with globus hystericus, and a spasmodic contraction of the diaphragm, continuing so long that her friends feared asphyxia. In these attacks, which occurred about three or four times a week, she heard what was said, but could not speak. Cessation took place at forty-two, and the nervousness increased, for she laughed or cried at the least thing. The day the patient entered the hospital the house-surgeon saw her in one of these

attacks. Pain at the pit of the stomach, and a sensation of stricture at the basis of the chest were first felt, then respiration was suspended, after which followed great efforts to inspire and expire, both being separated by variable intervals, and accompanied by laryngeal whistling. The noise was strongest during inspiration, which was attended by an exaggerated dilatation of the chest, and great efforts to swallow an imaginary bolus. Several of these attacks occurred, lasting from half a minute to three minutes, and were followed by pain at the pit of the stomach, by fainting and exhaustion. The attacks seemed to abate on pressing the pneumogastric nerves at the inferior edge of the thyroid cartilage.

Although there were no ganglionic symptoms in the following case, it much resembles the previous one.

Case 21.—*Hysterical asthma.*—Miss O., tall, stout, of a sanguine temperament, was fifty-seven years of age. The menstrual flow came at thirteen, and was regular until fifty, when it ceased gradually. Until then she had never any serious illness, and no marked hysterical symptoms, though she was always very excitable. Just before cessation she had the shingles, and soon after erysipelas, but with the exception of flushes and gentle perspirations she remained well for two years. Five years ago, Miss O. was, for the first time, and without known cause, seized with the nervous affection for which she consulted me. Without being sick, she goes through the pantomime of sickness; she gasps for breath, but retains consciousness, and does not suffer from positive pain, but from the anguish of not being able to breathe. The attack lasts from three to ten minutes, and is often preceded for several days by a spasmodic affection of the jaws, "as if she could not put the teeth in the right place." A neuralgic flash of pain across the forehead and heavy sweats, are its immediate precursors, and it leaves her in such a state of exhaustion, that she has often kept her bed for several days. These attacks used to occur at short intervals, but lately there has been a longer period between them. Worry brought one on a month ago. She has no epigastric pain during the attack, or at any other time. For the last three years there has been a red sediment in the urine, and an unusually frequent desire of passing it. She has no

leucorrhœa, but for two years she has been frequently troubled by great irritation of the labia. Hard lumps are said to arise, and, after remaining a few days, to disappear, without suppurating, but sometimes end by a pimple, and she has suffered sometimes from piles. Miss O. is evidently very nervous, and, although grown stouter, she is very weak, and as her attacks were becoming less and less frequent, no active treatment was required. I recommended the comp. camph. mixture to be taken, off and on, for several months; twenty drops of liquor potassæ in a little water, after meals, and the sulphur and borax at night. Warm baths were also suggested, particularly when there was pudendal irritation, and citrate of quinine and iron. This patient enjoyed such excellent health until cessation, that I attribute all the subsequent illness, the nervous attacks, the erysipelas, and the pudendal irritation, to the organic changes set on foot by the turn of life, and some years afterwards, I learnt that Miss O. has only felt slight returns of the same symptoms.

Voisin also relates, that a case of hysterical hemiplegia was sometimes attended by instinctive and prodigious efforts to breathe, with emission of a singular noise from the glottis. Dr. Marrotte considered his case analogous to the laryngismus stridulus of children; but when the subject was discussed at the *Société de Chirurgie de Paris*, Dr. Beau judiciously observed, that there was no analogy between the two affections. At p. 84 of my work on "Uterine and Ovarian Inflammation," I have given the case of a lady, aged thirty-three, whom I have frequently seen similarly attacked; there was no laryngeal spasm, but absence of all respiratory movements for five or six minutes, as she lay immovable, and with open mouth. The gradual solution of the spasmodic contraction of the diaphragm could be measured by the increased length of respiration, a full respiration bringing back consciousness. Sir B. Brodie mentions the case of a young lady, in whom the slightest pressure on the epigastric region would bring on paroxysms of suffocation from spasmodic contraction of the walls of the chest. In a diminished degree, the symptoms frequently attend an ordinary hysterical attack, though they may occur in an aggravated form in women suffering little

from the ordinary forms of hysteria, and who present no signs of emphysema, or of heart or lung disease. In my six other cases of hysterical asthma at the change of life, the symptoms were less marked than in that of Miss O.; but those described by Dr. Marrotte were reputed not uncommon by Dr. Beau, who mentions having seen a woman, suddenly taken with suffocation, and die in two minutes, without any discoverable cause. M. Bacchias, in his thesis, has given several similar cases.

Having described the minor, as well as the most severe forms of cardialgia,—having adduced examples of it, where the prominent symptom was pain or sensations almost baffling description, and complicated by various reflex neuralgias, it is well to inquire the opinions of pathologists, who have described the severe forms of the disease of the ganglionic centre. Hippocrates has noticed agonizing epigastric pain, accompanied by the impossibility of breathing, as having occurred at puberty. F. Hoffman, in describing cardialgia, insists on the intense pain at the pit of the stomach, the sense of anxiety, the difficulty of breathing, and the prostration of strength, opining with Barras, that the stomach was alone affected. Some of Schmidtman's cases of this disease are similar to mine, like that of a girl of sixteen, who, for several months before menstruation, suffered severely, at the pit of the stomach, for a few days every month. Barras adopted, I think erroneously, the term Gastralgia, for the ganglionic phenomena occurring at lactation, chlorosis, or pregnancy; and remarks, that his patients refer the sensations of weakness and prostration which overpower them, to the epigastric region. Joly and Georget also described these symptoms as Gastralgia, and noted its frequency in women during the reproductive period of life, or whenever the system is strongly reacted on by the reproductive apparatus. Louyer Villermay gives cases in which hysteria is accompanied by attacks of intense epigastric pain, exhaustion, syncope, or suffocation. Dr. Addison has not exaggerated the frequency of gangliopathy in those suffering from uterine affections, and Hufeland and Chambon state that, at the change of life, women are subject to suffocation and epigastric spasmas. Dusourd, remarking on the same phenomena, says, "they simulate asthma," and adds, that "the affections

and sensations at the pit of the stomach, at the change of life, baffle description."

Dr. Shearman—*Medical Times*, September 20th, 1856—bearing in mind the fact, already well established by Romberg, that neuralgia of the vagus nerve is indicated by patients becoming ravenous, who could previously take only the smallest quantity of food; and coupling this with Bernard's discovery, that irritation of the origin of the vagus caused sugar to form in the liver, to be removed by the kidneys, and appear in the urine, Dr. Shearman "concluded that the disease was one of the vagus nerve, in some parts of its tract, either centric, peripheral, or intermediate; of irritation in its early stages, and of palsy succeeding to that irritation." He designated it *sinking dyspepsia*, and treated it as he would the neurosis of any other centripetal nerve. If I be not deceived, Dr. Shearman has exaggerated the frequency of neurosis of the vagus, describing as such, those affections of the ganglia and cœliac plexus, which are more or less complicated by reflex neuralgia of the vagus nerve. The vagus is a bridge by which the central portions of the two nervous systems are placed in communication; uniting both nervous systems it resembles both, but principally the sympathetic, by its organization and the modes of its distribution. It is not a well-isolated nerve, for it often anastomoses with the sympathetic, and helps to form the cœliac plexus, by nerves which are both numerous and voluminous. Thus anatomically united, I believe the affections of the vagus and of the epigastric ganglia generally coincide.

Causes of Gangliopathy.—The ganglionic nervous system, particularly its epigastric centre, may be morbidly influenced, firstly, by concussion; secondly, by mental emotion; thirdly, by heat; fourthly, by cold; fifthly, by poisons.

Firstly. A blow to the pit of the stomach does not kill by inflammation, but by a shock, so suddenly intense, that the laws of pugilism forbid "to hit under the belt." The blow may, however, be so graduated as to determine corresponding shades of neuralgia and of leipothymia. The recoil of a pistol, to the pit of the stomach of a lad aged thirteen, made him faint and lose consciousness for several minutes, emptied the stomach and rectum, and for fifteen minutes the heart's action

was very feeble and the radial pulse could not be felt. The anguish of vomiting is partly due to the more or less intense concussion of the epigastric ganglia, which explains the intense debility it causes, and the not unfrequent deaths that occur when, as on board ship, it cannot be checked.

Secondly. Great sudden and depressing emotion may act on the ganglionic centre like a blow, setting up morbid action, lasting for twenty years, as in the last case of the next chapter, or for a shorter period, as in a dispensary patient, aged forty-seven, who was ceasing to menstruate, and was in good health when a son came home ill; and what with the fatigue from nursing and the fear that her son would commit suicide, she was suddenly seized with great epigastric pain, and a shaking of the abdomen so distressing that she was obliged to stop quiet, and support it with her hands. This symptom was most troublesome at night, and was made worse by exertion or worry. A flooding came on, and the patient gradually mended.

I have met with cases in which connection acted as a depressing poison to the ganglionic nervous system, causing intense epigastric pain, unconsciousness, and great prostration, lasting for two or three days. There was nothing to explain this constitutional peculiarity except the fact of connection being unattended by pleasure.

Besides the capability of being stunned by a blow or sudden emotion, the great central ganglia are susceptible of receiving shocks from self-generated poisons spontaneously evolved in the system. "Miseros vidi ægrotos," says Lobstein, "qui, vix somno dediti, subitò fuerunt expergefacti atque valido et quasi electrico ictu territi, ab epigastrio proficiscente; crudele phenomenon, quod per plurimum mensium spatium duraverat." Other authors have noticed the same strange sensation, but independently of these rare occurrences, it will be obvious to the pathologist that the ganglionic centre may receive, from causes spontaneously arising in the frame, milder shocks, which determine the varied forms and degrees of ganglionic disturbance.

Emotions, varied feelings of pain or pleasure, past, present, or anticipated, are conceived in the brain, and sent, lightning-like, along the nervous cords to the various ganglia which

stimulate the viscera to respond by appropriate action. This is admitted by everybody, but the converse is equally true that the viscera by their ganglia react on the central epigastric ganglia, and thereby on the brain, so as to suggest to this supreme organ the emotions whose purpose they subserve. What is obvious with regard to emotions, is very probable with regard to the physiological and pathological stimuli that the viscera transmit to each other and to the brain. In both sexes, there is more or less of paralysis and perturbed action of the central ganglia during convalescence, in consequence of the undue strain put on the ganglionic system to support the increased effort made to repair the effects of disease; in helminthiasis, when the expansions of ganglionic nerves are irritated by worms; in agues, of which the ganglionic system is the prime motor; in hemorrhoidal and other flows, when indiscreetly stopped by cold; in chlorosis, hypochondriasis, and in the earliest stages of insanity, before the ganglionic, are cast into shade by the magnitude of cerebral symptoms. But the greatest and most frequent cause of disturbance of the ganglionic centres, is the strong reaction of the reproductive organs: puberty, menstruation, pregnancy, lactation, and cessation, almost always cause slight forms of gangliopathy, and sometimes the severest, and may lead to insanity and to suicide. Woman suffers more than man, for her ganglionic nervous system is doubly taxed for self-nutrition and that of the race, and if she be susceptible of so often "tumbling to pieces," and of being again knitted firmly together, it is because her ganglionic nervous system has been endowed with extraordinary powers for good or for evil; but man does not escape, and I can confirm the accuracy of Schmidtman, who has paid so much attention to nervous affections, when he says, "so often as a young man consults me for cardialgia, I suspect onanism." Gangliopathy, under varied forms, is frequently observed in spermatorrhœa, and explains why some have committed suicide, and many have become hypochondriacs. The *debauché* and the *roué* are frequently at a loss for terms to express the annoyance of their sufferings at the pit of the stomach. These sensations in women at the change of life, may be the harbingers of others that obscure them, such

as flushes, perspirations, diarrhœa, bloody stools, and hysterical symptoms.

3dly. Dr. Morehead has noted the prominence of what I call ganglionic paralysis in what he describes as the cardiac variety of heatstroke. Denon relates that when marching through the burning plains of Upper Egypt, in the hottest part of the day, several men died of heat. "Nothing," says he, "can be more frightful than this death. Of a sudden comes intense sickness, then sinking and fainting that nothing can relieve, and death soon occurs." A French surgeon, describing the effects of the sirocco, on soldiers marching from Oran to Tlemcen, speaks of a kind of incubus weighing on the epigastric region, of debility almost reaching to syncope, of sudden bursts of heat in the face and intense headache. Similar phenomena, only less intense, may be caused by remaining too long in Turkish baths too much heated, as I know by my own experience of one I took at Damascus.

4thly. Dr. H. Jones has drawn attention to the paralyzing influence of raw and intense cold, and to the manner in which it strikes at the pit of the stomach, yielding to brandy and warm epigastric clothing.

5thly. Poisons paralyze the ganglionic nervous system in various ways. *a.* Too much food or undigested food remaining in the stomach often gives rise to much of the ganglionic disturbance that characterizes nightmare, and sometimes to death in the aged, as suggested by Mr. Higginbotham. *b.* There is great similarity between some of the sufferings of hysteria and lead-poisoning. There is the same exquisite distress referred to the pit of the stomach, and the same instinct to seek relief by pressure to that part.

Symptoms and Diagnosis.—Debility underlies all other ganglionic affections, in the same way as nervous irritability underlies all cerebral diseases. Debility existed in a marked degree in all the cases enumerated above, although it was only marked, intense, and prolonged, in forty-one instances, where it did not seem to depend upon any other cause than the change of life. Sometimes there was an overpowering sense of exhaustion pervading the whole system; thus forty-one women, of previously active habits, deplored being rendered helpless

by intense and long-continued debility. A. M., a hard-working woman, says, "she hardly knows how to dress herself, and is often obliged to lie down to recover herself." M. W., a thin, delicate, red-haired woman, aged forty-five, two years ago got her feet wet at a menstrual period: the flow stopped: there were great abdominal pains, and a state of intense and long-continued prostration, without any other cause than the change of life. In others, the debility is so rooted in the system, that a full meal or stimulants will not dispel it. There is only a difference of degree, none of nature, between this thorough exhaustion of radical strength, and its slight manifestations, so frequent at this period, which seem to originate from the pit of the stomach. This epigastric faintness occurred in 220 out of 500 cases, and is one of the most frequent of the minor torments to which women are subject. Pathologists have noted the severe cases of disease of the ganglionic centre, but they have failed to see the connection between these and its milder forms, which occur habitually; whereas, between the severest of the 49 severe, and the slightest of the 220 mild cases, I only see a difference of degree, none in the nature of the complaint, which is as variable as the ever-varying shades of the same color. The symptoms are described as "a sinking and faintness," "faint heats," "or a dull sickly feeling at the pit of the stomach;" and the sensations are compared to those of "hunger, or to the craving of the dram-drinker for his wonted stimulus." Others feel "as if they could faint," as "if they wanted support," as "if they had no inside," as "if there was a vacuum." They will not allow the sensation to be called pain, but speak of its being so irritating and irksome that it is worse to bear than pain. They will frequently say that "all the complaint lies in the chest," but they point to the pit of the stomach, and have not a single symptom of disease of the lungs. There may be oppression and faintness, with or without violent pain at the pit of the stomach; sensations like "the fluttering of a bird," "the throbbing of an animal," or those "of internal rawness," "of gnawing and of tearing;" but these feelings do not depend upon gastric inflammation, since the stomach, even in some of the most distressing cases that I have related, could digest any food; nor upon dyspepsia nor disease of the liver, and I there-

fore adopt Lobstein's opinion, that they indicate a state of suffering of the ganglionic nervous centre—"Hodie certissime evictum est, quod, tot numerosæ sensationes, quæ in epigastrio percipiuntur, neque ad musculos, neque ad vasa, neque ad organa gastrica sint referenda, sed unice ad plexum nervorum gangliosum, trunco cœliaco, insidentem, atque a Wrisbergio, summo cum jure *cerebrum abdominale* vocatum." At the same time it is evident that more or less ganglionic disturbance often accompanies disease of the stomach, liver, intestines, and of the womb. Romberg thinks "that the peculiar sense of fainting and annihilation accompanying the pain, is pathognomonic of cœliac neuralgia, and distinguishes it from neuralgia of the vagus," in which case there will be a sensation of stoppage in the œsophagus, of choking, or of scalding, rising from the stomach to the throat, with regurgitation of ropy mucus or vomiting; copious perspirations or a greater flow of urine. Pressure often relieves, though a slight touch may sometimes increase the pain. Women instinctively unfasten their clothes, and on account of their liability to gangliopathy, many of my patients have left off stays. The debility entailed by a severe attack of this disease is beyond the conception of those who have not witnessed it. A good night's rest does not restore the usual strength, which seems drained in its fountain head, and is not recovered till the patient has had several nights of sound sleep. The intermittent character of the pain has been well indicated by Schmidtman, *Per intervalla vexat cardialgia et remittet intermittetque.* I have seen the worst paroxysms of gangliopathy come on in the midst of perfect health and without any apparent cause, but I have seldom seen them assume the tertian type, said by Dr. Shearman to be of frequent occurrence. Whether the presence of sugar in the urine is a pathognomonic sign of neurosis of the vagus, as stated by Dr. Shearman, is to me very doubtful, on account of the intimate connection of the vagus with the cœliac ganglia, and this leads me to question whether the formation of sugar in the blood is not rather to be sought in that nervous system which is chiefly connected with nutrition; but this is a fit subject for future researches. Admitting, with Romberg, that the sense of repletion after taking a small amount of food, and the absence

of satiety after taking a large quantity, indicates hyperæsthesia of the gastric branches of the vagus, and that the accompanying sensations of burning or gnawing at the pit of the stomach, with overpowering debility, indicate cœliac neuralgia, the distinction has no practical bearings, as Romberg himself admits. At puberty, during irregularly performed menstruation, pregnancy, lactation, or the change of life, the pains at the pit of the stomach may be supposed to depend on hyperæsthesia or paralysis of the solar ganglia and cœliac plexus, particularly if the patient has been subject to causes likely to produce nervous affections, or to diseases of the sexual organs, if cerebro-spinal neuralgia coexist and has been intermittent, and if nervous symptoms be unexplained by organic lesions of the stomach.

When debility is intense it passes by a gradually sliding scale into the state called leipothymia by the older writers, and may end in the total extinction of vital power. Fainting is generally considered synonymous with syncope, whereas *syncope* is the failure of the heart's action, *fainting* is the sudden loss of ganglionic power, determining loss of consciousness; while *faintness* is the temporary depression of ganglionic power, consciousness being unimpaired. It is true that leipothymia and syncope may coincide, and produce each other; though in some of my severest cases of gangliopathy, I have seen fainting occur, consciousness diminish, and respiration imperfectly performed, while the heart's action was undisturbed. Dr. Copeland has already noticed this fact, and states, that in similar cases, he has even sometimes found the pulse to indicate bleeding. By *fainting*, I understand the "deliquium animi," or the "defectio animi," of Celsus, the leipothymia of Sauvages, whose definition is true to nature—"Subitanea et brevis virium dejectio, superstite pulsus vigore, et cognoscendi facultate." Syncope is rare at the change of life, whereas a frequent liability to fainting, occurred in 25 out of 500 women. M. S., aged forty-seven, frequently fainted from slight exertion at this epoch, but never swooned before cessation. S. A., a strong-looking woman, aged forty, was obliged to give up work six months after cessation, and for the first time in her life, because exertion brought on fainting, and irksome sensations of a load at the pit of the

stomach. She has several times fainted off for three-quarters of an hour. She is relieved by passing wind, is not dyspeptic, but nervous, and has globus hystericus. M. G. never fainted in her life until the dodging time, and then fainting fits occurred two or three times a week, for three years. A. L. frequently fainted before first and last menstruation, and during each menstrual epoch. C. S. had repeated fainting fits in the year following cessation. B. de Boismont has noticed fainting at the change of life, but he has not connected the comparatively rare cases of fainting with faintness, and the debility so often complained of; but I consider fainting to be linked, by insensible gradations, to the slightest sensation of epigastric faintness. The preceding considerations may throw light on some cases of sudden death, insufficiently explained by *post-mortem* examinations. Those who have written on ague, and more recently Dr. Handfield Jones, have noted the paralyzing influence of paludal miasma over nervous power. Sir G. Blane relates how the Walcheren patients, when in full convalescence, would unaccountably drop down dead: and in the hospital of San Spirito, at Rome, I have seen a man, recovering from pernicious fever, expire suddenly, without any *post-mortem* appearances being found to explain the cause of death. Some of the cases of sudden death in puerperal women, already in full convalescence, seem to me susceptible of being accounted for by the previous observations. A tall, thin, pale-faced, flaxen-haired, inanimate lady had been confined a week, and was doing so well that her accoucheur had ceased his daily visits, when, on sitting up to take her usual food, she fell back, and suddenly expired. No clot in the pulmonary artery, nor anything else was found to explain this event, except a somewhat flabby state of the walls of the heart.

As women grow old, all the ganglionic nervous affections abate, except debility, which may persist, to a variable degree, until death occurs from the extinction of that amount of power allotted to the ganglionic system.

Chlorosis is another form of debility, of which the late Dr. Merei affirmed that it is one of the most extensively diffused pathological conditions of the present age. It is,

doubtless, most frequently met with in the years which follow puberty, but all should recognize its frequency at the critical periods of women's reproductive life. Caseaux has pointed out its occurrence during pregnancy; Blaud admits it to be more common than is generally believed among adults; Dusourd has recognized it, at the change of life, and I have noticed it in 40 out of the 500 tabulated cases. Indeed, every one must have noticed the altered appearance that will sometimes take place at that period, the change of skin from a healthy hue, to the waxy, sallow tint, the bloodless lip, the pale white of the eye, with headache, pseudo-narcotism, and general debility. Leaving out of the question all cases in which anæmia was caused by flooding, it is well proved that puberty, pregnancy, lactation, and cessation may cause the relative proportions of the blood globules to fall low enough to produce chlorosis. This is doubtless a blood disease, but it originates in some peculiar loss of power of the ganglionic nervous system which moves the bloodvessels and vitalizes the blood. I have long believed, with Dr. Joly, of Paris, that chlorosis is a neuralgic affection of the ganglionic nervous system; and, while admitting with Dr. H. Jones, that in many cases of chlorosis occurring amongst the poorer classes in London, the action of malarious influences upon the ganglionic system is the first link in the chain of causation, such cases must not be severed from others equally frequent, wherein chlorosis arises under the healthiest circumstances and in the wealthiest families, showing that the ganglionic system may spontaneously develop the disease. At the change of life, as at puberty, the nervous energy of the ovaria is below par, or too great, and the epigastric centre, being morbidly influenced, is unable to promote the healthy performance of nutrition, so the blood is impoverished and the whole system suffers.

Therapeutics.—The cases related in this chapter show that gangliopathic affections are to be cured by sedatives, alkalies, by promoting the action of the skin, and by tonics; but I shall more particularly allude to these medications, and mention several remedies not yet alluded to by me. And to

begin, I cannot sufficiently praise the utility of sedatives applied to the pit of the stomach.

The common consent of mankind, the convictions of many illustrious men, and the facts recorded in this chapter, go far to prove that, in the epigastric region, there is a real centre of nervous power, and I therefore seek to act upon it, by such remedies as seem likely to increase or diminish this power, or to regulate its disordered action. This should be done, if only to relieve the painful, distressing, and unaccountable sensations experienced by patients in this region; but being firmly convinced that this ganglionic nervous centre is in constant action and reaction on the brain, and having so often seen it derange more or less severely the mental faculties, at puberty, during pregnancy, puerperality, lactation, and cessation, I deem it imperative to apply remedies to this centre. Another important reason for trying, in every way, to relieve epigastric pain and anomalous sensations at the change of life, is, that women will not long endure these sufferings without seeking relief. If medicine does not relieve them, they will instinctively fly to stimulants, the poor to porter and gin, the rich to wine and brandy. Is it not then better to endeavor to alleviate these distressing symptoms by medicine, than to let women run the risk of becoming gradually addicted to deplorable habits?

The chapter on the general treatment of diseases at the change of life should be borne in mind, inasmuch as local applications can be of little utility without constitutional treatment. When the mild forms of cardialgia are presented, the epigastric uneasiness, the sinking and faintness, I first ascertain whether these sensations coexist with foul secretions requiring purgatives, before ordering my sedative mixture before meals, the alkali after meals; 3 grs. of blue pill and 2 of ext. of hyosc. every, or every other night; a mustard, or a hot linseed meal poultice, sprinkled with coarsely-powdered camphor, and a teaspoonful of laudanum every other night; dry cupping, as recommended by Galen, and a piece of piline, or a camphor sachet, to be worn during the day on the pit of the stomach. If the pains continue, I prescribe a belladonna, or an opium plaster, which is to be left on, and should it fail

to relieve, I renew it every fourth or fifth day, or I apply two; one to the pit of the stomach, and the other to the opposite region of the spinal column; or I order alternately, an opium or a belladonna plaster every fourth day. I often prescribe 2 grs. of sulphate of atropia with 4 of acetate of morphia, to 1 oz. of stiff glycerine ointment, and I tell the patient, to spread about the size of a small filbert, on a bit of Mackintosh calico, and to apply it to the epigastric region. This can be taken off the following morning, and reapplied to the same region, after spreading some more ointment on the calico. When the atropia affects the eyes, the application should be omitted until vision is fully re-established, when, if necessary, it can be reapplied every second or third night.

Extract of belladonna in frictions, and taken internally in 1 gr. doses, has already been recommended by Dr. A. Bayle in his *Eléments de Pathologie Générale.*

If, besides the sensation of prostration, there be downright pain, resisting the local means previously detailed, I have sometimes, with benefit, applied a piece of lint steeped in chloroform, and covered with oil-silk, to the pit of the stomach, retaining it in its place by a bandage. A blister, though often ineffectual, has sometimes relieved the pain; and this reminds me that Comparetti and Barras derived no benefit from blisters in similar affections they attended, at Venice and at Paris; neither did Lorry. In the worst cases of cardialgia, where there were fits of agonizing epigastric pain, its intensity was often abated by taking from 30 to 60 drops of aromatic spirits of ammonia in the smallest possible quantity of water; or from 10 to 15 minims of chloroform on a lump of white sugar, and melted in a little water; or by chloric ether; or by 20 drops of sulphuric ether in one ounce of which a drachm had been dissolved; or by a drop of essential oil of peppermint, on a lump of sugar, and dissolved in water. In some cases the paroxysm would take its course, and abate of itself; in others, all milder remedies failing, I have denuded the skin of the epigastric region to the extent of a crown piece, by strong blistering tincture, or placed on its surface a piece of linen wetted with strong spirits of ammonia, applying afterwards from 3 to 6 grs. of acetate of morphia, and I have also derived

benefit from the hypodermic injection of morphia. Veratria and aconitine are also invaluable agents in difficult cases. I have employed them externally, as Dr. Turnbull has done in other affections, incorporating the active agent with lard, 1 scruple of veratria, or 1 gr. of aconitine to 1 oz. lard, directing a piece, the size of a filbert, to be rubbed on the epigastric region, for a quarter of an hour, until warm and pricking sensations were excited, and this may be repeated, every second or third day. Trousseau and Mathieu thought highly of this method of applying veratria; and a liniment composed of ext. belladonnæ, ʒss.; tinct. aconiti, ʒiv, and liniment. saponis comp. ℥iss. may be useful.

If there be nervous irritability and sleeplessness I give one or two 3-grain pills of ext. of hyoscyamus every night, and if that does not do, 5 to 10 grains of Dover's powder, or 20 minims of the British Pharmacopœia solution of acet. of morphia, with 20 minims of ipecac. wine, and in exceptional cases the 16th of a gr. of acet. of morphia every one or two hours, until the induction of drowsiness.

Dehaen, Barras, and many who have paid attention to the obscure affections under consideration, praise equally with myself, the internal and external exhibition of opium, hyoscyamus, camphor, and cherry-laurel water. Dumas, of Montpellier, frequently prescribed the 15th part of the following compound to be taken daily, for nervous affections of the abdominal organs:

Castor, ...	30 grs.
Camphor, ...	15 "
Opium, ...	8 "
Conserve of roses, ...	q. s.

Indian hemp alone, or associated in pills with extract of henbane, is invaluable to quiet nervous symptoms; the same may be said of bromide of potassium, and I have given ten grains of chloral three times a day with benefit, and I think it will turn out to be a valuable ganglionic nervine. Neither should I omit to mention, while writing of sleeplessness, in connection with gangliopathy, that a friend of Dr. Handfield Jones has found a sinapism to the epigastrium, to give sleep

when many other remedies had failed to relieve the insomnia of insanity.

Emetics are heroic remedies in a host of nervous affections, in long-continued globus hystericus, in spasms of the œsophagus, in nervous aphonia, in hysterical pains, or semi-paralysis of limbs; and as they frequently cure, without the removal of bile, they probably act by suddenly breaking in upon a morbid condition of the cerebral and ganglionic nervous forces, and promote their healthy equilibrium. When, however, there is great debility in connection with the distressing epigastric sensations which I have described as gangliopathy, emetics do harm, and Joseph Frank, who was in Vienna, when Stoll's theory was in full force, mentions having seen the ill effects of emetics in such cases.

With regard to tonics, when gangliopathy predominates, I rely on good food, wine, and mineral acids, while the menstrual flow is still making irregular appearances. Mineral acids improve digestion, restrain irregular hepatic action, and cool the skin, often teased by heats and flushes, and in support of my practice, I may mention that Hufeland gave Haller's elixir in diseases of the change of life. Acetate of lead, in one-sixth of a grain doses, has been frequently given, with success, by J. Frank, in cases of cardialgia caused by onanism, and accompanied by spermatorrhœa; but I have never tried it. J. Frank considers that the principal remedy for neuralgia of the cœliac plexus is oxide of bismuth, the third of a grain being given two or three times a day; and that the "oxide of bismuth and nitrate of zinc have a decided influence on the nerves of the stomach, appeasing the nervous affections of the cœliac, and of the abdominal ganglionic plexus." Hufeland writes favorably of hydrocyanate of zinc, in 1 to 4 gr. doses, two or three times a day, but I prefer the valerianate of zinc. Nitrate of bismuth is frequently given in 10 to 20 gr. doses, suspended in a little mucilage, and should be taken on an empty stomach.

Oxide of silver has been given by Sir J. Eyre and Dr. Davey; in recommending nitrate of silver, Dr. H. Jones correctly remarks, that, when only taken for a fortnight, there is no danger of the skin being darkened. Dr. Shearman gives half a grain of nitrate of silver, with the same quantity of

opium, and 5 grains of ext. of camomile, three times a day; sulphate of quinine, dissolved in an acid mixture; and ʒj. doses of solution of potash, to prevent the formation of sugar in the urine.

There is a general concordance of belief on the part of good observers in the power of strychnia to rouse and increase nerve force, and I give it when great loss of nervous energy is not associated with anæmia or chlorosis. The powder of nux vomica in 2 gr. doses, or its ext. in a 1 gr. dose, was strongly recommended by Schmidtman. Dr. Davey gives strychnia, and Dr. H. Jones writes encouragingly of it. I prize arsenic more and more as a nerve-tonic, at the change of life. Dr. H. Jones praises it in cases similar to those I have been describing, and if Dr. Leared has found it so useful in cases of confirmed dyspepsia, it may be the drug acts by toning the nerves, in and around the stomach. I have seldom given digitalis at the change of life, but its power to strengthen and regulate the heart, when given in small doses, fully warrants its more extensive trial in visceral neuralgia.

When, after cessation, there is a tendency to anæmia or chlorosis, I give quinine and iron, varying the preparations in the same case, but never giving large doses. Comparetti and Barras speak highly of ice, to calm pain in spasmodic affections of the stomach, to increase the sensation of strength, and the peristaltic movement of the intestines. This reminds me that, in some severe cases, when the patient could not swallow cold water, or anything warm, there was a strong inclination for ices; which, as well as Nesselrode pudding, could be easily swallowed, and the pain was for a time relieved. Intense heat is as serviceable in this, as in other neuralgic affections. The actual cautery and moxas to the pit of the stomach have been used in olden times, so transcurrent cauterization might now be useful. The Chinese relieve cardialgia, by plunging acupuncture needles into the epigastric region. And lastly, there is electricity, for the application of which we have Pulvermacher's chains, one end of which is to be applied to the pit of the stomach and the other to the corresponding point of the spinal column or to the nape of the neck. Any other mode of applying electricity to the epigastric region, cannot be done too cautiously, or the result might be fatal.

CHAPTER VII.

DISEASES OF THE BRAIN.

TABLE XXV.

Frequency of Cerebral Diseases in 500 Women at the Change of Life.

Nervous irritability,	459
Headache,	208
Monthly headache,	7
Sick headache,	92
Hemicrania,	3
Apoplexy and hemiplegia,	6
Pseudo-narcotism,	277
Hysterical state, or hystericism,	146
Hysterical fits, since cessation only,	3
Globus hystericus, since cessation only,	17
Laughing and crying fits, since cessation only,	4
Monthly hysterical symptoms,	1
Hysterical flatulence,	8
Prolonged fits of unconsciousness,	3
Epilepsy, since cessation only,	3
Epilepsy, much aggravated,	5
Delirium,	3
Insanity,	16
	1261

Thus 500 women divided 1261 forms of cerebral disease, many of them presenting several of these nervous symptoms at the same time, and this confirms the general belief in the frequency of cerebral affections at the change of life. After cessation, the liability to nervous affections greatly decreases; headache, nervous irritability, and pseudo-narcotism, have

seldom the same intensity; and if cerebral hemorrhage, apoplexy, and softening of the brain become more frequent, it depends on pathological conditions common to both sexes, in old age. A glance at the preceding table will show that at the change of life, women suffer chiefly from functional diseases of the nervous system, which explains why the mortality from cerebral diseases, according to the Registrar-General's reports, is always greater among men, than women from the twentieth year and upwards.

Of those who confirm my assertion, Gardanne and Dr. Ashwell state, that even when most favorably passed, the change of life brings with it a train of nervous symptoms. Gardanne and B. de Boismont speak of the tendency to headache; Dr. G. Bedford alludes to the frequency, the intensity, and eccentricity of the nervous symptoms at this epoch; and B. de Boismont thinks transitory delirium and insanity then of frequent occurrence. I believe that many women, are thoroughly unhinged by the change of life being left to take its course. Eccentricity embitters their existence and the lives of those around them; and should they lose fortune or friends, they may become insane, or may be thought so, erroneously, by relatives; hence arise scandalous suits, and the squandering of fortunes among lawyers, while all this might have been prevented by the systematic treatment of nervous symptoms when they first occurred. I cannot repeat too often that this crisis, like puberty, weighs upon the subsequent lifetime of women, and, thus considered, the nervous symptoms of the change of life assume vast importance. I shall now pass in review—1stly. Nervous irritability, the groundwork of all cerebral diseases; 2dly, Cerebral neuralgia; 3dly, Pseudo-narcotism; 4thly, Hysteria; 5thly, Epilepsy; 6thly, Insanity; and to understand these affections better, I shall throw on them the light derived from their study, at other phases of the reproductive function, and, after giving facts and the results of experience, attempt to account for their production and discuss their treatment.

1stly. NERVOUSNESS AND MORBID IRRITABILITY.—By this is meant that the nervous system is more than usually suscepti-

ble to external impressions, such as cold, light, noise, to the stimulus of diseased viscera, and to that of emotion. There are not only innumerable degrees, but various modes of nervousness. If patients are asked if they are nervous, they understand the term to mean hysterical, and are often indignant at the question, though they will readily own that they cannot bear the slightest noise, although not over-sensitive to emotional stimuli. In some, the temper remains unruffled, but they are ready "to jump out of their skin" at the jarring of a door, and are in agony at hearing the leaves of a book turned over. To some it is torture to hear others converse; others say, that on the most trivial occurrence, they "feel pulses beat all over them;" they "feel all of a tremble, all of a shake;" "my flesh feels so heavy upon me," said one Dispensary patient, and "sensation is my calamity, not pain," was the eloquent expression of another; while one could not "stop in church because she felt the people too close." The fidgets—the *anxietas tibiarum* of nosologists—are a very frequent expression of nervousness. They indicate *nervous plethora*, seeking to be relieved by exercise or muscular action. Although one cannot determine the anatomical conditions of the nerves, when they are the seat of nervous congestion, I think it should be admitted as much as the congestion of bloodvessels by blood. The nervous fluid is too subtle to be seen or felt, but from the effects produced, the mind can deduce the fact of its being too abundant. I first allude to this nervous irritability because it is the "materia prima" of all nervous affections, the basis on which they rest, and the soil in which they grow; but to speak of nervousness as *hysteria*, is to perpetuate the state of confusion out of which the pathology of the nervous system has scarcely emerged. The last table shows the frequency of nervous irritability at the change of life, and I believe it to be then, as at puberty, of almost constant occurrence, just as frogs are more susceptible to electrical influence every returning spring.

2dly. HEADACHE.—Our poverty of language for cerebral diseases, is shown by the fact that we are obliged to give the same name, to an indisposition that does not interfere with

habitual pursuits, and to something that will keep a patient in sleepless agony for two or three days. Headache is a very frequent symptom at the change of life, as at puberty. It occurred in 208 of my cases. Some like E. P., aged fifty-five, never had a headache until cessation, but have ever since suffered from it more or less. In another patient headache was the prominent symptom at menstruation, parturition, and at cessation; a dull heavy kind of pain, with pseudo-narcotism which lasted more or less for six months. With regard to its seat, it may be met with in the following order of frequency—viz., in the temple and forehead, at the top of the head, and at the occiput. The last-named places have been noticed by Friend, Etmuller, and others, as most habitual. I have rarely met with it in the occiput, though if Gall's localization were correct, that should be its most frequent seat. With regard to the nature of this pain it is described as "shooting," "throbbing," "gnawing," "burning," or as "if the head were in a vice." It varies in intensity, from that slight amount which merely inconveniences, to that agonizing pain sufficient to prostrate a hard-working woman and make her lie by, for some days. In ninety-two cases, the patients suffered from sick headache without any signs of gastric disease, and mucus was alone brought up; and need one be surprised at sickness sometimes accompanying cessation, when it often accompanies puberty, and sometimes attends each menstrual flow? Headache may, doubtless, be caused by plethora, but generally it is a nervous symptom and behaves as such. I have had frequent opportunities of observing the alternation of violent hemicrania and gangliopathy, the one arising as the other abated; I have also witnessed a marked antagonism between the cerebral and pelvic extremities of the spinal cord, the violent headache subsiding as pain became intense in the sacrum; and as a general rule those who suffer much from cerebral, are less troubled by pelvic pains.

Case 22.—*Periodical headache at cessation.*—Sarah T., a tall, stout woman, with the capillary vessels of the cheeks very apparent, looks nervous and as if going to cry, was fifty-six in September, 1855, when she came to the Farringdon Dispensary. The menstrual flow appeared at sixteen, and

left gradually at fifty-one, after dodging her for a year. She then suffered for a twelvemonth from flushes and perspirations, particularly at meals; otherwise she was pretty well all day, but at two o'clock in the morning a severe headache generally awoke her from a sound sleep. This occurred "off and on, for two years after cessation," says the patient, and her account is confirmed by her daughter. The sudden loss of her husband induced great debility, and caused the flushes and drenching perspirations to return, four years after their subsidence.

Dr. Teissier, of Paris, has published—*Gaz. Méd. de Paris*, 1851—a case of periodical hemiplegia. A lady, sixty years of age, becomes unconscious every month since the cessation of menstruation and at the period she had been accustomed to menstruate. On recovering her senses one-half of her body is paralyzed, and her speech is affected. This continues for several days, and gradually disappears to return at the next monthly period. Being naturally of a calm and tranquil disposition, those about her know when the attacks are coming on, by her agitation and restlessness.

Case 23.—*Cerebral Neuralgia.*—I have related in my handbook of "Uterine Therapeutics," how, after having enjoyed tolerable health till the fortieth year of her age, a lady began to suffer from chronic inflammation of the womb, which increased nervous excitement and occasionally caused hysterical fits and vomiting that resisted all approved remedies, and only yielded to the application of an issue at the pit of the stomach.

On menstruation ceasing in her forty-eighth year, the patient still suffered occasionally from vaginitis and exulceration of the cervix with a yellow discharge, but she became less nervous and had no more hysterical attacks, which were replaced by maddening attacks of pain in the head, coming on every second or third week, and obliging her to remain for twenty-four hours in a dark room. During three years a host of remedies were tried in vain; among those given internally were the salts of zinc, Indian hemp, and bromide of potassium, while chloroform, the deutosulphide, and the tetrachloride of carbon were tried as outward applications to the nape of the

neck, and to the temples; an occasional application of leeches to the temples doing more good than any other remedy, while the neuralgic nature of the complaint was shown by the fact that no severe attack occurred during a six weeks' stay at Birkenhead; the attacks returning when she came back to her own healthy and comfortable home. After this state of things had lasted about two years, Dr. Russell Reynolds met me, and we agreed to consider the case as one of those unsatisfactory ones, in which pain seemed to depend on perverted cerebral nutrition, the result of chronic disease and its unhealthy necessities, and he suggested alteratives and tonics, and whatever exercise could be taken. The sudden loss of a husband, leaving her less well provided for, than she had a right to expect, and subsequent pecuniary losses, will account for the cerebral attacks becoming severer and more frequent. They often lasted forty-eight hours, with little abatement of pain, with a considerable amount of salivation, and incessant desire to pass a very large amount of scarcely colored urine; and as there were often two attacks a week, they told very unfavorably on the memory of the patient, and on her power of attention: and she had also lost flesh, although digestion had improved. Such was the state of the case when Dr. Livingston, of New Brunswick, wrote to suggest the trial of tincture of aconite in a solution of hydrochlorate of ammonia, and I first tried scruple doses of this salt, three times a day, for a fortnight without any good effect, and on the 30th of last October I tried the tincture of aconite, beginning with five drops, but pushing on rapidly to twenty drops three times a day. After she began to feel fulness in the throat, and tingling in the tongue, the attacks ceased for a month, when came a desperate one. The aconite was continued, and again there was no attack for another month, when two occurred. I increased the aconite to seventy-five drops in the twenty-four hours, and there were no attacks for three weeks, and then two in succession. I diminished the dose of tincture of aconite to twenty drops three times a day, as the larger dose was disagreeable to her. Although the aconite has thus checked the frequent recurrence of the terrific hard attacks, never a day passes without headache, and about three or four o'clock A.M.

the patient begins to bathe her head with Raspail's lotion, which she has found to be the most effectual of all milder measures, and in the afternoon she feels better and brighter. The respite given to the patient, by the aconite, has permitted her to follow out more fully the advice repeatedly given to her, to get out every day, and to mix more with society.

A fortnight after a previous attack came one which lasted four days. The skin was hot, the lips parched, the pulse at eighty, the eye deep sunk. There was a sensation as of blood rushing to the brain, and this was but slightly relieved by six leeches to the temples, although the loss of blood was considerable. At the next attack she took a whiff of nitrite of amyl, which frightened her by the prostration it produced. Chloral in doses of twenty to forty grains gave a certain amount of unsound sleep, and a different kind of headache, with painful congestion of the sclerotics. Dr. Russell Reynolds advised placing the patient under the influence of atropia during the attacks, but the effects were so disagreeable that the patient would not long take it. He likewise advised the arseniate of iron, which was taken for two months; it did no good, and assuredly caused a spasmodic cough, which only desisted on lying down. Now this patient is taking a combination of sumbul and bromide of potassium, at Dr. John Ogle's suggestion, but with questionable utility. The right remedies are not always attainable, and doubtless a pleasant companion to enliven solitary meals, and plenty of travelling, would do more good than medicines.

3dly. PSEUDO-NARCOTISM.—The following cases will show the meaning I wish to convey by this term.

CASE 24.—*Pseudo-narcotism.*—Mary H., very stout, middling stature, sanguine temperament, flushed face, heavy eyes, uncertain walk and attitude, with all the appearance of being intoxicated, was sixty, when she came to the Paddington Dispensary, September 24th, 1849. The menstrual flow appeared at eleven with giddiness and sleepiness; it continued regular and abundant, though always accompanied by "a drowsy giddiness," for which she was often bled and cupped. She married at twenty-one, and had a child at twenty-six. The dodging time began at forty, and lasted until fifty-eight, when ces-

sation occurred. During these eighteen years the menstrual flow was irregular, being sometimes very scanty; at others, a flooding. She was also troubled with leucorrhœa, bad back pains, faintings, flushes, sweats, headaches, and was so giddy that she frequently tumbled down, and people thought her tipsy. When walking out, she was always obliged to get near the railings, so as to have something to hold by. She said she never drank anything but cold water, and her landlady confirmed her statement. At about fifty-eight, when the flow stopped, she was at St. George's Hospital for ascites and boils. Diuretics considerably reduced the ascites, and for the last six months she has suffered more from cerebral symptoms. Intense headache, with pain, and singing in the ears, pains in the eyes, chills, and flushes, are now most distressing; and the perspiration trickles down her face. Every twenty-eight days these symptoms are very troublesome, and remain so for a few days. She has been unable to do any regular work for five years. I had eight ounces of blood taken from the patient, ordered a brisk purgative, to be repeated every week, several glasses of cream of tartar lemonade to be taken daily, and warm pediluvia every night. By following this treatment for a few weeks, the case was greatly improved; but she would not allow the bleeding to be repeated, whereas if ever there was a case in which bleeding would have been beneficial it was this; for she was of full habit, bore bleeding well, and the menstrual flow had always been abundant; three to four ounces of blood should have been taken from the arm every month, for the first two months, then every third or fourth month, with baths, purgatives, alkalies, and mild sedatives. This is one of the most marked instances of pseudo-narcotism I have met with. It appeared with first menstruation, returned at every menstrual period, and completely incapacitated the patient from earning her livelihood for five years.

What name then is to be given to this nervous affection? If it be called congestion of the brain, there were no signs of this condition in the following case, in which the nervous symptoms were similar:

Case 25.—*Pseudo-narcotism.*—Mary G., thin, tall, with dark hair, delicate complexion, drowsy look, and, when roused,

looks as if she expected to see something dreadful; was forty-nine and unmarried. The menstrual flow appeared at fourteen, and continued regular, with little pain or other disturbance until the last two years, when it became irregular, and like "brown cinder dust." She also became unusually nervous, "feels silly, as if her head were one dead lump," and "five minutes after putting things away, she forgets where she has put them." More than once, she has lost her way in streets well known to her. She sleeps all night, wakes unrefreshed, often falls asleep during the day; sometimes feels stunned, and loses her senses for an hour. She complains of a *hot* pain at the pit of the stomach, with frequent sensations of sinking, which pain is worse after eating. She will stop three days without food, and then eat ravenously. For the last six months the bowels have been costive, and for the last two years, she has been troubled with flushes and sweats. I ordered the comp. camph. mixt. before meals, the carb. of soda after, 3 grains of blue pill, and 2 of ext. of hyoscyamus every night, also 10 grains of Dover's powder, a large belladonna plaster to the pit of the stomach, with hot pediluvia every night. This was continued for a week, and I never saw greater improvement in so short a space of time. The eyes seemed at peace with surrounding objects; she looked cool, comfortable, and self-possessed; she had lost her strange feelings, and was less drowsy during the day. The improvement was lasting; and I only saw the patient now and then, when there was a slight return of the head symptoms. Pseudo-narcotism is generally allied to other cerebral symptoms, but in this case it was not obscured by other symptoms; for there was no headache, sick-headache, or hysteria. Again I ask, what is the name of this nervous affection? Congestion of the brain? There was none. Anæmia? There was none. Neither can it be called hysteria, unless by adopting the common custom of calling *hysteria* any nervous affection that is little understood. I say that these patients suffered from pseudo-narcotism; and if it be urged that it is useless to give a new name to exceptional cases, I reply that this affection is common at all the critical epochs of woman's life, espe-

cially so at the change, when I observed it in 277 out of the 500 cases.

At puberty, girls previously lively and clever, often become stupid and useless when sent on a message, as they forget what they were sent for, or how to come back; or when at home, they will let things fall out of their hands, and fall down in stooping to pick them up. Pseudo-narcotism is often very intense when the menstrual flow is either very painful, deficient, or completely absent. I have known intense pseudo-narcotism, resulting from amenorrhœa, mistaken for an idiopathic affection of the head in a girl of twenty-one. Her head was shaven, and she was bled and salivated, to the ruin of her constitution. N. G., at menstrual periods, could almost sleep while walking, and once remained sixteen hours in a state of stupor, from which she awoke quite well. K. R., at menstrual periods, would remain for hours in what she called her "quiet fit," a state of self-absorption, unaccompanied by hysterical phenomena, or by convulsions. Such examples of pseudo-narcotism are fortunately rare, for they present the extreme of what may frequently be observed. The ordinary symptoms are, a great tendency to sleep, an uneasy sensation of weight in the head, a feeling as if a cloud or a cobweb required to be brushed from the brain, disinclination for any exertion, a diminution in the memory and in the powers of the mind. But whether slight or intense, the symptoms indicate different degrees of the same cerebral affection which I have described in the patient's own words. They represent the diminished degree of that hysterical coma, in which, says Pomme, some would have been buried alive had he not interposed. A high degree of pseudo-narcotism is sometimes the immediate consequence of connection. This was always the case in a patient of mine during the first year of marriage. Sometimes she would recover from it, in half an hour or an hour, sometimes the morbid would merge into the natural sleep, being followed by headache and prostration of strength during the following day, and I have repeatedly met with patients in whom connection brought on sound sleep which could not be obtained from drugs. During pregnancy, the milder forms of pseudo-narcotism are frequent. The heaviness of head, the dulness

of intellect, the giddiness, the tendency to fall, which are often erroneously considered symptoms of plethora, used formerly to be treated by venesection. S. C. always knew herself to be pregnant by feeling heavy in the head, giddy, and by very sleepy sensations which augmented as she increased in size. In P. N. there was no pseudo-narcotism at the menstrual epochs, but much during pregnancy.

The milder forms of pseudo-narcotism are amongst the symptoms of over-lactation. Physiognomists will be struck by the appearance women frequently present at this period, their uncertain step and tottering gait, their vacancy of feature, the drowsy or drunken expression of the eyes, and the efforts they make to recover their oppressed intellects when aroused by a question. When asked what they feel, they complain of "heaviness in the head," "a stupid feeling," "a lump in the head," "a stupid headache," "a numbness in the head, not pain," of "feeling silly," "stunned," and "the head like a dead lump." Some talk of "an impulse to fall forward," they "are often giddy even in bed." Others complain of "senselessness," of "feeling lost and bewildered," "of a temporary loss of wits," "of the fear of going mad."

At cessation, the temporary loss of memory is sometimes a most distressing symptom. Patients forget where they have put their purse, keys, or things they are in the habit of using, a few minutes after putting them away. "I write everything down, or I should forget it," says one patient; and another, "I am obliged to stop and ask myself if I am doing what is right." One was so forgetful that she habitually made her children remind her; some forget their way home and even their own names. Patients say they feel so "sleepy and dreamy-like," "heavy for sleep, but without pain," "can sleep anywhere," "can hardly keep the eyelids open," and are "so sleepy they could drop off their chairs." In a few cases, however, I have noted *sleeplessness*, as in M. C., who says, that her head feels so funny when the time for the menstrual period comes round, that she cannot sleep for three or four days. Some patients feel as if they had taken too much, as if something had got into their head; they are accused of being tipsy when holding by the rails they pass in the streets; they

have been turned off as drunk, or at least are not allowed to open the door to visitors by a master anxious to save his servant's reputation. Pseudo-narcotism is most frequent and severe at the change of life, while hysteria is rare, but it may alternate with hysteria or gangliopathy, as in M. J., who, at this epoch, suffered severely from dull pains in the head, on the subsidence of which she could sleep anywhere. The nervous system of some women is so sensitive to the disturbing influence of the ovaria, that they have begun to be pseudo-narcotized at eight, and this has continued, more or less, until cessation. In advanced life, pseudo-narcotism becomes less frequent, less intense; should the contrary occur, it denotes a liability to insanity, as in A. H., who ceased fifteen years ago, but who is so sleepy she seldom rises before 5 P.M.

I have hitherto kept the results of my own observation clear from what stands on record: but lest it should appear that I have been too much struck by exceptional cases, I shall now show that esteemed authorities have met with cases similar to mine. They have not, it is true, drawn attention to the minor degrees of pseudo-narcotism, being satisfied to consider them as symptoms of hysteria, but they have noted the coincidence of prolonged sleep or coma with amenorrhœa, pregnancy, lactation, and cessation. Dr. Sandras, of Paris, gives instances of its occurrence in both married and unmarried chlorotics. Dr. Villarty de Vitré has made known—*Union Médicale*, tom. v—a curious case of lethargy, occurring regularly, every month, in a girl suffering from amenorrhœa, the attack lasting seventy-three hours; the lethargic state disappearing when the menstrual flow was restored. Dr. Copland notices coma, as a symptom of severe hysteria, in plethoric subjects, and in pregnancy; and he mentions its occurring from the suppression of the menstrual and of the lochial flow. Montfaucon states, that in some cases of hysteria the principal symptom was continued sleep, lasting for several days, and only interrupted to take food. Pomme, who had a large acquaintance with nervous disorders, makes the following remarks: "L'hystérie est quelquefois accompagnée par une sorte de sommeil profond, qui prive les malades de tous sentimens. Elles perdent quelquefois connaissance aussi subitement que dans l'ap-

oplexie, ce qui en a imposé plus d'une fois à ceux qui négligent d'examiner alors l'état de la mâchoire, qui est en convulsion dans l'accès hystérique." Tissot, and those who have written on onanism, relate that some of those addicted to it, do not sleep at all, while others are almost always in a state of stupor. Mr. A. Hunter—*Annals of Medicine*, 1799—Mr. Blake and Dr. Montgomery have cited cases where pregnancy was accompanied by very great drowsiness; and in Dr. Montgomery's case the patient's memory was a perfect void, during the whole time of her pregnancy. Dr. Reid relates the case of a woman who was always able to judge pretty correctly of the time of conception, by a peculiar sensation of drowsiness, attended by sickness, with which she was then affected. J. Frank has known pregnant women to sleep eighteen out of the twenty-four hours, and he remarks that some women can distinguish fruitful connection by symptoms which seem to imply a narcotic influence in the spermatic fluid; but independently of conception, I have known connection give sound sleep when opiates could not. Baudelocque mentions the fact of women about to be taken with fits of eclampsia being thought drunk by the inexperienced; and although this disease may appear without prodroma, still heats and flushes, giddiness and bewilderment, are often its precursory symptoms. Soporous affections have been noticed at the change of life by Chambon; and Tissot says, "I have seen one of the most reasonable and witty women I ever knew pass two years of her life, at the cessation of menstruation, in a constant dream of a calm and gay character like her own habitual disposition. She was at the same time so troubled with the fidgets, that she could only remain sitting for ten minutes at a time, and if she persisted in doing so longer her sufferings were intense. Her nights were often sleepless, and remaining in bed was painful to her."

It is well to bear in mind that nature is immutable, that observers record the same facts, although they differ in their mode of interpretation, and I cannot better conclude these citations than by a case, related by Pomme, of periodical pseudo-narcotism in a young lady.

CASE 26.—*Successive fits of coma at menstrual periods.*—Mdlle. ——, aged eighteen, sanguine and nervous, was suddenly affected with a lethargic drowsiness, when the menstrual flow should have come on, which symptom was alleviated by bleeding. At the following monthly period the drowsiness came again, but with greater intensity, and bleeding was again resorted to, but it failed to relieve her, so was not tried at the third and following menstrual periods, when the same lethargic state occurred, instead of the menstrual discharge. The drowsiness was followed by hysterical delirium; she became violent, and refused all food for seventeen days. Pomme put her, by force, into a tepid bath, and after remaining in it twelve hours, she quieted down, and took food. For two months she stopped daily eight hours in the bath, cold applications being made to the head; the delirium then disappeared, and the menstrual flow came.

The fact of morbid sleep being so frequent a symptom of the disturbed performance of the reproductive functions, tempts me to say one word on sleep as a physiological phenomenon. As sleep is often produced by the morbid action of the ganglionic nervous system on the brain, it is fair to ask, whether this nervous system has nothing to do with the production of our daily sleep? I think that a good theory of sleep should take into consideration the influence of the ganglionic nervous system in its production; and without attaching too much importance to a singular case, it may be mentioned that, in 1824, at the great hospital at Vienna, Joseph Frank saw a man who, for many years, passed all his time in sleeping. When his body was opened, the only unusual appearance was a considerable hypertrophy of the semilunar ganglia of the cœliac plexus, and of the other divisions of the great sympathetic.

I said that the singular cerebral condition described by me has no name, but is confounded with hysteria, with which it has nothing in common, or with coma, a disease of rare occurrence, which may be the result of some other affections. I have, therefore, given it a name, because new words are justifiable, when they serve to specify the nature of things. Sir H. Holland has observed that, the difficulty of getting a correct nomenclature for morbid sensations, applies particularly to the

cerebral. "Nervous stupor," or "spontaneous narcotism," would be good terms, but as the symptoms are similar to the gentle or powerful effects of narcotic poisons on the brain, I have applied to this group of cerebral symptoms the term *Pseudo-narcotism*, thus graphically expressing the fact, without prejudging the question.

4thly. HYSTERIA.—Medical writers should be careful to explain their meaning when using the term hysteria. When Dubois d'Amiens, Vigaroux, Béclard, Gardanne, and B. de Boismont say, women are not subject to hysteria at the change of life, and F. Hoffman, Pujol, and Meissner, say that they are, what do they mean? Do they mean that they are not subject to globus hystericus, and the minor symptoms of hysteria, or that they are not subject to hysterical fits? A glance at the table that heads this chapter will enable the reader to decide the question relating to the frequency of hysteria at cessation; for out of my 500 cases, 146 who had suffered more or less from globus hystericus and the minor symptoms of hysteria still continued to suffer from them at the change of life; and, for the first time after cessation, seventeen had globus hystericus, and four had repeated laughing and crying fits, whereas only three had hysterical fits. In several of these cases, globus hystericus was so severe as to make the patient jump up in bed, for fear of being suffocated. Landouzy gives a table showing that, out of 351 cases of hysterical fits, twenty-five only occurred after the fortieth year, and that they are very rare before puberty. Out of 821 cases of hysteria observed by Georget, Briquet, Landouzy, and Beau, only twenty-one originated from the fortieth to the fiftieth year, while 259 began from fifteen to twenty, and 574 from ten to twenty-five years of age. With regard to the effects of the social position, hysterical symptoms are much less common among the poor, and they occur most frequently when the nervous system of woman is wrought up to an artificial state by luxurious living, by overworking the mental faculties, and still more by the over-development of emotion. With regard to the influence of temperament in producing hysterical phenomena, I have met with them most frequently in patients of a sanguine temperament, in whom the least disturbance of the periodical function has,

through life, often brought on this disorder; whereas in women of a nervous temperament, hysteria often diminishes in proportion as the activity of the reproductive organs diminishes, ceasing entirely with the subsidence of their action. Landouzy has shown that, in the vast majority of cases, hysterical convulsions were ushered in by pain or strange sensations in the hypogastric and ovarian regions, pains which induce the sensation of suffocation felt at the pit of the stomach, and then the globus hystericus. Dr. Copland has known the convulsive attack to be preceded by leipothymia, and I have often been struck by the alternations of gangliopathy with globus hystericus or other minor hysterical symptoms; globus hystericus subsiding, for instance, when a paroxysm of cardialgia appeared.

Case 27.—*Hysteria.*—Lucy P., tall, thin, with brown hair, gray eyes, and a chlorotic complexion, was forty-nine when she came to the Farringdon Dispensary, in October, 1854. She had always enjoyed good health, and married at eighteen, the menstrual flow first appearing the day after her wedding. She had several children, the last at thirty-three, and from that time until she was forty-four, the flow continual regular. It then dodged her for three years. For six months it came regularly every fortnight, then every two, three, or five months. Several times, when she had been long without the menstrual flow, "a gush of blood would come from the mouth or ears, and she was obliged to go to bed." She was much troubled with faintness, flushes, sweats, abdominal pains, piles, which bled occasionally, pseudo-narcotism, and for the first time in her life, hysteria. She once had a convulsive fit, and very frequently crying fits, and the sensation of a lump in the throat. After suffering in this way for three years, the menstrual flow completely ceased two years ago, and her health grew worse. She has become weak, and her complexion turned from ruddy to sallow; she is laid up for weeks with bilious attacks; she brings up bile, and her bowels are either relaxed or confined. She is much troubled with headache, with pseudo-narcotism, with nervousness, and with the hysterical symptoms already detailed. This patient had always enjoyed good health until the dodging time began; she had never been well for the fol-

lowing five years, but she was restored to health in about six months. She first took 4 grs. of blue pill, and 2 of ext. of hyoscyamus, every other night; the comp. camph. mixture before meals, and a drachm of carbonate of soda in a mouthful of water after meals. After three weeks these medicines were discontinued, and 5 grs. of citrate of iron were given in an effervescing draught, after meals, twice a day, and 10 grs. of Dover's powder every other night. The bowels were kept open by an occasional dose of sulphur.

E. W., aged fifty, the sister of a very nervous man, and herself very nervous, has not menstruated for the last sixteen months, but has been troubled by bleeding piles. She awakes every morning with pain in the lower part of the abdomen. This is relieved by pressure, and by lying on the stomach; but only vanishes on her throwing up a large quantity of wind, which often gives her the appearance of being five months pregnant. There are no signs of dyspepsia about this patient. Under the influence of mental annoyance, I have often seen a copious extrication of flatus occur in healthy persons of both sexes, the flatus finding vent in repeated eructations.

5thly. EPILEPSY.—When it appears in connection with first menstruation, it will often wear itself out after a certain number of years, but it occasionally returns at the change of life. I have seen four such instances, and in another, the patient first suffered from epileptic fits during lactation; she had seven children, but the fits only came on during four lactations, and lately at the change of life. She could assign no cause for their coming on at some lactations and not at others; but she had kept the temperance pledge four years previous to the epileptic fits at cessation. Drs. Tyler Smith and B. de Boismont have seen several cases wherein hysterical and epileptoid attacks only came on at first menstruation, at the decline of life, and at each menstrual period, the nervous symptoms completely disappearing on the cessation of the menstrual flow. Dr. Radcliffe informs me, that one of his patients had repeated epileptic fits at puberty, which induced medical men to advise her remaining single. She, however, married, had children, and did not suffer again from the epileptic fits until the change of life. In one of my patients, epileptic fits became more fre-

quent and severe after the ménopause, and in two other cases, epilepsy occurred without any other cause than the change of life; and Moreau notes this epoch, as the only cause of epilepsy, in nine out of 529 cases occurring in women. Besides the well-known anomalous sensations arising from various parts of the body, I have met with one patient in whom the attacks were brought on by a fixed and intense ovarian pain, the result of subacute ovaritis. Pressure on the ovarian region often brought on attacks, and I myself thus caused a severe one. Dr. Copland has often seen epileptic fits preceded by leipothymia, the pulse retaining its usual strength; and this confirms my belief that the ganglionic nervous system may have something to do with epilepsy, although it be a disease of the cerebro-spinal system.

CASE 28.—*Aphasia.*—Mary H., a tall, healthy-looking woman, with brown hair, and hazel eyes, a harnessmaker's wife, was fifty when she consulted me. The menstrual flow appeared at ten, and came regularly with little disturbance until she married at twenty-one. She had four children, the last at thirty-nine, and was regular until forty-seven, when cessation took place, after menstruation had been irregular for four months. Some days after the last menstrual flow, and without any known cause, while she was hanging out clothes in the garden, she felt giddy and fell down, remaining insensible for ten minutes. The fit was repeated once a week, then every fortnight, afterwards with an interval of six weeks, when she became free from them for six months, but felt more nervous than usual; and some time after, while in apparent good health, and talking to her husband, she was all at once deprived of speech. She was perfectly conscious, knew what she wished to say, but could not utter the words. She had no pain, no choking sensations, she did not stammer nor stutter, she had no headache, but felt giddy even when lying down. For two years this fit came every day, and if it missed the day, it would come at night, on waking after her first sleep. She consulted me because the fits have, of late, come two or three times a day. She is now very nervous, frightened at the dark, and at everything, and she complains of headache. After well opening the bowels, with the comp. col. and calomel pills, I gave my comp. camph.

mixt. before, and the carb. of soda after meals. This was continued from the 12th of December to January 26th, and the number of fits of speechlessness diminished from four to one a day, and were of shorter duration. In addition to other measures, I then ordered 8 grs. of ox. of zinc, and 2 grs. of ext. of hyoscyamus to be taken every night. This was continued until March 15th, when the patient was discharged, still complaining of being once a day utterly unable to give utterance to her thoughts, but the speechlessness is of short duration. She was in good circumstances, had a kind husband, seemed in fair health, and the change of life could alone account for her fits, which resemble the little fits of epilepsy.

Case 29.—*Epilepsy and Impetigo.*—Mary F., a woman of the average size, with gray eyes, brown hair, and a florid complexion, came to the Paddington Dispensary, February 16th, 1849. She was then forty-eight. The menstrual flow came at ten, and continued regular, sometimes too abundant, but without other disturbance. She married at seventeen, had three children, the last at thirty-four; since then she has been left a widow, and the flow remained regular until the last two years, when it began to dodge her. With the exception of giddiness during the previous year, she had enjoyed uninterrupted good health up to this period, but now flooding at irregular periods, with great abdominal pain, lays her up for three months at a time; there is no uterine disease, but she is troubled with obstinate constipation, faintness, flushes, and sweats. She suffers from pain at the top of the head, which is worse when she lies down; without sick headaches or hysterical symptoms, she always feels giddy, stupid, sleepless, heavy, and "never as she ought to feel." Moreover, two years ago, when the menstrual flow began to be irregular, she had, for the first time in her life, a cutaneous disease, attacking both arms and face. The arms soon got well, but the face was sometimes better and sometimes worse. Now the cheeks are hot, livid, hard, and covered with flaky scales, a quiescent state which has lasted for three months, but the skin often blisters and distils a watery or a gummy discharge every month or six weeks. Since this affection of the face has appeared, the patient has been subject to fits, which come on suddenly from fright, exertion, or with-

out cause. Talking to me has often brought one on. They come three or four times a day at uncertain periods. Her teeth chatter, she becomes unconscious, and this, at first, lasted only for a few minutes, but now often for an hour, when she becomes violent, and tears everything she can lay hold of, which obliges her to have some one to take care of her. The fits are worse and more frequent when the eruption fades, and the brain always feels relieved when the eruption is worse. February 16th.—I ordered 2 comp. col. and calomel pills to be taken every second night, and 1 oz. of castor oil the following morning; a scruple of sulphur and borax twice a day; one drachm of carbonate of soda after each meal. The comp. camp. mixt., hot foot-baths every night, 10 grs. of Dover's powder every night, were afterwards given, and March 8th, five leeches were placed behind each ear, for the patient would not be persuaded to be bled. March 17th.—The leeches did no good, the patient being no better than when she first came. In addition to the usual treatment, as the face is worse, it is to be fomented with warm milk and water. April 5th.—Abdominal pains were much complained of, and required enemata, with 30 drops of Battley's solution twice a day; without pain, however, or any red discharge, she would frequently pass "large clean clots of blood." A blister once benefited her, so I ordered another, which was useless. June 14th.—She has just recovered from a flooding, which had not occurred for the previous eight months. This has relieved the abdominal pains, but the head is as bad as ever, the nervous fits as frequent, and the face discharges much gum-like matter every second day. I ordered a blister to be kept open on each arm, but being myself laid up about this time, I lost sight of her. The life of no woman ever presented a more marked contrast. Perfect health up to the change of life, after which constant illness. The organic changes set on foot by the change of life caused all the patient's sufferings. Bleeding, daily tepid baths, prolonged for three or four hours, would have been very serviceable, but could not be taken. I would not have attempted to cure the cutaneous eruption before an abundant drain had been permanently obtained from blisters or issues.

6thly. INSANITY.—Some authors assert that insanity is more

common to women than to men; and explain this supposed frequency by the shock felt in the nervous system at puberty and at cessation. The first assertion is doubtful, and the second an exaggeration: for, on consulting the Registrar-General's Reports, it will be found that deaths from insanity are most frequent in women from twenty to forty, or while the reproductive organs are endowed with greatest activity; results in accordance with the statistics of Haslam, Pinel, Esquirol, and Fodéré. From forty to sixty, when men are most actively engaged, and hope fails as well as physical strength, many more men than women die insane. From sixty to eighty, when the sexes most resemble each other, insanity affects them equally. A still better way of ascertaining the liability to insanity at the change of life, is to take the admissions of a large lunatic asylum. The following table, for which I am indebted to the late Sir Charles Hood, shows the ages of women admitted at Bethlem Hospital, from January, 1845, to December, 1853.

TABLE XXVI.

Relative frequency of Insanity at different periods.

Period of Life.	No. of Cases.	Period of Life.	No. of Cases.
Under 15 years,	9	40 to 45 years,	162
15 to 20 "	61	45 " 50 "	153
20 " 25 "	216	50 " 55 "	122
25 " 30 "	223	55 " 60 "	57
30 " 35 "	217	60 " 65 "	55
35 " 40 "	218	65 " 70 "	27

Hence it appears that, although the time at which the change of life generally appears is not most prone to insanity, still 437 out of 1320 became insane from forty to fifty-five, whilst after that age the number suddenly diminished. Dr. Davey, of Northwoods, informs me that about one in every six insane women have had a first attack between thirty-six and forty, and that the chances of insanity diminish from forty to fifty-five. The effects of the puerperal state and lactation in producing insanity explain why it is most frequent in women

before the fortieth year; but the table heading this chapter shows that, out of 500 women, there were sixteen in whom the mental and moral faculties were severely compromised by the change of life. B. de Boismont received into his asylum in one year eight patients, in whom insanity could only be accounted for by this cause. Dr. Forbes Winslow assures me that he has frequently seen insanity brought on by this epoch; and Dr. Wood confirms this assertion. If headache, pseudo-narcotism, hysteria, and epilepsy be caused by the change of life, it would indeed be strange if it should not likewise produce insanity. If Esquirol be right in establishing that derangements of menstruation form one-sixth of the physical causes of insanity, and B. de Boismont in professing the same opinion, and in saying that the menstrual epochs are always "*un temps orageux*" even for insane women who regularly menstruate, it would indeed be singular if the change of life did not sometimes produce insanity. If it be caused by puberty—a fact already recorded by Hippocrates—it would be astonishing if it were not sometimes the result of the change of life. A favorable prognosis of climacteric insanity may be generally given as to ultimate recovery, but it is best to explain to the relatives that the disordered state of mind may last for two or three years, although I have known women recover in six months. In two cases there had been insanity at an earlier period of life, but no relapse at the change of life.

FORMS OF CLIMACTERIC INSANITY.—I shall pass in review—I. Delirium; II. Mania; III. Hypochondriasis, or Melancholia; and IV. Irrepressible impulses, and the perversion of moral instincts.

I. DELIRIUM.—B. de Boismont, who has seen four cases of delirium at puberty, has likewise met with transitory attacks of it at the change of life. Sometimes the delirium is general, or it may run exclusively on one subject; and it is a matter of reflection for the psychologist, that while, in virtuous women, ideas thus combined, without the guidance of volition, may take a lascivious turn, in depraved characters, if Parent Duchatelet is to be believed, delirium runs on ordinary matters,

and never on erotic subjects. I have met with three cases of delirium at the change of life.

Case 30.—*Delirium.*—Mary S., of the average size, but thin, with a sallow complexion, dark hair, and hazel eyes, was forty-seven. The menstrual flow appeared at thirteen, and it had always been particularly free from morbid symptoms. Though twice married, she never conceived. About fifteen months ago the menstrual flow became irregular, and she was much troubled with headache and abdominal pains. One night she went to bed as usual, and awoke delirious. She ran down the street in her nightgown, required three men to hold her, was taken to the Bristol Infirmary, and in three days, the menstrual flow having come on, her senses returned. Several abscesses appeared in both arm-pits, some broke, others were lanced, and, when better, she came to London, and applied at the Dispensary for relief from headache, nervousness, and lightness of head. There had been no menstrual flow for the last ten months. I gave her a scruple of Dover's powder every night, and the comp. camph. mixture, which cured the patient. The singularity of this case is, that no nervous symptoms presented themselves until the attack of delirium. The patient was in tolerable circumstances, had a kind husband, and nothing to trouble her, so I cannot attribute the delirium to anything but the change of life.

Case 31.—*Delirium.*—Mary L., a tall, stout woman, with brown hair, light gray eyes, and a sanguine temperament, was thirty-six when she came to the Paddington Dispensary, October 31st, 1850. The menstrual flow appeared at twelve, and continued regular, abundant, and without much disturbance. She had none of the usual head-symptoms of menstruation, but, from her twentieth year, was subject to epileptic fits. She married at twenty-two, had three children, pregnancy always warding off the fits. The menstrual flow was regular until her thirty-second year, when, a few days after its last appearance, without any known cause, she became delirious, and was taken to the Marylebone Infirmary. In a few weeks she was well enough to leave, and, though her health was not restored, she never had a similar attack. She is very nervous, giddy, and bewildered; but for the last year has had no fits.

Ever since cessation the breasts have been very painful, and the nipples frequently exude a milky-looking or glutinous fluid. Treatment similar to that employed in the preceding case relieved the patient. She was forty when I last saw her, and the menstrual flow had not returned. If the sudden stoppage produced delirium in this case without any appreciable cause, the nervous system was tainted with epilepsy; the patient's sister was also epileptic.

II. MANIA.—Drs. Dusourd and Tyler Smith have noticed mania at the change of life. Before giving a curious instance, I shall mention that B. de Boismont has seen a case of mild dementia transformed by this epoch into furious mania, which lasted long. On the contrary, when cessation occurs in maniacs, it generally causes the disease to subside into dementia, and a sudden calm follows a state of furious agitation. Ferrus, Dubuisson, B. de Boismont, and others have noticed this singular effect, which reminds me of a mode of curing mania, ascribed to the priests of Cybele. "*Qui ante castrationem maniaci erant, sanam aliquanto mentem ab illo recuperant.*"

CASE 32.—*Mania.*—Alice B., a bilious-looking woman, with gipsy features, dark hair, gray eyes, tall and slender, was forty-four. The menstrual flow appeared at thirteen; was abundant every two or three weeks, with a good deal of headache, sick headache, and pseudo-narcotism. Married at nineteen, had several children; the last at thirty-six, and was regular until she had a violent flooding at forty-two, since which time there has been no menstrual flow. After this sudden cessation, the abdomen swelled, was very painful, and without serious disease she dwindled down to a skeleton. She was improving, when, about two months after the flooding, as she was sitting by the fire, she felt a sudden flush in the head, face, and arms; she could not speak, and became unconscious. She was very violent, scarcely slept, eat enormously, and wanted what she could not afford. After this had gone on for three months, one night she said in a collected manner to her husband, "I will go to bed." She did so; slept soundly; was much more rational when she awoke, and gradually improved, without any other medicine than an occasional purgative. She never had a return of mania, but it has left her nervous, light-

headed, and she forgets where she puts things. She came to the Dispensary for an inguinal abscess, with flushes, and drenching perspirations, and returned for advice whenever the nervous symptoms became too troublesome, and they were always subdued by scruple doses of Dover's powder, alkalies, purgatives, and tepid baths. The particulars of this case were confirmed by the patient's husband. Both state that the attack of mania came without any known cause; I therefore consider it a result of the organic changes evidently determined, in a nervous woman, by the sudden cessation of a flow accustomed to be abundant every two or three weeks.

III. Hypochondriasis and Melancholia.—These two degrees of the same mental condition are often met with at the change of life, particularly hypochondriasis, which seems to be an exaggeration of some of the symptoms of pseudo-narcotism. I have already drawn attention to the haziness of intellect, and to the state of temporary self-absorption into which women so often fall; to their love of solitude, their distrust of friends, their exaggerated estimation of trifles; and what is this but a temporary state of hypochondriasis, susceptible of becoming permanent at the change of life? This is why Gardanne and Dubois d'Amiens say they have often observed hypochondriasis at cessation; and they correctly remark that it is accompanied by epigastric suffocation, sensations of strangulation, and neuralgia. Chambon has likewise noticed the frequency of hypochondriasis at this period, and thinks the bilious are most liable to it. Sir H. Halford has drawn from nature the following picture: "She sits in an indolent posture, looks gloomy, hardly speaks at all, and we learn from her attendants that she lives under the impression that some fancied evil is about to befall her. She is suspicious, undecided in all her movements, and manifests symptoms which differ in degree only from melancholy mania."

Dr. Maudsley also observes that "when positive insanity breaks out, it usually has the form of profound melancholia, with vague delusions of an extreme character, as that the world is in flames, that it is turned upside down, that everything is changed, or that some very dreadful but undefined calamity has happened or is about to happen The counte-

nance has the expression of a vague terror and apprehension. In some cases short and transient paroxysms of excitement break the melancholy gloom. These usually occur at the menstrual periods, and may continue to do so for some time after the function has ceased. It is not an unfavorable form of insanity as regards probability of recovery under suitable treatment." In a paper read before the members of the Provincial Medical Association, Dr. Conolly mentions having seen the melancholia of cessation last two years; but those must have been very exceptional cases, of which he could affirm that they were the beginning of the incurable decline of bodily, as well as of mental health. With regard to the causes of this state: it may be induced by plethora of the portal system, by ovarian misrule, and uterine irritation, but these physical causes would never produce melancholia without some cerebral predisposition and the concurrence of psychological causes. Peace and tranquillity of mind may be the lot of those who have passed the crisis; but it is easy to understand how the life of women, in this transition period, may be replete with anguish. Supposing health not undermined by the coming change, how can a sensitive mind and a loving nature remain undisturbed when all is changing around her, and, one by one, the cords snap which anchored her to life? At fifty, parents may have been gathered to the dust, children may have deserted the parental roof. The flame of vitality cannot die without forebodings of decay, and there springs up a doubt never before harbored—a doubt whether, with faded charms and failing energy, one can possibly retain possession of a husband's affection, and proofs of unkindness are looked out for where none were meant. Because the strength of youth is gone, a woman tries to convince herself she is useless, and may become first suspicious and then revengeful. If unmarried, is it wonderful that this peremptory notice served by nature, to put aside all long-entertained visions of fancied bliss, should wound to the quick a sensitive nature? The future then becomes a void, and despondency shows itself as boundless as the sands I have often watched at sunset, from my desert tent. In this desert of her thoughts no refreshing fountain is heard to pour forth the melodious song of hope; no palm-tree promises relief against

a scorching sun. She peoples the void with imaginary evils; hears strange voices where all is silent; feels awful forebodings, though nature smiles around her; and thus hopeless and full of fear she will sit alone for weeks and months in the darkened room of some gloomy dwelling, without any other enjoyment than solitude, or that of brooding over unbegotten evils, with mental faculties now paralyzed, or at times revived by conscience reproaching the poor sufferer with her inactivity, her sloth, and her want of faith in that God who deserts not His children.

CASE 33.—*Apathy and sudden change of previous habits.*—This incapability of, or rather dislike to, exertion,—this aversion to the mental exercise of *willing*, is characteristic of the female mind when disturbed by cessation. I have been often consulted by a lady blessed with connections, personal appearance, and with a mind so highly cultivated that she might have taken the lead in society, had she not shrunk from its pleasures and duties, so soon as she first felt the influence of the change of life. Cessation took place five years ago, and ever since she has severed herself from connections, shut her door to numerous friends, and lived in seclusion. She rises at 4 P.M. and goes to bed between 4 and 5 A.M., so that, in winter, she sees as little of the sunshine as the Laplander. She says she cannot do otherwise, though she knows that her mode of life forces her sons to seek elsewhere for society they cannot find at home. To expostulation or joking, she replies, "You do not understand me;" the usual reply of those who cannot justify their conduct. This want of energy, which has been so unfortunate for others, is no less detrimental to her own happiness; for though annoyed at her distressingly nervous condition, she has not the courage to follow any plan of treatment. I said I had been often consulted, but my advice has been seldom followed, and few of the host of medical men this lady has consulted have been more fortunate. But what could medicine do in such a case without judicious management? Her present state depends upon her having had no strong guiding influence when it was most wanted. Evidently, therefore, to look for improvement while her actions have no other rule than caprice or apathy, is like placing an infant at the

helm of a three-decker, and expecting it to steer safely into port. In this lady's case, a widow, with children unable to direct her, the greatest chance of recovery would be to enter the family of some judicious medical man, under a promise to stop three months, and implicitly to obey all directions. Thus would the patient, in spite of her lamentations and prophecies, be gradually brought back to reasonable hours; thus could the medical man teach her the long-lost art of taking exercise, sometimes mingling it with distractions, at others carrying it to fatigue; and travelling might complete the cure.

CASE 34.—*Melancholia, with suicidal tendencies.*—Mary W., a tall athletic woman, with a pale face, iron-gray hair, a whimpering tone of voice, and apparently always ready to cry, was forty-five when she came to the Farringdon Dispensary in November, 1855. She was the wife of a publican, and in good circumstances. The menstrual flow appeared at thirteen, and came regularly, even during lactation, for she had borne several children, but it ceased suddenly eight months before I saw her. Two months after cessation, she passed a large quantity of blood by the bowels, and for the last five months, every month or fortnight she has had several loose motions containing blood. The abdomen was also very painful and enlarged, so much so that she was thought pregnant by a high obstetric authority. For the last few months she suffered much from dry flushes during the day, and from "her skin stinging and perspiring" during the night. "All this," says the patient, "I could easily bear, were it not for my nervous state." She complains of being all in a tremble, she is sleepless all night, and powerless all day, sometimes dozing, as if intoxicated, and waking up to thank God she is still in her senses; at others, she sits alone, doleful and disconsolate, ashamed of herself for being so lazy, and still unable to do anything, or forgetful of what she ought to do. She says, that "when she sits thinking, she feels numbness and a pricking sensation in her limbs," and is much afflicted with suicidal thoughts. I first prescribed my usual mixture before meals, carbonate of soda after, 3 grs. of blue pill, with 2 of ext. of hyos. every other night, 10 of Dover's powder every night, a large belladonna plaster at the pit of the stomach, and vaginal injections with a solution of acetate of

lead. February, 1856.—To relieve the abdominal pains, she took pills, each containing 2 grs. of blue pill, and a quarter of a gr. of ext. of opium. March 27th.—The patient was in every way better, but the motions were again bloody; the same treatment was continued, and on April 16th she stated that she was less subject to gloomy fits and to suicidal tendencies, though pseudo-narcotism was intense, the abdomen much distended by wind, and the tongue furred. An increased amount of flushes and perspirations coincided with the improvement, and she had grown suddenly stouter, although eating very little. I continued the same treatment, for I could not obtain her consent to have 3 oz. of blood taken from the arm. May 17th.—After fourteen months' absence of the menstrual flow, she passed, after great vaginal pruritus, many large black clots of blood, with skin-like substances, after which she had a watery discharge, and voided about a teacupful of blood by the bowels, with sickness, flatulence, and the old symptoms. More blood was passed on the 28th, after a scene with her drunken husband. I ordered her to take three times a day a tablespoonful of a mixture containing 2 drachms of the solution of hydrochlorate of morphia and of chloric ether, in 6 oz. of distilled water, and when this had cured the internal pains she took effervescing draughts three times a day. August 13th.—She had again become bilious, had passed a little blood in motions, looked seven months pregnant, but her health and appearance have surprisingly improved, notwithstanding the worry of sick children, and a home ruined by the bankruptcy of an unkind husband.

Case 35.—*Melancholia.*—Mrs. L., a thin, nervous-looking lady, with dark hair, and gray eyes, was fifty-nine when she consulted me in December, 1855. The menstrual flow appeared at fifteen, and came regularly with but little disturbance. She married at twenty, had six children, and was regular until the menstrual flow ceased gradually at fifty-four. Soon after this, without worry or any apparent cause, she became subject to headaches, drowsiness, and for a time both her sight and hearing failed her. She would sit by the fire all day absorbed in transacting strange things with strange people of former times, and often frightened by ghastly faces. At other times, she

felt an incontrollable impulse to move about, and to dash her head against the wall, getting up and moving about without a motive, and then sinking down again, to remain immovable for hours. She slept with a light in the room, lest on awaking in darkness, she should throw herself out of the window. At times she had a strong impulse to kill her two grandchildren, and took care never to be left alone with them; but finding the temptation becoming too strong for her to resist, she left an affectionate daughter's comfortable home. She was much troubled, off and on, with dry flushes, and with the sensation of weight and gnawing at the pit of the stomach. I ordered 10 ounces of blood to be taken from the patient's arm, and, after a brisk purgative, I prescribed a quarter of a grain of acetate of morphia, every night for the first ten days, every other night for the next ten days, and every third night for the ten days following. I prevailed on her to stop two hours a day in a tepid bath, hot water being added when the water got cool. The baths were thus taken for a month, after which time, the patient looked and felt another person. All the symptoms had abated. I then gave 10 grains of Dover's powder every night, my comp. camp. mixture, and ordered a belladonna and an opium plaster to be applied, on alternate weeks, to the pit of the stomach, and a scruple of a powder composed of equal parts of flour of sulphur and of biborate of soda, to be taken twice a day. When this had been taken for a fortnight, the flushes, instead of being dry and burning, were mitigated by gentle perspirations. The treatment was continued for several months with slight interruptions, and a tour to the German spas completed the cure.

IV. UNCONTROLLABLE IMPULSES AND PERVERSION OF MORAL INSTINCTS.—As pseudo-narcotism has been seen gradually merging into hypochondriasis, so the symptoms of insanity are often those of hysteria, made intense and permanent. Girls, well-behaved until puberty, then become snappish, fretful, uncontrollably peevish, full of deceit and mischief: is not this a state of miniature insanity? Law has decreed, that to establish a defence on the grounds of insanity, it must be proved that, at the time of committing the offence, the accused did not know that he was doing wrong; whereas medicine

teaches, that some are led by an irresistible impulse to deeds which they know perfectly well are criminal; deeds committed without motive, because liberty is warped by an instinctive impulse, which the patient cannot control. Freewill alone is punishable, says medicine; where freewill is not, punishment is barbarity, and the more barbarous, if inflicted by the hand of justice. It is, however, so difficult to distinguish the strong temptation, which might have been successfully resisted, from this irresistible impulse, that judges are averse to the doctrine of irresistible impulses; they look upon it with suspicion, because it is the plea frequently brought forward to save undoubted criminals from the scaffold. Abstract views of punishment also render judges averse to this doctrine. Baron Bramwell, in summing up on Dove's case, is reported to have said: "Why should punishment be administered at all? It is not inflicted on a man because he has inflicted evil on others, but to hold out an example to deter others from evil. That is the true reason, in my opinion, and the only object of punishment." Assuredly the punishment of criminals has also for its object the appeasing of divine justice, and the atoning to society for mischief done; and although the inconsiderate admittal of the plea of irresistible impulse, would certainly increase crime by withdrawing that constant check on evil inclinations, —the fear of punishment—still, rather than one innocent should suffer, it is better that a hundred criminals should escape. However much the plea of irresistible impulse may have been abused, I firmly believe it leads some to the commission of crimes they abhor. I have been consulted by at least ten women of high or low degree who, at the change of life, bitterly lamented their frequent temptation to commit suicide or murder. Judges, as enlightened as merciful, have admitted the doctrine of uncontrollable impulses in cases of puerperal insanity. If they admit that parturition determines uncontrollable impulses, they must also allow the possible occurrence of the same impulse at all the critical periods of woman's life; during puberty, pregnancy, lactation, the menstrual periods, and cessation. It is notorious, that the female mind is susceptible of being totally unhinged by the first impressions of the reproductive apparatus on the nervous system;

by the irregular performance of the menstrual function; by connection, parturition, and lactation; by some diseases of the ovaries and womb; and lastly, by the shock felt on the withdrawal of that ovarian stimulus to which the system had been accustomed for thirty-two years. Such being the case, what is to be the fate of women, who, at the change of life, unfortunately yield to some ungovernable impulse? Judges should be consistent, and as they shrink from inflicting punishment on mothers who murder their children during a fit of puerperal mania, and as on two occasions* they have advised juries to return a verdict of "not guilty" for the murder of infants by young women who had habitually suffered from disordered menstruation, they would, I trust, deal in a similar spirit with crime committed by women at the change of life, if it could be proved by medical testimony that this period has been an evident source of mental trouble, to a woman convicted of stealing, murdering, or committing other crimes. I lay some stress on this subject, because, when, a few years ago, a lady was brought up for stealing some pocket-handkerchiefs, and the mental infirmities determined by the change of life were pleaded in extenuation of the offence, the jury were divided. The difficulty of dealing with such cases is, that a patient cannot accept the benefits of a humane interpretation of the law, without abiding by the means wisely devised for the prevention of crime by the insane,—seclusion amongst criminal lunatics. Now seclusion may be useful in some cases, but is objectionable, until it has been proved that judicious treatment cannot remove a form of temporary insanity, as yet shallowly rooted in the system. Dr. Reid's† reflections on mental derangement apply forcibly to that occurring at the change of life. "Lord Chesterfield speaks in one of his humorous essays, of a lady whose reputation was not *lost* but only *mislaid*. In like manner, instead of saying a man has lost his

* Regina *v.* Brixey, Central Criminal Court, June, 1845. The murder of an infant by this woman was proved; but she was acquitted on the plea of her being subject to disordered menstruation.

Amelia G. Snoswell was tried at Maidstone, March 20, 1855, for the same crime, and was acquitted on the same plea.

† Reid's "Essays on Insanity," p. 204.

senses, we should, in many instances, more correctly say, that they were mislaid. Derangement is not to be confounded with destruction; we must not mistake a cloud for night, or fancy, because the sun of reason is obscured, that it will never again enliven or illuminate with its beams. There is ground to apprehend that fugitive folly is too often converted into a fixed and settled frenzy, a transient guest into an irremovable tenant of the mind, an occasional aberration of intellect into a confirmed habit of dereliction, by a premature adoption of measures, sometimes necessary, but only so in extreme cases."

I shall briefly notice the most frequent of the ungovernable impulses occurring at the change of life, after mentioning that I have known women, previously economically inclined, become reckless in their expenditure, and given to extravagance at the change of life; while others, from generous, became penurious, or avaricious, in the midst of plenty, and their talk was about the workhouse, and dying without bread. A lady, who suffered much from melancholy at this period, twice had *both* her ponies shot, because one of them was taken ill; and a Dispensary patient labored under a delusion that she was covered with lice, which I could never detect; and, notwithstanding copious ablutions and sulphurous baths, she constantly returned with the same pitiful story.

TEMPER OR UNCONTROLLABLE PEEVISHNESS.—As at puberty, so at the change of life, temper is perhaps the most frequent of its instinctive impulses. The patient often says, "From mild and kindly disposed, I have become irascible and mischievous;" or, "I have suddenly become so mischievous, that I am quite afraid of myself." The character of a charming lady, whom I have been so fortunate as to cure, was thus for a time completely altered. The menstrual flow came at thirteen, and left at forty-seven. During the dodging time, uterine prolapsus was troublesome, and required a pessary; at cessation, there was uterine irritation, incontinence of urine, distressing flushes, and perspirations. She was low-spirited, melancholy, snappish, quarrelsome; so uneven-tempered that her servants would not stop long with her; and so suspicious, that a commonplace observation made by her husband, servants, or friends, was interpreted as a conspiracy against her.

This condition, after lasting more or less for two years, yielded gradually to treatment, and there has been a surprising amendment during the last year. Both at puberty and at cessation this lady became suddenly very stout.

DIPSOMANIA.—Like B. de Boismont, I have several times seen, in temperate women, a craving for spirits only at the menstrual epochs, which subsided with the flow, and the same desire has been noticed in pregnant and puerperal patients. Esquirol and H. Royer Collard have met with women, in good circumstances, who all through life had been temperate, but who, at the change, were suddenly seized with an irresistible desire for brandy, which again became disagreeable to them, when the critical period was passed. This impulse is akin to the well-known longings of pregnancy, and those who yield to it know they are doing wrong, struggle against it, but are overcome. It is easy to understand how such impulses should be rife at all the periods when the ganglionic nervous system is in a state of perturbation, and when anomalous sensations at the epigastric region indicate morbid action in the ganglionic centre; they should, therefore, be considered not so much as despicable failings as complaints admitting of being cured by proper treatment.

KLEPTOMANIA.—Drs. Taylor and Marc have known patients who, previous to puberty or to disordered menstruation, were conscientious respecters of the rights of property, but who, though in affluence, would steal, at all risks, at the critical periods of life. Dr. Marc mentions a rich lady who, during pregnancy, could not resist the temptation of stealing a chicken from a cook-shop. I have already alluded to a case of this description occurring at the change of life, and I believe it to happen oftener than is supposed—though, while yielding to an ungovernable impulse, the sense of acting wrongly is still present to the mind.

HOMICIDAL MANIA.—This irrepressible impulse has been admitted in English Law Courts, whether it occurs during disordered menstruation, pregnancy, or puerperal mania. I cannot cite any case where this impulse led to lamentable consequences at the change of life, but one of my patients was con-

stantly troubled with the temptation to kill her grandchildren, and she feared to dine with them "because of the knives."

Suicidal mania.—Hippocrates relates that self-murder was epidemical among the young women of Miletus. It has occurred during menstrual irregularities, and B. de Boismont has observed it at puberty and at the change of life. From his extensive statistical researches respecting suicide in France, it appears that, for one woman, three men commit suicide; and, with respect to the age at which this crime is most frequent, he found that, out of 5960 suicides committed by women in the whole of France, the greatest number, 1111, took place from forty to fifty; 1026 occurred from fifty to sixty, and 992 from twenty to thirty. It appears, however, that the capitals of some countries are exceptions to the rule, for the same observer found that, out of 1380 suicides committed by women in Paris, the largest number, 343, occurred from twenty to thirty, and 241 from forty to fifty. Capitals excepted, wherein the battle of life rages with fearful fury, it is safe to conclude that women feel the greatest propensity to self-murder between forty and fifty. Many patients have told me, with inexpressible anguish, that they feel "so strange in the head, so lost, so troubled with sensations of impending horror, that they must commit suicide to prevent their going mad," and one drowned herself in a cistern.

Demonomania.—When the belief in Satanic influence had a strong hold on the popular mind, lunatics often thought themselves possessed by the devil; now they are more afraid of the policeman. The only case of demonomania that I have seen, occurred to a lady at the change of life. She attributed the distressing symptoms of uterine disease to the devil having taken up his abode in her body, and the delusion vanished when her health was restored. Dr. J. Conolly relates a similar case in his Croonian lectures; the patient was also at the turn of life: and on analyzing Esquirol's remarkable article on demonomania, I am struck by the fact, that all his cases occurred at this epoch. One patient, aged forty-six, thought the devil had placed a cord from the pubis to the sternum; another, aged forty-nine, had been troubled by cerebral symptoms ever since cessation, at forty, and thought the devil lodged in her womb. A third,

aged forty-eight, declared that he had taken up his abode in each hip-bone. A fourth, aged fifty-seven, from nervous had become insane at fifty-two, when cessation occurred, and she claimed the devil as the father of her children. A fifth, aged fifty-one, thought she had signed a contract with the devil—an illusion which originated in puerperal mania.

Impulse to deceive.—It is passing strange that women should surpass men by stupendous powers of deception. When man has an object to gain, when he wants to beg, or to escape military servitude, he is clever enough at deception; but he does not, like woman, find pleasure in deceiving for deception's sake. It would take a large volume to contain the authentic accounts of deception knowingly practiced by women merely to excite interest. There was nothing at all amiss with the bodily health of most of these women; in some, menstruation was deranged, and others were hysterical. Thus admitting on the part of women a large amount of fully intended deception, there will remain a certain number of cases in which the patient is herself deceived, and has not the slightest intention to deceive others, even when making the most outrageous accusations. It is well known that irreproachable women, when suffering from puerperal insanity, have accused themselves of having had connection with one or more men they knew little or nothing of. I have known women at the change of life to do the same, and who, after having been insane for six or eight months, have learned with horror of what they had accused themselves.

Apoplexy and hemiplegia.—Notwithstanding Dusourd's contrary assertion, women are little subject to apoplexy at the change of life. I give the following curious instance of an ataxic state of circulation leading to the simultaneous loss of blood from many parts:

Case 36.—*Hemiplegia.*—Eliza C., aged forty-seven, first came to the Farringdon Dispensary, February 18th, 1853, being then forty-four. She was of average stature and size, with brown hair, hazel eyes, and flushed face. The menstrual flow came at fourteen, and continued regular, but profuse, and with unusually severe abdominal pains. She married at fifteen. The menstrual flow ceased for eight months, and then a large

blood clot came away, and for several years either the menstrual flow came every fortnight, or was absent for five or six weeks, being then followed by a voluminous clot and great flooding. She never conceived, was once flooded for three weeks, and for the last six months the menstrual flow has appeared every fortnight. Such being her state of health, without known cause, she was suddenly seized with hemiplegia of the right side. She walked to the Dispensary, dragging the right leg, the right arm was numb, often felt like pins and needles, and could be pinched without causing pain. She looks stupid, complains of headache, loss of memory, temporary loss of sight, stutters in speaking, and cannot find the words she wants. The attack of hemiplegia was accompanied by epistaxis from the right nostril. She had been already cupped at the nape of the neck, and I ordered 8 oz. more blood to be withdrawn in the same way, and gave calomel with opium, and black draught. February 21st she lost blood from the right nostril; 8 oz. blood were withdrawn, and immediately afterwards came a violent flooding, which continued until March 5th, when I ordered alum injections, antimonials, and 1 gr. of opium, with 3 of c. ext. of colocynth, to be taken at night. During the flooding, blood frequently trickled down the right nostril. Notwithstanding the quantity of blood lost by the patient, her strength seems but little impaired; she is quite conscious, and walks to the Dispensary; but the hemiplegic symptoms are as marked as ever. May 12th.—She has returned from the country and is better, but still complains of numbness of the right side. She can say what she wants, but has a difficulty of utterance, and complains so much of pain on the right side of the head, that I ordered her to rub in twice a day the size of a filbert of 2 oz. of mercurial ointment, mixed with 2 drachms of ext. of belladonna, and to take the com. camph. mixture, and the aloes and myrrh pills at night. June 16th.—After having rubbed in the ointment four times, her head felt very sore, and "as if it was heavier and larger than usual." She could not see distinctly; salivation came on, but soon subsided, after which she was better in every way, the head was no longer painful, and she could use her right arm and leg, though they remained weak. I lost sight of the patient until May 31st, 1856, when she ap-

peared the same as when I first saw her, except that her face, instead of being flushed, was spotted with dabs of capillary injection. Since the flooding, during her previous illness, there had been no menstrual flow, and she had suffered more or less from headache, abdominal pains, faintness, flushes, and perspirations. Lately the head has been very painful, she finds it difficult to keep awake, and cannot bear to be spoken to; the right arm and leg are almost useless; the right hand is soddened with perspiration, has pricking sensations, and scarcely feels when it is pinched. Blood has been passed in the urine, and she says that hæmaturia occurred also in her first attack. I ordered 8 oz. of blood to be withdrawn as before, calomel and opium to be taken at night, and a black draught in the morning. June 25th.—She was cupped to the same amount on the 4th and 18th, the bowels had been kept freely open, antimonials had been administered, ice applied to the head, and the patient was sometimes better, sometimes worse, often bewildered, at times ungovernable, but the hemiplegic symptoms remained stationary. I again ordered the mercurial and belladonna ointment to the head; she rubbed in 2 oz.; the head seemed swollen; she felt stupefied, could not see clearly for three days, and was salivated. The head and right side then became much better, but the right hand is still powerless. She had a slight menstrual flow for three days, after an interval of as many years, and I prescribed comp. col. pills, the camph. mixt., and 15 grs. of nitre three times a day. Finding the hemiplegic symptoms somewhat worse on the 16th, I advised the posterior half of the head to be shaven, and the ointment to be again applied. This was done with decidedly good effect; and when I saw the patient on August 20th, she no longer suffered from hemiplegia, and was able to attend to her domestic duties, although suffering from debility, headache, and nervous symptoms, most likely increased by occasional fits of intemperance.

THEORY OF MENTAL DISEASE.—After recounting the facts which prove that there are morbid affections of the ganglionic centre, I sought to understand their import, before discussing their treatment; and now that the facts indicating the various forms of cerebral disturbance, induced by the change of life, have been related, I shall call attention to their probable mode

of production, before stating the best means of cure. Those who only want facts, and eschew theory, may pass over what follows, until their eye meets the name of some familiar drug; but they should remember, that if practicing in the time of Stoll, they would have inevitably sought to relieve the cerebral affections I have described by emetics; if during that of Mauriceau or Broussais, by repeated and copious bleedings. In other words, as practice must be swayed by theory, they had better choose the best.

How can organic or functional disease of the reproductive apparatus act on the brain? There are but two channels of communication between the reproductive apparatus and the brain; and something morbid must be conveyed from the reproductive apparatus to the brain either by the bloodvessels or by the nerves. It will not be difficult to show that the cerebral phenomena I have described do not depend on cerebral plethora, for, taking each phenomenon in succession, it will be found that intense nervousness exists more frequently in weak and anæmic than in plethoric patients. Leaving out of the question those in whom headache is caused by biliary derangement, it coincides much more frequently with a deficiency in the amount of blood than in the opposite condition, and often exists without any indication of congestion of the bloodvessels in the head. The same holds good with regard to hysteria and hysterical fits; doubtless there are sometimes fulness of the pulse and cerebral congestion, but in most cases the pulse continues weak, and the bloodvessels of the head exhibit no signs of over-distension. The symptoms described as pseudo-narcotism have many points of similitude with those of plethora and cerebral congestion, which were often, and are even now sometimes so interpreted, and when occurring in chlorosis or pregnancy, have been treated by bleeding; but the fact of the symptoms of pseudo-narcotism being often more apparent when the pulse is weakest, shows that it does not depend upon plethora. It is very seldom caused by biliary derangement, and its being unattended by paralysis, or other signs of cerebral disease, implies that it is not caused by structural lesions of the brain.

Doubtless, delirium and convulsions are often the immediate

results of flooding; and when the cerebral symptoms I have described occur with chlorosis or profuse menstruation, they may be explained in the same way as the nervous accidents after flooding or too copious bleeding—the brain being very imperfectly stimulated by too small a quantity of watery blood. Very frequently, however, hysteria, pseudo-narcotism, &c., are observed when the tissues present every appearance of health, and when the amount of fluids in circulation seem in exact proportion to the wants of the system. The nervous phenomena cannot therefore be explained by anæmia. Drs. Todd and Cormack revived the old opinion, which attributes hysterical delirium and convulsions to a poisonous state of the blood, owing to the retention of something that ought to have been eliminated by the menstrual flow; but as hysterical symptoms are observed before first menstruation, they cannot be attributed to a poisoning of the blood. In this respect my observations are confirmed by Landouzy, who says, that he has observed symptoms indicating the influence of the generative organs upon the nervous system, long before first menstruation, and even before little girls had any idea of sex; and I have met with well-marked cases of pseudo-narcotism in girls of eight or nine years of age, though first menstruation was delayed to fourteen or fifteen.

If the reproductive apparatus does not act on the brain by the instrumentality of the circulating organs and their contents, it must do so by means of the nerves. The genital apparatus is richly endowed with ganglionic nerves, and I have shown how frequently evident signs of disturbance in the ganglionic centres coincided with headache, nervousness, hysteria, and epilepsy. The influence of the generative apparatus in the production of nervousness is distinctly perceivable in many of the lower animals. In the beginning of spring, just before the period of copulation, the nervous system of frogs is endowed with a most remarkable degree of irritability. The slightest touch will then excite those states of the nervous system which, at other times, can only be produced by narcotic poisons, or by strong galvanic action. It is a matter of daily observation, that when women are subject to increased ovarian action, they

are also more irritable, more amenable to cold, to noise, to other physical agents, and to emotional stimuli.

Catamenial headache may surely be considered a nervous symptom; if it does not depend on plethora, is in frequent connection with other nervous symptoms, comes and goes like those affections, alternates with them, and yields, like them, to sedatives. Pseudo-narcotism may be explained in the same way. It should be considered as a peculiar kind of poisoning of the brain, by the too abundant galvanoid influence sent to it, from the diseased ganglionic centre; or else it may be owing to a loss of some control exercised in health over the brain, by the ganglionic nervous system, similar to the acknowledged control of the same system over the bloodvessels. Whether this disturbing influence acts on the brain, or on some particular portion of it connected with the function of sleep, I cannot say. Pathologists of all ages who have particularly studied diseases of women, though at variance in all else, agree in pointing to the reproductive organs as the starting-point of hysterical affections, and some of them, with Landouzy, have observed that, in hysterical fits, the patient generally complains, first of anomalous sensations at the lower part of the abdomen, then of pain or suffocation at the pit of the stomach, afterwards of the sensation of strangulation, and lastly, of involuntary laughter, or tears, convulsions, and coma.

The ovarian nisus seems to react on the *cerebrum abdominale*, so as to multiply its power, and causes it to so influence the brain, that woman, no longer the mistress of her own actions, is literally "fuddled with animal spirits, and made giddy with constitutional joy." The same ovarian nisus, acting with greater power on different parts of the brain, or on differently disposed nervous systems, after accumulating for a time, breaks out, spending its energy in hysterical convulsions, which may be followed by the temporary paralysis of the upper or lower limbs, as will be noticed in the next chapter. Finally, when the ovarian nisus is at the highest, if it be suddenly disturbed by intense mental emotion, the centrifugal nervous currents directing the menstrual flow receive a check. The whole energy of the ovarian nisus is thrown on the central ganglia, and reacts on the brain with such intensity, that in a few hours death

ensues, and nothing is found but congestion of the cerebral bloodvessels—congestion which may be in itself a result of the sudden shock. I would remark that, in ascribing such important results to nervous currents, I only follow the example of those who are working out the minute anatomy of the nervous system. For instance, Dr. Beale, in his paper on "The Paths of Nerve-currents in Nerve-cells," "concludes that the action of any nervous apparatus results from the varying intensities of continuous currents, which are constantly passing along the nerves during life, rather than from the sudden interruption or completion of nerve-currents."

Pr. Schulzenberger, of Strasburg, has shown—*Gaz. Méd. de Paris*, 1846—that it is sometimes possible, by mere pressure on the ovarian region, to cause the radiation of pain from that focus to the epigastric region, and by continuing the pressure, to cause globus hystericus, and then disturbance of the brain and spinal marrow, hysterical convulsions being thus produced, while pressure on any other part of the body produced no such effects. In a highly nervous hospital patient, pressure to the ovarian region caused convulsions, without the intermediate minor symptoms of hysteria; and this experiment was repeatedly tried by several professors of the faculty of Strasburg, as well as by Pr. Schulzenberger. Similar cases have been seen by Romberg. The intimate connection between the ganglionic and the cerebro-spinal symptoms of hysteria, their multitudinous gradations and great frequency, make me look upon hysteria as the keystone of mental pathology.

Esquirol has stated that the reproductive organs are often the centre from which emanates a stimulus sufficient to produce epilepsy; and I have lately seen this literally confirmed in a woman affected with subacute ovaritis, for pressure to the right ovary, intentionally or accidentally applied, repeatedly sent her off into epileptic fits, like the young lady mentioned by Sir B. Brodie, in whom a fit of chorea could be induced by the gentle pressure of the finger on the pit of the stomach. I have thus shown how the ganglionic nervous centre induces hysteria, which was already, to a certain extent, admitted by Willis, Van Swieten, and Lobstein. With regard to epilepsy, the predisposing condition of the cerebro-spinal system is, of course,

different from that of hysteria, but the mode of induction of the two diseases is the same. Epilepsy may arise without the generative organs being at all implicated, some other viscus impelling the ganglionic nervous centre to diseased action. Little is known about the anomalous sensations and epileptical aura arising from various parts; but the epileptic fit is often preceded by intense nervousness and fretfulness, numbness or formication of the limbs, and sometimes by epigastric pain, or a sense of suffocation sufficient to show the influence of the *cerebrum abdominale* in the production of the convulsive fit. Some of the cases recorded in this work, particularly that of Ollivier d'Angers, show that a relation of cause and effect may sometimes exist between gangliopathy and paraplegia.

Having passed in review the effects of the reproductive organs on the cerebro-spinal system at successive periods of life it remains to be shown, how, in some women, it can be the main cause of insanity. If the reader will recall the results of his own experience, he will own:

1. That between the haziness of intellect, the slight forgetfulness of pseudo-narcotism and idiocy, there is no break; that every intervening degree is exhibited in some women at one of the phases of healthy, or of morbid action of the reproductive organs.

2. That between the first slight estrangement of a girl's temper and the maniac's delirium there is no break; every intervening link being supplied by some women at one of the successive phases of healthy, or of morbid action of the reproductive organs.

3. That between those first indications of spontaneous muscular action called "the fidgets," and the strongest convulsions of hysteria, there is no break; every intervening link being supplied by some women at one of the phases of healthy, or of morbid action of the reproductive organs.

These organs can only react on the brain by means of their ganglionic nerves. What wonder, then, if the same powerful influence of the ganglionic nervous system should at times produce a *permanent* derangement of the mental and moral faculties, and permanent craving after what is sophistic in a mental point of view, after what is wrong in morals, as well as

after brandy and physical stimulants? I am thus led to look on the ganglionic nervous centre as a source of vital power in constant correspondence with the brain for the maintenance of the "animal forces," as they are called, producing reflex variable morbid phenomena, in accordance with variable cerebral predispositions, when it loses its control over the brain, or otherwise exerts undue influence over it. If this be a true explanation of those rare instances of insanity produced by the undue action of the ovarian nisus, it follows that in other cases of insanity, its cause should often be looked for in the ganglionic nervous system, as well as in the brain; for if one visceral apparatus, endowed with its ganglion and plexus, can so react on the brain, through the intermedium of the ganglionic centre, as to produce mental derangement, why should not another, endowed with similar ganglion and plexus, react on the ganglionic centre, so as to cause similar results? In health, the ganglionic nerves of each viscus send up few intimations of their operations to the brain, and do not disturb the harmony of its functions; but Hippocrates, and many other illustrious men, thought the liver and connected viscera were the main cause of insanity. Why should it not be so, since the converse holds good, and since the mind, through the medium of the emotional powers, which are twin-born with the intellectual, powerfully influences all the viscera endowed with ganglionic nerves? The soul acts on the viscera by emotion, and they react on the soul, so as to determine passion. There is no passion without visceral—that is, ganglionic sensations. "The yearning of the bowels," an oft-recurring expression in the Bible, is physiologically true. Mothers feel it, so do lovers, and so do sailors at the first sight of land. Neither can revenge be potent with strong visceral reaction; or, if, in popular phraseology, "a man lacks gall." Broussais was right in saying, that there cannot be epigastric pain without its causing some shade of anger, which was partly determined by ganglionic reaction. Many are without passion, because visceral sensations are slight, or absent; but if the brain acts so strongly on the viscera, it is not surprising that they should, in their turn, react upon the brain. When one of these viscera becomes a prey to morbid action, it reacts by its ganglionic plexus on

the semilunar ganglia which influence the brain. When the disturbance is slight, it is felt as a loss of power, or what is termed "low spirits," or a sudden failure of mental energy on feeling a sinking and faintness at the pit of the stomach. From some slight visceral disturbance, lowness of spirits and causeless melancholy frequently come over us like a cloud. And if the cloud does not pass away, what is this but hypochondriasis, or insanity, for which the cause will be sought in the brain by those who only take a partial view of pathology? These assertions bear the test of practice, and hold good with both sexes; for they are confirmed by some remarkable cases of insanity in men, some of which will be found in my work on "Uterine and Ovarian Inflammation." The patients were in good health, when, after a sudden mental shock, there immediately appeared the epigastric pain and phenomena, which lasted a considerable time, and were followed by a permanent cerebral disturbance, and by a strong and motiveless impulse to suicide and murder. Here the shock can be traced to the ganglionic centre, as in the following singular case:

CASE 17.—*Melancholia and Gangliopathy.*—About 1860, a lady came from abroad to consult me. She was tall and thin, with kind and intelligent pale face, and was forty-eight years of age. Born in India, and brought up at Gibraltar, menstruation first appeared at ten, and was quite regular, and her health was perfect till she married at nineteen. Although there was no intromission, and the semen merely passed over her, and although the wedding-night brought on the menstrual flow, she *then* conceived; for there was a quarrel the following morning, and husband and wife parted never to meet again. This unexpected shock was immediately followed by tremulous sensations at the pit of the stomach, compared to the fluttering of a bird, and these sensations have continued ever since with variable intensity, being always aggravated by worry and bodily illness. When her son grew up, he went into the army, contrary to his mother's wish, and for the four following years there were superadded frequent fits of violent epigastric pain, with expuition of ropy mucus. After having been irregular for a year, menstruation ceased at forty-six, and all her sufferings had been worse for two years, and during that time con-

stipation had been habitual, lasting once for sixteen days. The skin had always been dry and the flushes without any subsequent moisture. I found no signs of gastro-intestinal disease, no epigastric tumor nor aortic pulsation, and no uterine disease whatever. The fault was in the nervous system; for she had little sleep, with bad dreams, and an habitual distressing amount of nervous excitement or depression. She has vague terrors, is suspicious of everything and everybody, and is afraid of going to Woolwich, to see her son, and at other times she longs "to faint away, to be oblivious, to die, but not to commit suicide,"—although her father did so. She repeated, that "her life was a living death." The only treatment had been a three weeks' stay at Plombières, during the previous summer, and she had taken a daily warm bath of two hours' duration, and had drunk half a tumbler of mineral water twice a day, which had increased constipation. My advice was to keep the bowels open by purgatives; to take nitro-muriatic acid first, and then quinine, and a grain of Indian hemp every night for a fortnight, leaving it off for a week, then taking it again. I also wished plasters of opium and belladonna, to be alternately kept for a week on the pit of the stomach. If this plan of treatment did no good, I urged the patient to try hydropathic appliances, or the mineral waters of Aix-la-Chapelle, or Aix in Savoy.

There is in general no means of tracing the shock to the ganglionic nervous system, as in the previous case. The shock is spontaneous, self-generated, and seems to depend on some disturbance of the healthy action that one viscus exercises over the others, and all viscera over the brain, and I believe that insanity is generally preceded by more or less prolonged gangliopathy, but this is scarcely to be ascertained in lunatic asylums; to study insanity, in asylums only, would be like studying tubercular consumption in its second stage; the first stage of insanity is hidden in the domestic circle, incapable of understanding its phenomena, or anxious to hide whatever may be understood. This has been pointed out by Moreau, of Tours, who observes, "that almost all mental diseases are foretold and preceded by symptoms which generally pass unobserved, such as fainting, giddiness, and vertigo, and

by nervous sensations arising from different parts of the body like the aura epileptica, which the patients compare to excitement, or to electrical shocks." Dr. Shearman has laid great stress on the frequency of mental disturbance in the cases he has reported, and the subsidence of the ganglionic symptoms on the occurrence of the worst cerebral symptoms, has not escaped B. de Boismont, who remarks, "Without denying the part of the brain in hypochondriasis, it is evident that this affection has its starting-point in the ganglionic nervous system; and I have frequently remarked that gastralgic affections, with great disturbance of the digestive functions, *alternate* with mental diseases, and that these gastralgic affections cease entirely when insanity becomes permanent."

These views have been lately enforced by Dr. Maudsley, in his valuable lectures. "It is worth while observing," says he, "that in other forms of insanity, when we look closely into the symptoms, there are not unfrequently complaints of strange, painful, and distressing sensations in some part of the body, which appear to have a relation to the mental derangement not unlike that which the epileptic aura has to the epileptic fit. Common enough is a distressing sensation about the epigastrium: it is not a definite pain, is not comparable strictly to a burning, or weight, or to any known sensation, but is an indescribable feeling of distress to which the mental troubles are referred. It sometimes rises to a pitch of anguish, when it abolishes the power to think, destroys the feeling of identity, and causes such unspeakable suffering and despair that suicide is attempted or effected." And again he remarks, "Allowing that the generative organs have their specific effect upon the mind, the question occurs whether each of the internal organs has not also a special effect, giving rise to particular feelings with their sympathetic ideas. They are notably united in the closest sympathy, so that, although insensible to touch, they have a sensibility of their own, by virtue of which they agree in a consent of functions, and respond more or less to one another's sufferings; and there can be no question that the brain, as the leading member of this physiological union, is sensible of and affected by the conditions of its fellow-members. We have not the same opportunity of observing the specific

effects of other organs that we have in the case of the generative organs; for while those come into functional action directly after birth, these come into action abruptly at a certain period, and thus exhibit their specific effects in a decided manner. It may well be, however, that the general uniformity among men in their passions and emotions is due to the specific sympathies of organs, just as the uniformity of their ideas of external nature is due to the uniform operation of the organs of sense."

Should I be asked to prove the preceding assertions by post-mortem examinations, I would reply, that at present morbid lesions are earnestly sought for in the brain, while the condition of the ganglionic system is never ascertained. Accurate research might confirm the assertion of Comparetti,* who found the splanchnic ganglia, particularly the semilunar, swollen and harder than usual in a hypochondriacal man who died at forty.

TREATMENT.—The frequency of slight cerebral affections, and the fearful gravity they sometimes assume, render their treatment most important. In the first place, it is the duty of the medical man to carefully ascertain whether the cerebral affection he is asked to treat is caused or aggravated by some visceral disease, for if a cerebral disorder is caused by uterine disease, or an affection of the liver, their cure is the first means that should be adopted to restore the healthy action of the brain; and if, by clinical facts and rigid argumentation, it has been shown that the cerebral phenomena of cessation do not depend on general or cerebral plethora, it is to be hoped that, whatever may be the oscillations of medical doctrines, the time will never return for headache, pseudo-narcotism, and some forms of hysteria to be treated by repeated and copious bleedings. As, however, the influence of plethora as an additional cause of cerebral affections at the ménopause is not to be underrated, I hope I shall not be taxed with inconsistency, if, while repudiating large bleedings, I seek to impress the conviction of the importance of occasional small emissions of

* Occursus medici de vaga ægritudine infirmitatis nervorum. Venetiis, 1780, p. 136.

blood at the change of life. Mild purgatives, either the saline, or vegetable extracts, with calomel or blue pill, are often as advantageous in cerebral affections, at cessation, as at other periods, even when they are not positively indicated by the furred tongue and morbid intestinal secretions. The use of antacids, cooling salts, and diuretics, as already explained, are useful adjuncts. Warm baths relieve the hyperæsthesia of the nervous system, severe pseudo-narcotism, and all those conditions which verge on insanity. The good effect of prolonged baths has been long shown by Pomme; and Recamier revived the practice, which is now generally followed in French lunatic asylums.

Hydropathic treatment will be found very useful in various forms of functional nervous derangement, particularly when the patients are stout and present no signs of organic disease. Witness a childless lady, the wife of a rich man, who, two years after cessation, persuaded herself that she was pregnant, on account of a slight increase of abdominal swelling. She would not allow an examination, for fear her anticipation should prove untrue; she engaged a monthly nurse, and made all other arrangements. After a time an examination was made, and the womb was found unimpregnated. For many months she was very hysterical, having choking fits, and long fits of crying and depression. Many remedies and doctors were tried without benefit, whereas six weeks of hydropathy restored her to good health, which has been maintained for the last three years.

Sedative medications are, however, the chief remedies; and what has been already said on this subject in the chapter on Therapeutics should be read as a preface to the suggestions about to be made. I will merely add that I have invariably given sedatives for pseudo-narcotism, just as Hoffman cured the sopor of intermittent fever with large doses of opium. Faithful to the plan of applying the sedative to the suffering surface, I seek to relieve the distressing headaches of the change of life, and many of its more distressing affections, by applications to the head. In all mild cases of headache, pseudo-narcotism, and hystericism, I recommend the patient to sponge the head all over, once or twice a day, with cold

vinegar and water or eau de Cologne and water, and after half drying the hair, to rub in, for five minutes, sweet oil, or any pomatum. If these refrigerant measures do not relieve, hot flannels to the temporal regions can be tried. The head should be sponged with water, holding in solution 2 to 4 oz. of camphorated spirits of wine to the pint, with the addition of a little eau de Cologne or lavender water. Camphorated vinegar and water, or water in which camphor has stood, or the comp. camphorated liniment well diluted, are excellent remedies. This last has been sold as "Ward's essence for the headache;" but a still better preparation is Raspail's sedative lotion, which is made by adding 2 oz. of liquid ammonia and of common salt, and 3 drs. of camphorated spirits of wine to 32 oz. of water. This lotion may be used with a small sponge, or a pad of soft linen may be soaked in it, applied to the painful part of the head, and renewed as often as may be required. It reddens the scalp, causing burning sensations, but its action can be lessened by diluting it with water, and in severe cerebral affections, a handkerchief should be tied round the forehead to prevent the liquid running into the eyes, while copious spongings are made to the head of the reclining patient. Cold cream should afterwards be rubbed into the scalp, or cold cream with 1 dr. to the oz. of camphor, and 10 drops of the essential oil of bitter almonds. In pseudo-narcotism amounting to stupor, I have, in addition to other means, rubbed into the scalp, eau de Cologne with as much camphor as it would dissolve. After rubbing it in for a few minutes the patient has come to herself. In a case in which these attacks of stupor frequently followed the epigastric pain, this was my only treatment during the attack. On recovering her senses, the patient felt as if her brain were "benumbed," and then succeeded a sensation of internal pricking, like "pins and needles." When this was complained of, I wrapped the head in flannel, and left the patient to repose. The effects of the measures are sometimes surprising when they are faithfully carried out; but as nothing is so irksome as system, most patients prefer talking about the inefficacy of medicine to carrying out systematically any plan of treatment. In very exceptional cases the head should be shaven, and sedatives rubbed into the scalp. The ext. of bel-

ladonna, hyoscyamus, and opium, are what I formerly used, 1 drachm of each to 1 ounce of cold cream; and they may very advantageously be combined with mercurial ointment, as in the instances already given. The other treatment required to cure nervousness, pseudo-narcotism, hysteria, &c., is given in my chapter on Therapeutics and in the cases I have related. The case 23, at page 168, shows the many remedies that may be tried for cerebral neuralgia, and I may add that Graves found nitrate of silver to be useful in this complaint, and that it may be given for a fortnight without danger of darkening the skin. I will again remark on the urgency of procuring sleep, for long-continued sleeplessness is likely to produce insanity by habitually subjecting the mind to that increased intensity of feeling which takes place in the darkness, the silence, and the solitude of night. It is astonishing, in how much more lively a manner we are apt, in these circumstances, to be impressed by ideas that present themselves, than when the attention of the mind is dissipated, and its sensibility in a considerable degree absorbed by the action of light, sound, and that variety of objects which, during the day, operate upon our external senses.

In the first place, sleep should be courted by abstaining from exciting pursuits or amusements, between the last meal until bedtime. This will be often sufficient, and will allow required remedies to act well and speedily. It should be also remembered, that if cold sometimes causes insomnia, this is more frequently the result of the bad habit of so tightly shutting up bedrooms that the air becomes foul and hot; indeed, Dr. H. Bennet tells me that insomnia is to be always cured by sleeping with the window open. Some cannot sleep while the process of digestion is going on, while others sleep better for a light supper, and very bad sleepers should have a cup of milk or a slice of bread and butter, on their night table, for taking one or the other will often give sleep to those who have been tossing about for hours. Failing these hygienic modes of procuring sleep, I have recourse to henbane alone, or with Indian hemp, Dover's powders, in 5 or 10 grain doses, are the remedies I have most frequently prescribed; but chloral promises to eclipse all other agents when the only object is to produce

sleep, for its action is trustworthy and unattended by the drawbacks of all narcotics. It must not be supposed, however, that opium and morphia are to be dispensed with. They have other modes of action beside that of promoting sleep, and are often useful at the change of life. With regard to sleep, young practitioners must be aware that the assertions of aged patients cannot be implicitly relied on unless they be corroborated by other testimony; for the aged often fancy they do not sleep at all, and firmly deny having done so, after a very fair proportion of that blessing.

When incipient insanity is accompanied by signs of ovario-uterine disease, a very important part of the treatment is the exhibition of sedatives by the rectum. Amongst others benefited by this mode of treatment, I may mention a patient sent to me by Mr. F. Brown, of Chatham. She was about fifty at the change of life, lived in complete seclusion, and was a prey to all sorts of strange delusions. As there was leucorrhœa, frequent uterine pains, and great suffering on digital examination, there was a chance that sedative enemata might afford her relief; so I ordered them, with other measures, though without giving much hope to her husband. I heard, however, that the treatment had been very successful. Dr. Ferrus attributed great utility to menstrual medications, when insanity has coincided with, or has seemed to be determined by the suspension of the menstrual flow; and he agreed with Dr. Conolly that, in such cases, the prognosis is most favorable. Many patients are sleepless, restless, nervous in the extreme, always in motion, always attempting, but with little strength to perform; the distinction, then, between the radical and acting forces should be remembered, the object being to moderate the acting, and to increase the radical forces; accordingly, steel may sometimes be advantageously associated with sedatives; the citrate of iron in 5 or 10 gr. doses, in an effervescing draught after meals, is the best way of taking it. With regard to the prevention of nervous affections and insanity at this period, my only recommendation is, to read over again the chapter on the general principles of hygiene at the change of life.

CHAPTER VIII.

NEURALGIC AFFECTIONS AT THE CHANGE OF LIFE IN 500 WOMEN.

TABLE XXVII.

Liability to Neuralgic Affections at the Change of Life.

Lumbo-dorsal neuralgia,	226
Hypogastric pains,	205
Monthly hypogastric pains,	16
Frequent ovarian pains,	5
Habitual dry colics,	6
Paraplegia, mild forms of,	6
Sciatica,	4
Intercostal neuralgia,	6
Numbness and impaired sensation in hands and arms,	3
Paralysis of arms, hysterical,	1
Brow ague, brought on,	1
Brow ague, increased,	2
Aphonia, hysterical,	3
Temporary deafness, induced or aggravated,	10
Permanent deafness,	1
Odontalgia,	2
Total,	497

Thus, during the change of life, 497 neuralgic affections were divided amongst 500 women, some taking more than their share. In after-life, these affections become much less frequent, with the exception of lumbo-dorsal neuralgia, which often persists, in a slight degree, until advanced age, and few women escape those neuralgic affections of the nervous expansions of the skin, which are often called rheumatism, while, of course, the senses become more and more obtuse. When the organs of

vegetative life are seriously disturbed in their functions or structure, pain is experienced, sometimes in the viscera themselves, but most frequently in some portion of the walls of the cavities in which they are contained. The spinal nerves which are distributed through the viscera, receive the morbid influence, transmit it to that portion of the spinal column whence they originate, and the pain is then reflected through the spinal nerves which proceed to the cavities containing the viscera.

The ovary may transmit pain to the spinal nerves by means of the splanchnic nerves. The upper part of the womb is supplied with spinal nerves from the intercostal branches, through the medium of the splanchnic nerves and ovarian plexus, and any disease seated in that part of the womb may cause the reflected pains to be felt in various parts of the spinal column. The middle and lower portion of the uterus is furnished with branches of spinal nerves from the lumbar plexus through the medium of the hypogastric, and when this part of the womb is diseased, the pains are transmitted along these nerves and reflected on those which arise from the lumbar plexus, and therefore along the nerves supplying the muscles of the lumbar portion of the back, the walls of the abdomen, inside of the thighs, the front of the leg, and even sometimes to the instep. The spinal nerves distributed to the vaginal portion of the generative intestine arise from the sacral plexus; hence disease of the vagina causes pains to be reflected along the nerves which come from this plexus, and as this plexus furnishes nerves to the sacral region, to the peritoneum, the posterior part of the thighs, and the calves of the legs, pains may be experienced in all this course, and, in some rare cases, even in the soles of the feet. It will therefore be seen that it is not possible to ascribe the dorsal and the hypogastric pains, each to a distinct set of nerves.

Dorsal pains.—These are almost always fugitive in the upper portions of the spinal cord, and principally settle in its lower extremity, radiating to the small of the back, the loins, thighs, and legs. The pain is generally described as an aching or numbing pain, a gnawing, dragging, burning, or grinding pain; a sensation as if the back were broken, or as if it were opening and shutting—varieties of pain, like those of neuralgia

in other parts of the body; their intensity varies from that of slight pain, which does not prevent moving about, to that which, for a time, usurps the place of all other sensations, confining women to their beds for a few days. The frequency of these pains is as follows:

Lumbo-dorsal pains already existed in . .		70 per cent.
They were augmented at cessation in . .	46	"
" the same in	17	"
" less in	7	"
They did not exist in	30	"
	100	

A great intensity of pain in the brain and spinal column is seldom met with at the same time, for the two are in general so counterbalanced, that when a great amount of cerebral disturbance exists, the spinal symptoms have not a similar intensity. During the prodroma of menstruation, and during the "dodging time," the cerebral symptoms are most intense; the spinal symptoms are, in general, more common and annoying during the period of the full activity of the generative function; and at cessation great is the intensity of both modes of suffering.

HYPOGASTRIC PAIN.—This pain is generally referred to the ovarian, and to the uterine regions. It differs from the symptom just described, in being a pressing, forcing, or bearing-down pain. It seems to indicate a tenesmus of the cervix uteri, to have an expulsive character, and to mark the direction of those neural currents which direct the course of blood towards the womb, and procure its expulsion from that organ. Even when the menstrual flow has ceased, these pains sometimes recur monthly, and determine the leucorrhœal discharge, or the diarrhœa, by which they are often accompanied. Such pains had previously recurred during menstruation in

		51 per cent.
They were augmented at cessation in . .	30	"
" the same in	12	"
" less in	9	"
There were none in	49	"
	100	

I have known women suffer habitually from colics for eight and ten years after cessation, the intestines being the seat of pain, which, however, did not interfere with their proper functions. The following was a tedious case in which dorsal and a fixed ovarian pain were the prominent symptoms:

CASE 38.—*Lumbo-abdominal neuralgia.*—Patience K. was tall, stout, with a broad face, thick masculine eyebrows, dull, squinting gray eyes, brown hair, a sanguine temperament, and she was in her forty-eighth year. The menstrual flow appeared at fifteen, and continued regular without disturbance. She was once laid up for a year by some acute affection of the brain before she married at twenty-four, but was fruitless. At forty-four she again suffered much from pains in the head, and pain in the right arm, which was benumbed and contracted for some time. This was cured, but P. K. has been ailing ever since, off and on, subject to a throbbing, heavy pain at the top of the head, to nervousness, to trembling, to loss of memory, to palpitation, to epigastric pain, sometimes only after taking food, at others without a cause. This has been more troublesome during the past year, and for the last four months she regurgitated sour or bitter stuff once a week. She looks vacant, bewildered, and of late has had fainty feelings, and a clammy skin. For the last two years there have been frequent pains in the ovarian regions, "as if from the plunging in of a knife," and for the last year intense pains have arisen at the lower part of the back and sacrum; her other sufferings have increased and have become more frequent. During this time the menstrual flow has also been irregular, much more abundant, and with scarcely more than ten or twelve days between the menstrual periods.

To allay the derangement of the biliary functions was the first indication; the next was to prevent the too frequent recurrence of the menstrual flow, by adding 6 drachms of tincture of cinchona to the comp. camph. mixture. Two tablespoonfuls to be taken three times a day. I also prescribed 20 drops of liquor potassæ in a little water, after meals, and at night 4 grs. of blue pill, with 2 of ext. of rhubarb, to be followed by ½ an ounce of castor oil in the morning. An opium plaster to be applied to the pit of the stomach. Feb. 12th.—Ten oz. of

blood were taken from the arm. The previous remedies were continued, with the exception of the pills, which were now to be taken only on alternate nights. March 11th.—The menstrual flow has not appeared for six weeks. The food is better digested, but the tongue is still furred, and there is much pain under the left breast and in the left ovarian region. Leucorrhœa is abundant, the os uteri has the usual size, it is painful on pressure, which also increases the habitually felt hypogastric pains. There is no ovarian swelling. April 21st.—A blister to the left ovarian region only relieved the intense pain for two days. Mercurial and ext. of belladonna ointments rubbed in twice a day did no good, so I ordered 20 drops of Battley's solution and 1 drachm of tinct. of hyoscyamus mixed in a little warm milk to be injected once a day into the rectum. May 20th.—The sedative injections have given great relief. The menstrual flow came without much pain after an interval of three weeks. There is still intense pain in the back. On again examining the patient I can find no organic uterine disease. The pains are caused by the cessation of the uterine function in a woman whose nervous system has been shattered for the last five years. July 22d.—The menstrual flow came after an interval of ten weeks. The patient is again very bilious, and is ordered the blue pill and previously named remedies; 4 oz. of blood are to be taken from the arm. November 1st.—The biliousness has gone, the sedative injections control the intense pains; the head symptoms are better. The menstrual flow has again appeared after an interval of thirteen weeks. When I lost sight of the patient she had been many months without menstrual flow, the pains much less severe, and her health good.

Treatment.—There is a distinct indication to use sedatives until the habitual pains are assuaged, and they may be continued for weeks without ill effects. Soothing liniments may be rubbed in night and morning; I mean camphorated liniment, with the addition of tinc. of opium, belladonna, hyoscyamus, separately or combined, as the case may suggest. Soft opium or belladonna plasters may be applied and renewed every four or five days; and, better still, my ready-made plasters, made by spreading atropia glycerine ointment on Mackintosh calico,

as described in my "Handbook of Uterine Therapeutics." Linseed-meal poultices sprinkled with camphor, mustard poultices, and even blisters, may be useful. For abdominal pains the best application is a piece of piline large enough to cover two-thirds of the abdomen, to the upper corners of which tapes are to be sewn, so that the piline may be worn like an apron next the skin during the day. This alone often gives relief, but a teaspoonful of laudanum sprinkled over the cloth side of the piline makes the remedy more efficacious.

Paraplegia.—In infants, paraplegia generally depends on intestinal irritation; in adults, on vesical or uterine affections; and in old age, it appears as an idiopathic disease. It might have been supposed from the manner and frequency with which the lower part of the spinal cord is influenced by menstruation, miscarriages, parturition, and diseases of the sexual organs, that women would suffer more than men from diseases of the spinal cord, but out of 177 cases of paraplegia tabulated by Brown-Séquard, only forty-nine occurred in women. Out of 114 cases of locomotor ataxy collected by Dr. Topinard, there were only thirty-three women; and in seventy cases of the same disease collected by Eisenmann, there were only twenty women. With regard to paraplegia at the change of life, it must be considered a very rare disease.

Gardanne mentions having seen paraplegia occur after the sudden cessation of the menstrual flow, but he gives no details. My six cases and a few others subsequently observed were of a mild nature, and all recovered. There were pricking sensations in the feet, numbness of the lower limbs, great pain in the dorsal region, and an inability to walk. Three complained of a difficulty in passing water, and the sensibility of the skin of the lower limbs being impaired. Similar cases have been met with by Dr. G. Bedford and B. de Boismont. Paraplegia occurred in two out of Dr. R. Leroy d'Etiolles' twelve cases, and on careful inquiry at the Salpêtrière, where there is a great number of paralytics, many of the paraplegics dated their complaints from the change of life. Most of them might have been cured in the early stage of the disease, when it depended upon congestion of the spinal cord; but, subsequently, atrophy of its lower portion prevented the possibility of cure. In

cases, there was no organic uterine disease to account for the paraplegia; but in one of Dr. R. Leroy d'Etiolles, there was considerable uterine swelling, and abundant leucorrhœa, and the patient could not walk without several attendants. Iodide of potassium cured the uterine hypertrophy, and the paraplegia disappeared. The following case is related by Ollivier d'Angers, who does not seize the import of the ganglionic symptoms which play so prominent a part in the case.

CASE 39.—*Frequent attacks of paraplegia, with gangliopathy.* —A lady, aged forty-nine, in whom the menstrual flow had been very irregular for a year, every now and then, without ascertainable cause, had the following train of symptoms, whether in bed or up, reposing or walking, eating or fasting. There was pain and constriction in the epigastric region, with or without sensations of suffocation, which sometimes awoke the patient suddenly. Then came flushing of the face and head, and afterwards burning sensations in the upper part of the spinal column, with pain and numbness in the arms, which became partially paralyzed. This lasted for about an hour, when cold perspirations appeared; she then felt as if cold water were poured down her back, and her lower limbs became paralyzed. This temporary paralysis has often occurred so suddenly, that the patient, taken unawares, has fallen down. In about three-quarters of an hour, these symptoms disappear, without leaving any trace; but they have recurred, from three to five times in one day, on several successive days, previous to the menstrual flow, and about ten days after, during which time constipation was great, urine more frequently passed, and with tenesmus. Leeches repeatedly applied opposite to the painful part of the spinal column, tepid baths and purgatives, greatly diminished the frequency and intensity of the attack, and the menstrual flow became more regular.

A blow to the pit of the stomach determines paralysis; and here, the womb, after its fashion, gave a shock to the nervous ganglia at the pit of the stomach, which reacted on the spinal cord, and caused paralysis of the limbs. In remarking on this case, Ollivier d'Angers insists on the necessity of applying the leeches to the spinal column, asserting that the same effect would not have been produced by applying them to the pu-

denda; but this position is disproved by the following case, which occurred in the practice of a medical friend:

CASE 40.—*Paraplegia.*—A lady's maid, aged forty-five, complained of violent pain in the loins, for which a mustard poultice was ordered; and, as the pain persisted, a blister was subsequently recommended to the lumbar region. This application was soon followed by paraplegia, and a neighboring practitioner gave, as his opinion, that the application of the blister had determined the paralysis of the lower limbs. Although this assertion was contradicted by another medical man, who was called in on account of the persistence of the paraplegia, my friend received several letters from the solicitor of the family, menacing him with an action; but he set them at defiance, and he afterwards learnt that the patient went home to her friends, and that a country practitioner, more clear-sighted in this instance than the eminent men of town, putting together the circumstances of the patient's age and the previous irregularity of menstruation, applied leeches to the womb. The result was a gradual diminution of the paraplegia, and she was soon able to walk with perfect ease.

TREATMENT.—In how many cases, where partial paralysis was supposed to be caused by inflammation of the spinal cord, have the backs of delicate patients been uselessly tormented by blisters and moxas; whereas, the treatment should be directed to whichever organ, womb or kidney, may cause the paraplegia. I have seen admirable effects from the use of the hot mineral waters of Aix in Savoy, and great good is sometimes done there by parboiling the powerless limbs, the patient being placed in a bath, in and out of which hot water is continually flowing. Shower baths and douches of hot spring water will be found useful; and shower baths of water, alternately hot and cold. Such appliances, irrespective of sex, are valuable, not only in paraplegia, but in all chronic, local paralytic affections, which seem to depend on some obstructed circulation of the nervous fluid. When the patient cannot leave home, benefit may be derived from stimulating baths, which can be made by adding to the water 6 oz. of liquid ammonia, 1 of camphorated alcohol, and from 2 to 4 lbs. of common salt. On leaving this bath, the limbs should be rubbed for twenty minutes with some

camphorated and stimulant liniment. Remak thinks highly of electricity in these cases of hysterical paraplegia, one pole being applied to the pit of the stomach, and the other to the lumbar region of the spinal column, but this must be carefully done.

SCIATICA.—From four cases, I have selected one which forcibly shows the utility of sudorifics in diseases of the change of life.

CASE 41.—*Sciatica.*—Jane A., aged forty, had dark hair, gray eyes, small stature, nervous constitution, and was of slender make. After having suffered two years with violent headache and giddiness, she first menstruated between fifteen and sixteen, and continued regularly to do so very abundantly. She married at sixteen, became pregnant immediately; had seven children, was always regular until she quickened, and in three pregnancies she menstruated regularly up to the period of parturition. The previous summer she was treated for rheumatic fever, at the Royal Free Hospital. Menstruation proceeded regularly during the patient's stay at the hospital, appeared four times after her return home, and then stopped. She complained of an intolerable pain in the left lower limb; and, on examination, I found that pressure on the spine did not increase or cause the pain. To all appearances, the left limb was as sound as the right; and the pain was said to arise from behind the great trochanter, and to reach the back of the limb, following the course of the great sciatic nerve. The pulse was weak, the urine clear, and of the usual color. I ordered a blister to the spot which was the most painful, pills of compound extract of colocynth, and a sedative mixture. The blister did not relieve the excruciating pain. Turpentine embrocations were ordered, the other measures continued, and the blister repeated, without the least benefit. March 8th.—The patient suggested that her pains might have been caused by the sudden cessation of menstruation five months previously. On learning that she had lately had flushes and nightly perspirations, never experienced before, I ordered her to take, as an emetic, 1 scruple of ipecacuanha with 1 gr. of tartar emetic, to continue the mixture and the pills, and to take a teaspoonful of flower of sulphur in milk on going to bed at night. 15th.—

The heats and perspirations had increased; the pains had much abated. I prescribed another emetic, and continued the other measures. 29th.—The pain is very trifling, and the heats, flushes, and perspirations, are more frequent, coming on, not only on exertion, but in bed, at night, and in the morning. April 6th.—I ordered sulphur, 2 oz.; bicarbonate of soda, 4 drachms; and 2 scruples of ipecacuanha—a teaspoonful to be taken in a little milk every night. June 11th.—She has had no return of pain; but when the flushes and perspirations abate, she suffers either from headache or from the sensation of "something working" to bring on the pain in the leg. Jane A. has not suffered in any other way from cessation; and as she was subject to a copious discharge every month, one can understand that she should feel the effects of its sudden cessation; and as she was very nervous, it is not surprising that the nervous system felt the sudden shock, particularly that portion which was predisposed to disease by the previous attack of rheumatism. I saw this patient again in 1855; there had been no sciatica nor return of the menstrual flow, and her health was good.

Gardanne mentions, that a woman of a strong constitution, at her forty-fifth year, suddenly ceased to menstruate; and was at the same time seized with violent pains in the left thigh, and at the end of four months, was not able to move the limb. As she had suffered from syphilis in her youth, mercurials were given, but without effect. Sabatier and Gardanne then advised moxas to be applied to the leg, which produced slight fever and great perspiration, but restored the use of the patient's limb.

NERVOUS APHONIA.—This is a rare affection, but I have had a good opportunity for studying the case of a lady, at the change of life, who, after losing her husband, came to town, and settled in Belgravia. Though she had not hitherto been subject to nervous affections, cold, over exertion, worry, or sometimes no apparent cause, would suddenly deprive her of her voice for a few days. The nervous nature of the ailment was shown by the sudden coming and leaving of the aphonia, and by the effect of change of air; for a drive in the Regent's Park or to Hampstead would often restore her voice to its

natural tone. She therefore left town to reside in the country, and has since enjoyed a comparative immunity from this complaint. Sometimes a potion, containing ether, speedily dispelled the aphonia. Dr. Deslieux has found chloroform useful, giving from 10 to 15 drops in a little water. In two cases, I found sudorifics useful, the permanent return of the voice coinciding with a marked determination to the skin. Cerise speaks in favor of emetics for nervous aphonia, and I have witnessed their sudden good effects, but the best treatment is undoubtedly the direct application of electro-magnetism either to the tongue or to the larynx by means of Dr. Morell Mackenzie's galvanizer. The shock makes the patient scream—the spell is broken, and the patient is immediately cured.

NEURALGIC AFFECTIONS OF THE EYES.—In two women, at the change of life, I have noticed the head symptoms to be accompanied by marked photophobia, and many patients complained of an unusual dimness of sight, which wore off on the abeyance of pseudo-narcotism, and other head symptoms. H. D., aged fifty, and chlorotic-looking, has been irregular for the last six months, and suffers much from intense debility, even after a full meal. She can scarcely keep herself awake during the day, but at night is kept awake by a dull, heavy pain in the eyes, lasting more than two hours, the probable cause of which being that she has lately worked too hard at embroidery. B. de Boismont gives the case of a woman who, at forty-five, was blind for three days; Boyer rightly judged that it depended on the change of life, and on recovering her sight, she remained subject to giddiness. Dusourd met with three women who were blind for two or three days, at the change of life, and he has several times observed them affected with hemeralopia; but Romberg erroneously considers women predisposed to amaurosis at the change of life.

DEAFNESS.—When deafness occurs at the change of life it should not be considered senile, for it may depend upon inflammatory affections of the internal ear, or upon morbid lesions of the external canal; but deafness is, in general, purely nervous, attending on pseudo-narcotism; the patients being, as it were, stunned, do not hear until they are fully roused from their state of torpor. I have seen this deafness appear and

disappear suddenly; in one case it came on suddenly at cessation, when flooding abated about six years ago, but the deafness has continued ever since; and I have known women driven to desperation by continued noises in the ear, which baffle all treatment. M. S., a dispensary patient, aged fifty-two, never had a day's illness until forty-five, when she saw a man executed, which brought on flooding. The menstrual flow never reappeared, but loud and continued noises were constantly heard, which Mr. Harvey could not account for by a diseased condition of the internal ear. Cupping, blisters to the nape of the neck, and other treatment were useless. In a very nervous lady, erysipelas of the face occurred at the change of life, and left an excruciating pain, sometimes accompanied by a most annoying "forcing sensation" behind the ears. This had lasted for three years, but it yielded to general treatment, to the local measures necessary to cure uterine irritation, and to the rubbing in of belladonna ointment behind the ears.

RHEUMATIC PAINS.—Neuralgia of the nervous filaments of the skin is often caused by the damp state in which the underclothing is kept by continued perspirations at the change of life.

TREATMENT.—Heat under any form is good. Passing a hot iron over the painful part, previously protected by brown paper and flannel, may cure the patient. Vapor baths are serviceable. Sponging, with alternately hot and cold water, or shower baths of the same, will harden the surface against rheumatic influences. The thermal waters of Aix en Savoie are very effectual, and the best preventive is to wear flannel next the skin. In advanced age, these rheumatic cutaneous pains are often exceedingly troublesome, but women are then generally free from the eccentric nervous pains and temporary paralysis which have afflicted them in youth, and have been described, by Sir B. Brodie, as hysterical.

CHAPTER IX.

DISEASES OF THE REPRODUCTIVE ORGANS AT THE CHANGE OF LIFE.

TABLE XXVIII.

Liability to Diseases of the Reproductive Organs in 500 *Women.*

Flooding, a terminal,	82
Floodings, successive,	56
Leucorrhœa, frequent, at irregular intervals,	146
Leucorrhœa, monthly,	12
Remittent menstruation,	33
Vaginitis,	4
Follicular inflammation of the vulva,	10
Inflammation of the labia,	4
Ulceration of the neck of the womb,	9
Hypertrophic inflammation of the neck of the womb,	2
Prolapsus of the womb,	5
Uterine polypi,	4
Uterine fibrous tumors,	4
Uterine cancer,	4
Chronic ovarian tumors,	3
Irritation and swelling of the breasts,	14
Milky or glutinous secretion of the breasts,	2
Hard, non-malignant tumor of the breast,	2
Cancer of the breast,	1
Habitual deposits in the urine,	49
Pain and difficulty in passing urine,	9
Incontinence of urine,	4
Hæmaturia,	1
Erectile tumor of the meatus urinarius,	2
Perineal abscess,	2
Total,	464

The foregoing table gives a fair idea of the derangements of the reproductive organs that were met with in 500 patients

at the period of the change of life, various forms of suffering being frequently met with in the same patient. Hence it is clear that the change of life is a time of turbulent activity for the reproductive organs; and though they are less liable than before to acute inflammation, they are more than usually so to congestion, hemorrhage, mucous flows, and neuralgic affections.

When the change of life is over, the rule is, that the reproductive organs become more or less atrophied, and it is this process of involution which protects women against the frequent occurrence of inflammatory diseases of the womb. If these complaints occasionally occur, it depends on this process of involution having been checked by chronic inflammation; in other words, uterine inflammation seldom occurs at, and after cessation, except in those who have previously suffered from it. After cessation uterine inflammation may be due to a fibroid development in the substance of the womb, or to a polypus growing from the cervical canal, or from the mouth of the womb. I sometimes find the os uteri ulcerated, but never to the same extent as at the previous period of life. When occurring at the change of life, it seems to me that uterine inflammation is oftener accompanied by biliary disturbance than at an earlier period, and I have known patients daily bring up what seemed a pint of bile, for two or three weeks, notwithstanding all remedies. Of sexual infirmities after cessation, it strikes me that vaginitis is the most frequent, sometimes originated and attended by slight ulceration of the cervix; sometimes without any uterine lesion. The frequency of vaginitis is to be explained by the continuance of sexual intercourse long after cessation, for I have been repeatedly asked by women about sixty years of age whether, on account of vaginitis, it would be dangerous for their husbands to have connection with them.

Sometimes vaginitis coincides with a similar affection of another mucous membrane, which implies a general failure of health, and explains the frequency of relapses. It may be laid down as a rule that, during the change and after cessation, inflammatory affections of the sexual organs are less frequent and less severe, and that when these organs then assume great activity, it is an activity of a lower type, denoting a deterio-

ration of the plastic force; the ovary, the womb, the breast, becoming more frequently the seat of cystic, fibrous, or cancerous growths.

DISEASES OF MENSTRUATION AT THE CHANGE OF LIFE.—Flooding seems to have been the only disease of menstruation, at this period, which has engaged the attention of medical men; but besides flooding there is the *stillicidium uteri*, or continual dribbling from the womb, lasting for weeks or months, and effectually undermining strength. The pains accompanying menstruation may become unusually intense, and have been considered in the chapter on "diseases of the nerves;" but the mode of recurrence of the menstrual flow calls for some remarks. It is better for women that the menstrual flow should cease gradually, and its stopping suddenly may depend upon some removable circumstance. Attention to the general health, sedatives, mild tonics, and purgatives, an occasional tepid bath, and rest, will often cause the flow to reappear with comparative regularity, for some time longer; but I do not agree with Dr. Ashwell in recommending mustard hip-baths, stimulating embrocations, and sexual intercourse. Instead of returning every two or three months, the menstrual flow may return every two or three weeks. This occurred in twenty-six cases out of 383, in whom the catamenia were ceasing. It is unnecessary to point out how weakening and how irritating to the nervous system is this too frequent recurrence, which can, in most cases, be prevented by the exhibition of sulphate of quinia, in three-grain doses, to be given at night. If quinia, combined with the avoidance of hot drinks and rest do not check the too frequent flow, I give a mixture with sulphuric acid and alum, and advise the use of cold vinegar and water to the vulva and adjacent parts.

FLOODING.—Mauriceau, Levy, and others, look upon flooding, at the change of life, as indicating cancer of the womb; Astruc, Gardanne, and some modern pathologists, consider it to depend on ulceration of the womb or its chronic hypertrophy; but as I have known women, free from all uterine symptoms, and in every other respect well, have flooding from a fall, from suddenly hearing of the death of a relative, flooding need not be accounted for by ulceration of the neck of the womb,

and to test the accuracy of that opinion, I examined twenty such patients, and in two only did I find uterine ulceration. This brings me again to the diagnosis of flooding at the change of life, for I have already shown, at p. 55, that the flooding of internal metritis, uterine hydatids and fibroids, uterine polypi and cancer, are sometimes attributed to the change of life. I have known these mistakes to be made by the most talented, because they would not take the trouble to make a digital examination before giving a diagnosis. I have thus seen women reduced to the last stage of debility by a uterine blood flow, more or less abundant, being allowed to continue for two, three, or four years without an examination being made, because these patients were at the time of life when the menstrual flow usually ceases. Quinia and port wine were given, and change of air recommended; but no astringent vaginal injections, not even cold applications, had been made. I have now under my care a lady, with cheeks as white as my paper, who has been flooding more or less for the last two years, and who was repeatedly told that there was nothing to be done, that it depended on the change of life. On examination, I found a polypus hanging to a cavity of the womb by a pedicle as thick as my little finger. Another lady was allowed to flood, at short intervals for three years, and on examining her I found the cervix three or four times the right size, giving the idea of a soft and podgy substance, and quite denuded of epithelium. My first impression of the case was cancer, but I afterwards became convinced it was not specific, for I cured the patient by the means of nitrate of silver; and she regularly menstruated for several years.

When flooding occurs at a catamenial period, as a critical discharge, subsiding completely after a few days, every one recognizes it as depending on the change of life; likewise if successive floodings occur at successive menstrual periods. When flooding occurs a few months or even years after the absence of the menstrual flow, and is accompanied by flushes, perspirations, and other symptoms of cessation, without being explained by uterine disease, it is fair to suppose that it depends upon the change of life; but whenever it does not appear as a downright critical flow, when it is followed by a lingering

sanguinolent discharge, with returns of flooding at irregular periods, with leucorrhœa and other uterine symptoms of disease, the case is doubtful, and no medical man can conscientiously give a diagnosis without a previous examination. Who has not been consulted, for flooding, by women of forty-five in every appearance of health, and has not been grieved to find such cancerous lesions of the womb as warranted the conviction that the patient's days were irrevocably numbered? Louis and Valleix have mentioned that, before any visible cancerous changes have taken place in the womb, profuse menstruation will sometimes be the first symptom of the complaint. This is an additional reason why profuse menstruation should be frequent at cessation. No other cause of flooding is wanted besides the great predisposing cause already discussed; but it may sometimes be occasioned by a fall, a fright, a violent fit of anger, by sneezing, or by connection. Fothergill has seen an intermittent fever at cessation give rise to menorrhagia every month.

Beyond a certain loss of blood, which must be estimated by the patient's pulse, by the expression of her features, by her feelings of strength or weakness, the further flow is dangerous. If those who, at this period, lose too large quantities of blood, do not quickly repair the loss, they can seldom do so; and, although not completely invalided, they remain pale and chlorotic, they do not enjoy the degree of strength with which they were previously gifted, and become nervous. There is, however, a certain amount of danger in stopping the critical flow too soon, particularly in those who are plethoric, or who have been accustomed to lose much blood at the menstrual periods. J. Frank says he has often seen apoplexy brought on by means injudiciously used to stop the floodings of cessation; and two cases in my own practice confirm this remark. F. Hoffman has seen apoplexy at the change of life in women subject to an abundant flow. This sufficiently shows that it is wrong to let flooding at the change of life take its chance, and that it should be considered a complaint requiring medical advice. The treatment of flooding during the attack should be directed so as to check the flow, by placing the patient in the horizontal position on a horse-hair mattress, with light cover-

ing, in a cool room; by giving cold lemonade made with the *mineral* acids, alum whey, ergot of rye and strychnia, or nauseating doses of antimony. Local measures may be required, such as iced vinegar and water to the abdomen, and to the inner parts of the thighs; or a lump of ice to the neck of the womb, and by making her grasp a lump of ice, for the cold thus transmitted to the nerves of the womb may suffice to stop the flow. The injection into the vagina of a strong solution of tannin, or alum and zinc, has been sometimes successful. Dr. West has shown the utility of intra-uterine injections of a solution of gallic acid, or an infusion of matico, to stop continued flooding after all other means had failed, in a woman of fifty-one, and I have found a strong solution of the perchloride of iron still more useful. I have thus, even in cases of cancer, checked bleeding that had been going on for more than a year, but in a doubtful case that I saw, with Mr. Holberton, the injection caused such tenesmus, and so great an amount of pain continued for several weeks, that I asked myself whether the remedy was not worse than the disease. Caseaux has seen many women die several hours after puerperal hemorrhage had been stopped, too little blood having been left to stimulate the brain and nervous system, so as to enable it to perform the indispensable vital acts of respiration and circulation. In such cases he recommends circumscribing the blood into the smallest possible space, by bandaging the four limbs, and by pressure to the aorta. Similar measures might be useful at the change of life in exceptional cases.

It has been pointed out, that in the plethoric and those accustomed to menstruate profusely, bleeding often did good at the time, and prevented subsequent ill-health; but it is seldom advisable to bleed the month following a flooding, or the one after that, unless there be evident signs of congestion. It was for continued flooding that Fothergill, Hufeland, Lisfranc, recommended the plan of taking less and less blood, from a patient, at successively longer periods, and the practice is sometimes very useful. By bleeding we take away the material of flooding; but it must not be forgotten that hemorrhage as often depends upon the perturbed action of the bloodvessels as on plethora; and although other measures may be indispensable,

the return of many hemorrhages may require a judicious use of sedatives. A sedative mixture, containing Battley's solution, or a solution of acetate of morphia, taken at night, will therefore be found useful; and as the blood is directed with such force to the womb, it becomes a centre of morbid attraction requiring to be lulled and stupefied. This may be done by giving sedative injections by the rectum, or a suppository made of one grain of opium and two of extract of belladonna, may be used every night, until the nervous irritability of the reproductive apparatus be quelled. Saline purgatives and small doses of nitre are also indicated; and it should be borne in mind that at the dodging time, or after cessation, no centrifugal tendencies of blood should be encouraged by pediluvia, hip-baths, mustard poultices, or by similar applications to the lower extremities.

Leucorrhœa, or a flow of mucus unmixed with pus, at the change of life, is, like flooding, a critical discharge, the indiscreet interference with which might cause a more serious complaint, and I have met with those in whom it was immediately increased by wine and by emotion. If the discharge becomes abundant the best way is, not to check, but to regulate it, by increasing the solubility of the bowels and the habitual moisture of the skin. Frequent lotions with tepid water may be recommended, but I very rarely order cold injections, and, when these are necessary, seldom with the addition of any astringent substance; after a time, injections of water, containing 1 drachm of acetate of lead or of alum to the pint, are useful.

I have met with women who have a continual sero-sanguinolent discharge of no serious import. In one case the lady was remarkably strong and healthy, and menstruated with great regularity up to her death, at eighty-four. Six years before this lady's death I was consulted, and I found a considerable enlargement of the capillaries of the vagina, particularly on the cervix, but no redness of the mucous membrane itself, and no ulceration, enlargement, or cancer. Several applications of the solution of nitrate of silver did no good, neither did injections, so all treatment was abandoned. A very strong lady ceased to menstruate at fifty, and at fifty-two she was suddenly told that she was to be deserted by a man who had lived with

her as her husband for twenty-five years. The shock brought on delirium which lasted a fortnight, and a muco-sanguinolent discharge from the womb, which has continued ever since, and has now lasted three years, without impairment of health. There was neither ulceration, polypus, nor cancer to explain this discharge, which came from the internal surface of the womb, only inconvenienced the patient, and was not much diminished by astringent injections. Another patient has a pale pink discharge whenever she strains, or remains standing long, and whenever she puts her hands into warm water.

Vaginitis.—The occurrence of vaginitis at the change of life or afterwards was only noted four times in 500 patients, but I have seen many cases of this complaint during the last twelve years, and sometimes the patients were mothers of large families, and had never suffered till cessation, when vaginitis became troublesome. Vaginitis is often attended by great internal heat, bearing-down pains, vesical disturbance, with or without scalding sensations on passing urine. The discharge is sometimes purulent, offensive to the nose, and acrid enough to chafe the pudenda. At other times it is milky or watery, and the gentlest digital examination is most painful. Before ordering vaginal injections, in very acute cases, it is better to reduce the inflammation by a saline purgative, and copious dilution with imperial drink, or linseed tea; by large, thin, warm, linseed-meal poultices applied to the lower half of the abdomen; by lotions, with linseed tea, adding to each pint one or two drachms of acetate of lead; by the rectal sedative injections; and by a tepid bath, prolonged for an hour. In a few days the lotion may be used as a vaginal injection, and it may be requisite to apply to the vagina, every fifth or sixth day, a solution of nitrate of silver, forty grains to the ounce of distilled water.

It is not unusual for those who have suffered much from uterine disease to have occasional attacks of vaginitis after the change of life, and four patients have, for several years, been obliged to come to me on this account, once or twice a year. In them there is no trace of uterine disease, but sometimes vaginitis coincides with an enlarged and displaced womb, or with a fibroid. I have just seen a lady who, six years after

the ménopause, was given up as suffering from cancer, and in whom I can only find extensive vaginitis, with a large anteverted womb. Sometimes vaginitis seemed to be the result of a tendency to mal-nutrition of most of the mucous membranes, sometimes I traced it to too frequent connection in advanced life. I have also seen acute vaginitis in married women in whom there had never been intromission, and I have met with women who had previously had children, and nevertheless inflammation and spasm had so contracted the vagina that I could, with difficulty, introduce the forefinger. Occasionally vaginitis is the only organic lesion that accompanies distressing cases of neuralgia of the sexual organs, to be hereafter considered, but regarding which I may already state that the neuralgia persists after the cure of the vaginitis.

FOLLICULAR INFLAMMATION OF THE PUDENDA.—This form of disease is most frequent during previous years, but I have occasionally known it to begin at the change of life, and to be subject to occasional relapses for the following three or four years, while I have met with three instances in which the disease had begun about thirty, and continued many years after the ménopause. The annoyance suffered is extreme, and the irritation such as to render the application of the hands imperative, and causes the discharge, at other times mucous, to become bloody. In one lady the irritation came on periodically, and then several hard lumps, about the size of a filbert, would appear in the margin of the labia. These swellings seldom suppurated, but occasionally vesicles appear on the skin. I have observed that in severe cases of this description, there is no exaltation of sexual desires, connection being, on the contrary, abhorrent to the feelings, though it may be otherwise when the affection is slight.

The labia should be fomented every two or three hours, with a lotion containing half an ounce of acetate of lead, and two drachms of laudanum to four ounces of distilled water, and fine linen should be steeped in the lotion, and gently applied to the irritated surface, using afterwards a powder made of powdered starch, ʒv; powdered acetate of lead, ʒss; and essential oil of bitter almonds, ♏x. If that does not do good, I recommend a lotion made with two drachms of sulphate of

zinc, two drachms of diluted hydrocyanic acid, and two ounces of glycerine to sufficient distilled water to make an eight-ounce lotion.

A tepid bath, or hip bath, should be taken daily, or every other day, warm water being added, so that the patient may remain in it for an hour, or more, if possible. After the full effect of a saline purgative, a sedative rectal injection should be given once or twice in the day; and at night a scruple of Dover's powder, or of Battley's solution, may be beneficial. Should this plan of treatment fail, it would be necessary, instead of the acetate of lead, to have recourse to the application of a solution of nitrate of silver. The patient cannot effectually apply this remedy, which must be done by the medical adviser, who will have to steep cotton-wool in a solution of nitrate of silver—40 grains to the ounce of distilled water—and to rub it well into the recesses of the mucous membrane, before its morbid excitement will abate. Trousseau recommends, as a never-failing lotion for this affection, a pint of water, in which is dissolved a large pinch of a powder made with equal portions of deutochloride of mercury and muriate of ammonia. He also recommends first two vaginal injections a day, then one of a solution of deutochloride of mercury, 3j to the pint of cold water. I agree with Huguier, that the vulvo-vaginal glands are not liable to inflammation after forty-five.

PRURIGO PUDENDI.—This is a common form of prurigo, and after cessation it is often accompanied by prurigo of some other part of the skin, or prurigo senilis. This is a most distressing disease, and Lorry asserts that the mere local irritation is often succeeded by a fearful desire for sexual gratification. I have seldom met with severe cases, but B. de Boismont, Gilbert, and Mr. T. Hunt, note prurigo and eczema of the vulva and anus as not unfrequent at the change of life. The following case is derived from Mr. T. Hunt's practice.

CASE 42.—*Herpetic affection of the labia.*—A single lady of fifty, who had never menstruated, suffered from irritation, chiefly confined to the left side of the clitoris, which was in a state of hypertrophy from the constant friction. As the patient could not well retain her water, a careful examination was made, when it was found that the meatus was larger than usual,

and that *there was no vagina or uterus.* When young, she frequently had leeches applied to the labia to induce menstruation, but no examination had ever been made with a view of ascertaining the cause of the amenorrhœa, nor was she at all aware, up to the age of fifty, that she was the subject of malformation. She had all the other physical characters of a female, together with the modesty and delicacy of mind peculiar to her sex; there was sexual passion, and she would long previously have been married, had she not feared that matrimonial unhappiness might arise out of the total absence of the catamenia. She was never conscious of any local pain or fulness at the monthly periods; but she was frequently troubled with headache and giddiness at irregular intervals. In other respects her health was excellent; but the pruritus, which was often accompanied with an herpetic eruption on one of the nymphæ, was the great plague of her life, and strong religious principles had alone prevented her committing suicide. Arsenic and other remedies were tried in vain.

Mr. Hunt speaks most favorably of arsenic. In milder cases, saline purgatives have proved very useful; also, prolonged tepid baths, cold baths, cold hip baths, and cold water injections. The lotions recommended for vulvitis will be equally good in prurigo. Ointments with a preparation of zinc, lead, or mercury, may be tried, as well as powders containing calomel and camphor. I have given camphor in various ways, with good effect. Lotions made with the sedative camphorated lotion, or with camphorated vinegar diluted with water, camphor ointments, camphor powders, and camphor sprinkled between the bed and sheet. The utility of preparations containing carbolic acid confirms Hebra's assertion that prurigo is caused by pediculi, and suggests the careful cleansing of the patient's clothes so as to destroy the insects by which the complaint is often indefinitely prolonged.

NEURALGIC AFFECTIONS OF THE SEXUAL ORGANS.—In the first place, I must treat of Erotomania, or the inordinate desire for sexual gratification, which is a mental phenomenon, and should have been, therefore, placed on the list of irresistible impulses, in the chapter on cerebral affections. Pudendal neuralgia will then claim the reader's attention; and lastly, I will describe

as ovario-uterine, a little-understood form of abdominal neuralgia.

Erotomania.—The inordinate desire for sexual gratification, described by writers as *furor uterinus*, *uteromania*, and *nymphomania*, is a mental affection, suggested, promoted, and intensified in a very limited number of women by morbid ovarian influence, by uterine affections, and by the various kinds of pudendal disease that I have just described; and this sufficiently explains the importance of curing them.

The Greeks considered erotomania to be the result of Divine vengeance for neglecting the worship of Venus. In the Middle Ages, the complaint was considered to be a proof of Satanic influence; but we now rightly place in lunatic asylums those who suffer from it to an aggravated extent. I have stated at page 120, that the most distressing cases of erotomania are very rare at the change of life; but B. de Boismont had six cases in his asylum. Mathieu cites one case in a lady at fifty, and another in a woman at sixty years of age. Dusourd mentions three, and Louyer Villermay cites two cases, as having occurred after cessation. I do not agree with Mathieu and Roubaud that the disease is frequent at the change of life, for I have not met with a single instance of an aggravated nature. There is, however, so much of truth in the old French proverb about "Ce diable de quarante ans si habille à tourmenter les femmes," that towards the change of life, there is often a temporary rekindling of passion thought to be altogether extinguished, like the sudden reawakening of a smothered flame. This explains why, at the change of life, women sometimes take a husband when it is treatment they require, and why, occasionally, a married woman who had hitherto led so virtuous a life that it seemed impossible for her to go wrong, will actually sacrifice position, friends, children, and husband, to begin a new life with a worthless vagabond. With regard to treatment I will only say that it behooves the medical adviser to remove any kind of morbid irritation that may exist, not only in the pudenda, but in the womb and ovaries, and those who have to treat severe cases of erotomania in lunatic asylums must remember that a digital examination will not enable them to decide that there is no uterine disease; that point must be

determined by an instrumental examination, the patient having been previously placed under the influence of chloroform; indeed, it seems to me that medical men are incapable of well attending insane women, unless they thoroughly understand diseases of women.

Pudendal neuralgia.—It is easily understood that morbid lesions of the pudenda should give rise to more or less heat, aching, or itching; but occasionally at the change of life one or other of these sensations assumes a very distressing and long-continued intensity, although no structural lesion of the pudendal tissues can be detected. Many patients complain that for a few nights after each menstrual period, there is an intense itching and skin irritation, unaccounted for by any cutaneous eruption. Such cases explain why cessation is sometimes followed by itching of the pudenda, or of the whole surface,—the prurigo latens of Alibert, to which Aran believed women at the change of life to be particularly subject, and to indicate some form of uterine disease. In some of the most distressing cases of pruritus and perverted feelings, there is, however, nothing morbid to be detected, as in a woman of sixty, who was subject to hysterical attacks if a young man came near her, and in whom Biett could discover nothing amiss, although he inspected the pudenda with a magnifying glass. Lisfranc and Tanchou have drawn attention to vulvo-vaginal neuralgia; and the last thinks it occurs most frequently at the change of life. He mentions the case of a lady of forty-eight, who had never suffered from uterine disease, in whom the menstrual flow ceased at forty-six, and ever since she had been afflicted with pruritus and darting pains in the pudenda. These sensations were increased by walking and over-exertion; no morbid lesions could be found to explain the sufferings; and they were relieved by the internal exhibition of assafœtida and valerian, combined with the external application of opiates and belladonna. It must be confessed, however, that some of these cases stubbornly resist remedies, and yield only to those influences that have power to strengthen the nervous system, and to those nutritial transmutations of tissue that time alone brings about.

Ovario-uterine neuralgia—I am not aware that cases similar

to mine have been described by gynæcologists, but Dr. Handfield Jones has recorded two similar cases in his work on functional nervous diseases. One of his patients was thirty-eight years of age, the other younger still, but four of my cases occurred at the change of life, and two after cessation. These cases were characterized by a most distressing burning sensation in the vagina and pelvis, with a considerable amount of tenesmic action, shifting from the rectum to the bladder or to the womb, and sometimes felt in the three organs at once, the sensation being sometimes so well localized as to impress the patient with the conviction that there was a solid body pressing on the rectum or the bladder, or a tumor on the womb. These pelvic symptoms are said to bring on exhaustion and prostration referred to the pit of the stomach, followed by sleeplessness or pseudo-narcotism, despondency, apathy, and other forms of cerebral neuralgia described in a previous chapter as gangliopathy and ganglionic dysæsthesia, for these pathological conditions are closely related to that form of neuralgia of both sensory and ganglionic pelvic nerves which I think right to call ovario-uterine. I am strengthened in the belief that the ovaries are greatly implicated in this neuralgia, by my having observed a somewhat similar train of pelvic symptoms to occur in man as the result of concussion of the testicle. Very nervous women are most liable to the complaint, but I have seen it assume its worst form in strong-minded women, who, through life, had always enjoyed good health. I have always found the neuralgia accompanied by a certain amount of vaginitis, and its cure always alleviated the symptoms, but seldom cured it. Vaginal injections were often useful, but sometimes an injection brought on a fit of neuralgia, and for a time injections had to be left off. Worry, mental anxiety, and fatigue made the symptoms worse. A tranquil tenor of life, rest, particularly in the recumbent position, with the feet higher than the pelvis, quieted the symptoms for a time; and they sometimes yielded speedily to opium and belladonna suppositories introduced into the vagina, or the rectum, but the cure of the complaint must be sought for in whatever can strengthen the system, such as change of scene, travelling, more cheerful circumstances, the exhibition of our ordinary tonics and those called nervine, like

arsenic and strychnia. Although I have only met with six aggravated cases of this description, I believe that in a less degree the complaint is far from uncommon, remaining unnoticed, because many women effectually conceal their sufferings. The following cases give a good idea of the disease:

CASE 43.—*Ovario-uterine neuralgia.*—Miss X., was forty-seven when she first consulted me. She is small but well proportioned, has been highly nervous all her life, and is so still. Menstruation was irregular, and there was a muco-purulent discharge, vaginitis, and decided ulceration of the cervix, and a most irksome sensation of heat and irritation in the passage. I cured the vaginitis and ulcération by surgical measures without relieving the vaginal heat and pruritus, so I sent the patient out of town When she returned after many months, the pruritus was as bad as ever, and would come on after any excitement of fatigue or standing about, and would be relieved by resting with the feet higher than the pelvis.

This vulvo-vaginal irritation would sometimes disappear on the coming on of a similiar pruritus, on the palms of the hands and on the soles of the feet, showing that however much the chief seat of neuralgia might be in the womb and vagina, the extreme nervous expansions in other parts of the body might suffer in like way. When this irritation affects the feet and hands there is nothing to be seen there, and she refrains from scratching them, because it would make the irritation last for hours. As might have been predicated, the symptoms are worse at night, and lead to great exhaustion and despondency. I have watched this state of things for ten years and often could give no relief. She was always better for plenty of food and wine, and for such small quantities of citrate of iron and quinia as she could bear. I tried all sorts of injections; tar-water did most good, but it has been repeatedly advisable to leave off all kinds of injection, for they seemed, for a time, to do more harm than good. I syringed the vagina with a solution of nitrate of silver, and touched the passage with the solid caustic with questionable benefit. A rectal suppository containing a grain of opium and one of extract of belladonna often gave temporary relief, but this remedy could not be relied on. Many a daughter has, by the sacrifice of her own

health, repaid her mother the gift of life, and a year ago, my patient lost a mother who had been long a cripple, requiring anxious and fatiguing nursing; and afterwards she went out of town and got fat, and now suffers much less, having a slight return of the old symptoms when she gets weaker and more nervous.

Case 44.—*Ovario-uterine neuralgia.*—A very strongly constituted lady, aged forty-seven, is said to have had some acute uterine disease twenty years ago, while residing in France, when forty leeches were applied above the pubis. With the exception of not being able to retain the urine so well as previously to this attack, health remained so good that every year she was able to take long pedestrian excursions with her husband. She never conceived, and menstruation ceased suddenly at forty-four; for the following months the nose bled very frequently and the bowels became constipated; for this she went to Homburg, and was restored to health. On returning to town, in December, 1868, she took very cold enemata for constipation, which was so great that a wineglass of Friedrichshall water, taken every hour, failed to produce watery motions, but irritated the bladder, and was followed by anomalous abdominal sensations, that have lasted ever since. She feels as if there were a heavy body in the pelvis, bearing down upon the rectum, with a burning sensation, referred sometimes to that organ, sometimes to the vagina, or to the bladder. When in bed, and lying down, with the feet up, the patient feels comfortable; by the time she has half done dressing, the burning sensation begins, and lasts until the bowels have been moved; soon after this the burning comes back; it is aggravated by standing or sitting, by indigestion, flatulence, constipation, and repletion of the bladder; also by worry and bad news. The sensation is relieved by walking, by lying down, and by regularity of the bowels. Homburg was again tried, and did good, but on her return the lady was as bad as before, and consulted several doctors. One attributed the sufferings to stricture of the rectum, another to irritation of the bladder, a third to displacement of the womb. In due course of time Homburg was tried for a third time, but the waters were soon left off, as they aggravated all the symptoms, and after the patient's return to

town Dr. Beale sent her to me. In addition to the pelvic symptoms already described, there was considerable cerebral disturbance, for a strong-minded, sharp, matter-of-fact woman, was in a state of mental confusion, her brain felt muddled, and she would sit for hours dozing or doing nothing; despondency being doubtless increased by finding herself helpless as a child, after having passed all her life in doing everybody else's business as well as her own. She forgets where she puts things; once thought she had taken out a large sum of money in her purse, and that she had lost it, whereas a month afterwards she found it in some out of the way place. On examining, I found the rectum perfectly healthy, notwithstanding the pain and stricture ascribed to it. The vagina was so narrow that I could with difficulty introduce part of my index finger, and I gave so much pain that I desisted from all further investigation; ordered linseed tea and laudanum injections, three times a day, and henbane internally. A few days afterwards I was able to reach the os uteri with the tip of my finger; I found the womb exquisitely sensitive; and wishing to ascertain how far the bladder was implicated, I sounded it; found nothing abnormal except great pain when the sound passed over the urethra, but the pain was not caused by inflammation, for the finger in the vagina did not enable me to feel the urethra as a hard and round body, giving pain on pressure. Injections with acetate of lead and laudanum, as well as opium and belladonna, rectal suppositories, enabled me a little later to examine the womb without giving pain; there was no ulceration, and all along there had been very little vaginal discharge. The pain was most felt at the opening of the vagina, which looked sore, red, and injected, a condition that may account for an unusual hardness of the intervagino-rectal tissues, a hardness of which the patient is sensible, and complains of as something wrong with "the bridge." This is caused by long-continued congestion, and the parts are now without heat or redness. This sore state of the vaginal opening was relieved by the application, twice a day, of zinc ointment, to each ounce of which was added a drachm of diluted hydrocyanic acid. Vaginitis becoming worse, I swabbed the vagina once a week, with a solution of nitrate of silver, and I ordered alum and

zinc injections; but suppositories, whether administered by the vagina or the rectum, did harm. After thus treating the patient for a few months, the sensations of burning and weight had considerably diminished, but were often still very troublesome. Digestion was much improved by nitro-muriatic acid and pepsine; pseudo-narcotism and mental disturbance were not relieved by bromide of potassium, but were much reduced by henbane and Indian hemp, and for the last six weeks the patient has been taking, at three meals, the twenty-fourth of a grain of arseniate of iron, made into a pill with the eighth of a grain of Indian hemp; a combination suitable alike to the general nervous derangement and to the abdominal neuralgia. This leads me to the question of diagnosis. There was no organic disease of the bladder or rectum, nor of the womb, neither displacement nor ulceration of this organ. The disease was vaginitis, kept up by excessive walking at the change of life. The vaginitis causing neuralgia of both the sensory and the ganglionic pelvic nerves, the vaginitis and neuralgia causing pseudo-narcotism and the other forms of cerebral disturbance that usually attend the ménopause; the neuralgic element of the case being shown by the patient's often feeling the disturbance to ascend, as it were, from the pelvis along the spinal column, to the back part of the head, where there is most suffering. A residence at the seaside, and the continued use of injections and internal exhibition of strychnia will, I believe, complete the cure.

Diseases of the cervix.—Hard hypertrophy of the cervix has been admitted to occur at the change of life by Gardanne and B. de Boismont, but whenever I have met with cervical enlargement at the ménopause it was evidently the legacy of bygone years. Hard hypertrophy may then last for a long time, with slight symptoms or none, and I have never seen it turn to cancer.

I have only twice met with soft hypertrophy or engorgement originating at the change of life, and it has been observed by Dr. Gunning Bedford and by Dr. Forget. The cervix was much enlarged, felt soft and boggy, as if constituted by erectile tissue. Examined through the speculum, the cervix presented a ragged wound which bled freely. In this form of disease,

the repeated and abundant flooding principally comes from the cervix, and not from the cavity of the womb. My two cases had been taken for cancer, but the movability of the womb, the healthy appearance of the vagina, the absence of severe pain, and of the characteristic smell of cancer, enabled me to establish that it was not specific. Forget cured his case by repeated cauterization, and I mine by the alternate application of the solid nitrate of silver and its solution.

Ulceration of the os uteri.—It must be borne in mind that not unfrequently women have been suffering from undetected ulceration of the womb, for a variable period of time, when the sufferings of the ménopause cause it to be detected; and while this sheet is passing through the press, I have been consulted by a very strongly constituted widow, who has evidently been suffering from inflammation of the cervix ever since her last confinement, twenty years ago. The gradual ceasing of menstruation increased her suffering, and I found an ulcer about the size of a shilling at the os uteri, dipping into the cervix. Other women who had been well cured of uterine ulceration, many years previous to the change of life, then have relapses, and I have known some have return of this disease four years after cessation. A patient, now 60, had a first and severe attack at cessation, and has a slight return every year. Another who is married, but without children, had a first attack four years after cessation fifteen years ago, and ever since there is a tendency to vaginitis. When ulceration occurs after cessation there is frequently an hypertrophied womb, or a tendency to vaginitis, and I have repeatedly seen the point of insertion of small polypi to be the centre of a patch of ulceration varying in extent from the size of a shilling to that of a florin, and, in four cases, the inflammation and ulceration of the cervix seemed to have been caused by marriage during the dodging time.

I avoid repeating here, what I have written on the treatment of uterine inflammation, in my "Handbook of Uterine Therapeutics," but I will briefly state that, if the case be one of inflammation of the os uteri with erosions, it would be well freely to paint the diseased surface with the solid nitrate of silver, and after this has been repeated once, or more fre-

quently, at five days' interval, a solution of the same salt might be applied. I have tried alcohol, vinum opii, chromic acid, carbolic acid diluted with glycerine, the styptic colloid, but I prefer the nitrate of silver, for it is the best mucous membrane improver with which I am acquainted. It is, however, well to have a change of topics, for whenever uterine ulceration occurs in advanced life it is much more difficult to cure, as Dr. Bennet has already stated. In all such cases vaginal injections should be made by the patient two or three times a day, with linseed tea; a solution of acetate of lead, or of alum, one or two drachms to the pint. The patient, using an India-rubber syphon syringe, lying down when using the injection, and prolonging its use for five minutes at least. It will sometimes, however, occur that injections do no good, and cause pains like those of impending menstruation, and such cases have made Dr. Marion Sims too much disparage injections. I remember two cases in which the mouth of an atrophied womb was surrounded by a distinct rim of ulceration, which I could not remove by this plan of treatment, nor by the application of the acid nitrate of mercury or potassa fusa c. calce, and I was obliged to content myself with keeping in check what I could not cure, though time may.

INTERNAL METRITIS.—Even in a chronic form I consider internal metritis to be a very rare disease at, or after the change of life, and I have only seen one case of acute internal metritis after the ménopause which deserves to be recorded.

CASE 45.—Mrs. T., aged sixty-four, was sent to me in 1868 by Dr. Smith of Weymouth. She was very stout and florid, and it appears that she miscarried several times when twenty-five, and that the late Dr. Lever told her that if she did not take more care of herself she would suffer for it later in life. When forty-four, she consulted Dr. Smith, who has thus kindly informed me of what occurred when the patient was under his judicious care.

"I first saw Mrs. T. in 1847, for menorrhagia and hysteria. The womb was greatly congested, and I applied leeches to it several times, and sent her home apparently cured in Sept., 1847. She returned to me, however, in Sept., 1850, with similar symptoms, and was a month under my care, with no other

treatment than saline aperients and astringent vaginal injections, and she went home as before apparently well."

Menstruation ceased at fifty without bad symptoms, but when fifty-four she began to lose blood from the womb, and continued to do so more or less until the day of her death. As soon as menorrhagia set in, Mrs. T. went to Weymouth, and with reference to this period Dr. Smith writes me word:

"I heard nothing of her again until Sept., 1867, when she returned complaining of a sense of weight in, and bearing down of the uterus, with occasional discharge of blood, often attended with exquisite pain, vaguely described as being at one time in the uterus, again in the bowels, back, and hips. The uterine sound passed three and a half inches into the uterus, and did not give more than ordinary pain. I failed to check the bleeding, except for a time, though she was about seven weeks under my care. I dilated the os with sponge tents and tangle with the view of reaching any morbid growth, if any, in the uterus, but found none. I came to the conclusion the case must be one of fibroid tumor in the uterine wall, since all the ordinary mediums to check hemorrhage and allay pain had failed."

When I saw Mrs. T., in September, 1857, I found the womb about double its usual size, and painful when pressed; the cervix was much enlarged, and not at all ulcerated. I easily introduced three inches and a half of the uterine sound, and this gave great pain. If the flow of blood was checked for a limited time, a little pus would be passed in a gush and after great pain, leading me to believe that it had accumulated in the womb; but independently of the passing of blood or matter, Mrs. T. complained most of attacks of pelvic forcing pain, lasting from one to two hours. When she got worse, I saw her in one of these attacks, and nothing more resembled the pains of labor, as she lay on her back, with face injected, groaning or screaming, and tugging hard at a sheet tied to one of the bedposts. These pains increased, the paroxysms became longer, brought on vomiting, and they prevented sleep by coming on at night. The sickness was for a time relieved by an effervescing draught with prussic acid, but the various sedatives that I tried internally, externally, and by the hypodermic

method, muddled the brain without easing the pain or inducing sleep. Sulphuric acid, tannin, and ergot of rye did not check the hemorrhage, nor did various cold injections. I could not persuade Mrs. T. to let me inject the cavity of the womb with a solution of perchloride of iron until the plan was sanctioned by my friend Dr. Barnes. I easily injected from 2 to 3 ounces of equal parts of the strong perchloride and water, which caused very great faintness, but no increase of pains and marked diminution of blood loss. I repeated a similar injection a week afterwards, causing great aggravation of pain, which continued unceasingly; she gradually took less and less food, slept less and less, and died of exhaustion on the 17th of April, 1868. Notwithstanding my respect for Dr. Smith's opinion, neither I nor Dr. Barnes can see sufficient reason to suppose that this fearful pain was due to a fibroid developed in the substance of the womb. The paroxysms of pain were those of most acute metritis, and the tablespoonful of pus that gushed from the womb after increased pain could only have been generated in its internal cavity; but I could not prevail on the relatives to let me settle the point by a post-mortem examination. I cannot conclude the case without stating that I believe it would have had a fortunate termination if I had been able to persuade the patient to let me inject the womb at a much earlier period with a solution of perchloride of iron, or of nitrate of silver.

Before commenting on chronic internal metritis, I will state that I have never known uterine exfoliation to occur towards the ménopause, although singularly enough, in the first recorded case of uterine exfoliation, Morgagni mentions its continuing up to cessation, and Dusourd has met with similar cases. Those bodies called *fongosités* by Recamier being evidences of morbid action on the part of the uterine mucous membrane, it is easy to understand they may sometimes account for flooding at cessation; but it must also be remembered that the same bodies have been found in women who had no red discharge from the womb.

Chronic internal metritis.—During the last ten years I have seen three cases, in which, during "the dodging time," the patients suddenly passed more or less fetid pus at menstrual periods, after a moderate amount of uterine pain, and in one instance this was repeated at six successive menstrual periods.

Between the menstrual periods these patients suffered moderately from nausea and other uterine symptoms, the womb was painful when examined, enlarged, and admitted the uterine sound to the depth of four inches in one case. Rest and cooling injections, combined with small doses of ergot and strychnia, caused the purulent discharge to be replaced by the usual menstrual flow. I refer to chronic metritis, cases described by my friend Dr. Matthews Duncan as uterine leucorrhœa of old women. I am justified in doing so, by the discharge being often muco-purulent, and in the only case in which Dr. M. Duncan had an opportunity of examining, he found "the walls of the uterus abnormally thin and soft, and the mucous membrane of the uterine cavity had an irregular and almost ragged surface, the depressions being apparently seats of ulceration." The explanation of such cases is to be found in the fact that in rare instances, the unhealthy lining membrane of the womb continues to secrete, while the process of atrophy progressing in a healthy cervix contracts the cervical canal. When a certain amount of fluid has accumulated the patient feels a girdle of pain, and other uterine symptoms, which are dispelled by the spontaneous evacuation of the fluid, or by its surgical removal, for it is obviously the surgeon's duty to cut short the patient's sufferings by sounding the womb, and it may be necessary in rare cases to keep the cervix distended by sponge tents, until the walls of the uterus have contracted sufficiently to prevent a fresh accumulation. Dr. M. Duncan must have met with this disease, more frequently than I have, and under an unusually aggravated form, for I have seldom seen it, and I believe he exaggerates the danger of such cases, judging at least from a passage of a letter in which he tells me "that if not cured, these cases end in malignant ulceration in the uterus;" neither has Dr. West met with the cases described by Dr. Duncan more frequently than I have. His treatment principally consists in the injection into the womb of a solution of nitrate of silver, through a hollow probe, or a double-current syringe.

From this state, there is but one step to the obliteration of the cervical canal, which frequently occurs after the ménopause, without the slightest impairment of health. Should, however, the obliteration of the cervix coincide with an ulcerated state

of the uterine mucous membrane, its secretions will accumulate, the womb will swell, and then decrease, to enlarge again, as already related, after a few months, with more or less pelvic pain, nausea, and disturbance of the general health. In three cases of this description I did not feel justified in re-establishing the permeability of the cervical canal, and under the influence of rest, purgatives, liniments to the hypogastric region, the fluid collected in the womb was absorbed, and the patients have passed many years without presenting signs of any similar recurrence. Dr. Bennet informs me that he never adopted any other plan of treatment in such cases, and the extent to which uterine secretion may be absorbed is shown in a patient of Scanzoni, aged fifty-seven, whose uterus rose two inches above the pubis, to subside to the level of the pubis, after the application of nitrate of silver to the cervix, and the use of astringent vaginal injections. It is clear from what precedes, that whenever we have to apply strong caustics to the mouth of the womb, after cessation, it is still incumbent on us to maintain the permeability of the cervical canal.

Many of these cases had given rise to no disturbance of health, and had only been revealed on opening the body to discover some other disease; they will remind the reader of another case, related by Dr. Jallon, *Thèse*, 459, An XIII. A woman, aged fifty-two, two months after cessation, had difficulty in passing water and a swelling of the womb, anasarca, and atrophy, followed by death. The womb was found distended, its walls as thin as paper, and containing a yellow curd-like fluid. Duparque has also recorded a fatal termination, in a case of this kind, which occurred ten years after cessation. The distended uterine walls burst in a paroxysm of pain, causing death on the following day. A large quantity of blood was found in the peritoneum; the neck was cartilaginous, and the cervix obliterated.

The previous cases enable us to understand the transformation of the womb into a calcareous shell. In nine out of the eighteen cases collected by the elder Louis, cessation had taken place, and the age of the others was not mentioned. The 14th case in Louis' *Mémoire* relates to a woman who was subject to violent hysterical fits at forty, and their subsidence coincided

with the formation of a hard tumor behind the pubis, which gave rise to no untoward symptoms. After cessation, she was troubled, for twenty years, with hæmorrhoids, which sometimes bled, and she died at last of consumption. The womb had become a calcareous sac, containing an inodorous, caseous looking fluid; its shell was four lines thick, and so hard that a hammer was required to break it.

UTERINE DEVIATIONS.—At the change of life or after cessation patients seldom seek advice for uterine deviations, but they are still as frequent as when most complained of. Dr. Saussier de Troyes says, that out of 102 cases of uterine deviations, he has met with eleven women, from forty to fifty, suffering from this disease. I have detected many well-marked cases of anteversion and retroversion at the change of life and after cessation, which did not in the least inconvenience the patients; and, on the other hand, I have forty patients who, for many years before the ménopause, suffered much, from the displaced womb being diseased, and who are now leading a very active life, although the uterine displacement is as great as ever it was. The cessation of menstruation has extinguished the ever-recurring ovarian irritation and uterine congestion, which were the real causes of their sufferings, and not the displacements or malformations, that still persist after the recovery of health. Such facts are calculated to convince uterine pathologists that it would be wrong to consider the displacement as the *chief* indication of the treatment of uterine deviations, which should be governed by the nature of the morbid condition causing or complicating the deviation. This point of practice, and particularly the injudiciousness of treating uterine displacements by intra-uterine pessaries, has been definitively settled by the discussion that took place some years ago in the Imperial Academy of Medicine. I say definitively, for while the discussion was proceeding, Depaul, the reporter of the Commission, asked Sir James Simpson for cases to illustrate his treatment, but could only obtain instruments. Sir J. Simpson never appealed against the verdict then given against him, never alluded to it, nor to the many deaths caused by the use of the intra-uterine pessary, when his works were collected, under his supervision, by two of his best pupils; he allowed

judgment to go by default, and the profession has confirmed the verdict of the Imperial Academy. Although rarely occurring at the change of life, and after the ménopause, I have seen procidentia uteri occur for the first time at the age of forty-nine, in a single lady living in affluence, which could only be ascribed to forcing pains, frequent, though by no means severe, occurring during the dodging time. A dispensary patient, aged sixty-five, suffered as much from prolapsed womb after, as before cessation, which occurred at forty-eight; she consulted me for flooding, the consequence of a contusion of the prolapsed womb on being knocked down in Holborn. A Mrs. M. has had several children and miscarriages, but never uterine prolapsus till the sixty-ninth year of her age, when it was brought on by a severe attack of diarrhœa. The very rare cases of prolapsus in old age are explained by the fact insisted on by Kiwisch, that although the womb has become atrophied, it is less powerfully supported by a weaker and shorter vagina, and is no longer padded by the fat, which, in youth, abundantly lines the pudenda. This state of the parts likewise accounts for the occasional coincidence of prolapsus of both the womb and the rectum in old women.

Ovaries.—Before passing in review the heteromorphous growths that become so frequent after the ménopause, I will say a few words on the ovaries considered as the seat of congestion and inflammation. I am not aware of there being any case reported of abscess of the ovaries, at the change of life, neither have I noticed subacute inflammation of the same organs. It is difficult to separate the influence of the ovaries from that of the womb in the production of the sexual diseases of women, at the change of life. Nevertheless, as we positively know that the ovaries rule supreme over menstruation, and that they cause many diseases of women during the period of woman's greatest reproductive energy, it is fair to suppose that they aggravate and delay the cure of the most common uterine diseases, when ovarian irritation is no longer relieved by an habitual menstrual flow. There is no fear of erring in partly attributing to ovarian agency the unexpected reawakening of passion, and the strange sufferings that I have described as ovario-uterine neuralgia. As for the effects of the atrophy of

the ovaries, which gradually follows the ménopause, they have been studied in the present chapter, and in that on the physiology of women at the change of life.

UTERINE POLYPI.—They obscure the limitations of the menstrual period, retard cessation, complicate its diagnosis, and are as frequent at the change of life, as in previous periods. This will be shown by the following table, which embodies Dupuytren's experience, and likewise proves the little frequency of polypi after cessation. Polypus of the womb began in—

1	woman	from the age of	15 to 20
10	"	"	20 " 29
19	"	"	30 " 39
23	"	"	40 " 49
3	"	"	50 " 59
1	"	"	60 and above.
57			

UTERINE FIBROUS TUMORS.—Braun, Chiari, Malgaigne, Mr. Paget, and Dr. West, established the fact that between forty and fifty, uterine fibrous tumors are generally fatal; and I believe that most of these polypi and fibrous tumors originated from thirty to forty, though they may have only become apparent at the change of life. Fibrous tumors retard cessation, and render the occurrence of flooding more frequent, which is not surprising, considering how profuse the menstrual flow becomes so soon as a fibrous body is developed in the womb. I have a patient, now fifty-four, in whom a large fibrous tumor began at thirty-three; and ever since, the menstrual periods, though continuing regular, are extremely painful, and she passes a large quantity of blood, looking like treacle. After cessation the tumor may diminish, provided the change of life has not given an increased impetus.

S. A., tall, thin, with dark hair, aged fifty-one. The menstrual flow came at twelve, and continued regular but scanty. She married at twenty-one, but never conceived. The menstrual flow remained regular until forty-three, when a fright brought on flooding; the abdomen then swelled, and she was

thought pregnant. Flooding continued more or less for eight years, but it never interfered with her appetite, and only lately with her strength. The os uteri is enlarged, but in a healthy condition, and a large, flattened, fibrous tumor is easily detected lying across the abdomen. It may be well to mention that Dr. Bernutz has seen two cases of hæmatocele at the change of life, which were mistaken for fibrous tumors.

Those who have passed some time at the Salpêtrière know that frequently the fibrous bodies of the womb are found covered with cretaceous deposits, and that these bodies are sometimes replaced by calcareous concretions, which can be enucleated from the walls of the womb. I have twice seen a marked diminution of an ordinary fibrous tumor to coincide with the internal and external exhibition of iodine; syrup of iodide of iron and iodide of potassium, in drachm doses, being given twice a day, while the iodide of potassium ointment was used externally.

CANCER OF THE WOMB.—From forty to fifty is the "cancerous age" of woman's life, for the Registrar-General's Report shows, that previous to thirty years of age cancer is uncommon, both sexes being then equally liable to it; that between thirty and sixty cancer is very common, chiefly among women, and that the relative number of deaths from it, in women and men, is—

From 30 to 40 as 19 to 6
" 40 " 50 " 51 " 6
" 50 " 60 " 5 " 1

Out of 1200 cases extracted by Dr. Walshe from the Registrar-General's returns, 321 referred to males, 879 to females, and fifty only out of the 1200 occurred before thirty years of age. Leroy d'Etiolles found that out of 2781 cases of cancer, collected from French authors, the disease occurred 1227 times in persons above forty years of age, and 1061 times in those who had passed sixty. The womb was affected with cancer in 30 per cent. of these cases, and the breast in 24 per cent.

The statistics of Bayle, Boivin, and Lever, confirm the general belief that cancer of the womb is most frequent between forty and fifty; and Dr. West has lately shown that out

of 426 cases recently collected by Lebert, Kiwisch, Scanzoni, Chiari, and himself, 178 occurred from forty to fifty, and 122 from thirty to forty. The same fact results from the following table, published by Tanchou, *Gaz. des Hôp.*, 1838.

TABLE XXIX.

Age of 2568 *Women dying from Disease of the Sexual Organs in the Département de la Seine, from* 1830 *to* 1835.

Age.	Disease of Sexual Organs.	Cancer.	Remarks.
Before 20, . .	25		
From 20 to 30,	442	86	Maximum of inflammatory affections.
" 30 " 40,	279	212	
" 40 " 50,	137	402	Maximum of cancer.
" 50 " 60,	70	363	
" 60 " 70,	60	242	
" 70 " 80,	42	147	
" 80 " 90,	13	58	

The influence of cessation in producing cancer of the womb is to me evident. Sometimes it coincides with the first manifestation of uterine cancer, as in six out of Lebert's eighteen cases, and in twenty-seven out of fifty-three of my own. Cessation often gives great activity to cancer of the womb that had previously remained undetected, and more particularly then, does cancer progress insidiously and remain undiscovered until its work of destruction is nearly done. At the same time it is fair to admit with Duparque and Saucerotte, that however frequent cancer may be at the change of life, it often originated before; but if the average duration of uterine cancer be about sixteen months, as stated by Lebert and Dr. West, and if, as I have shown, the average duration of the dodging time is three years, then the coincidence between the change of life and the development of cancer becomes obvious. Sir C. M. Clarke considered the corroding ulcer of the womb peculiar to the change of life. With regard to treatment, I shall merely state,

that it may be better to narcotize a patient by means of the hypodermic injection of a solution of morphia than to leave her a prey to agonizing pains. When the womb, rectum, and bladder, are united into a foul cloaca, cold water irrigations promote cleanliness, assuage pain, and sometimes induce sleep.

UTERINE HYDATIDS occur so rarely from forty to fifty that I have never observed them; but Dr. Ashley thinks the complaint more dangerous at the change of life.

FATTY DEGENERATION OF THE WOMB.—Two cases have been lately recorded in which the muscular tissue of the womb was in a state of fatty degeneration, at fifty and fifty-three years of age.

OVARIAN TUMORS.—Like uterine polypi and fibrous tumors, ovarian cysts generally originate in the period of full sexual activity. Thus, Lebert found that out of fifty-nine chronic ovarian tumors,

15	occurred	from	20	to 30	years.
12	"		30	" 40	"
13	"		40	" 50	"

From the Fifth Report of the Registrar-General, it appears that out of 100,000 deaths from all causes, there were 1205 from ovarian dropsy, of which 362 occurred from forty to fifty, and out of forty-four deaths, occurring in London from this disease, in 1848, seventeen took place between forty and fifty; thus confirming the received notion that ovarian tumors are most fatal at the change of life, even if they have originated previously. Their march is often more rapid than that of uterine fibrous growths, and more speedily followed by a fatal termination; but, as far as the menstrual flow is concerned, ovarian are far less detrimental than fibrous tumors; for ovarian tumors, when developed many years before the average date of cessation, oftener diminish than augment the menstrual flow; which, in other cases, proceeds uninterruptedly, and is sometimes altogether absent. It seems to me that cessation is rather brought on earlier, than retarded by the growth of ovarian tumors, as I have stated in the chapter on the physiology of the change of life; at all events, they do not cause flooding

Cases of galloping ovarian tumors generally occur between twenty and forty; and when an ovarian tumor has remained quiescent for some time before the change of life, this will either give it increased activity, or make it stationary. There are many instances on record of women having lived to an advanced age without their comforts being much interfered with by an ovarian tumor; but if it be voluminous or on the increase, it is better the patient should run the risk of ovariotomy.

Taking into consideration that the internal exhibition of medicines is almost useless to check the progress of ovarian tumors, that tapping is only the beginning of the end, and that other surgical measures are of little or no avail, except in very exceptional cases, a pathologist cannot find words too strong to express his admiration for the American surgeons who originated ovariotomy, and for the British surgeons by whom it has been perfected. Mr. Spencer Wells, who must be mentioned as first amongst British ovariotomists, estimates the mortality of his first 300 cases to be 28.33. To ascertain how far this mortality was modified by the patients' age, I have constructed the following table out of 292 of his cases in which the operation had been completed:

TABLE XXX.

Mortality of Ovariotomy.

Rates of Mortality.	Averages.	Cases.
General averages of mortality at all ages, .	28.33	300
Average mortality in women under 40, .	31.64	158
Average mortality from 40 to 62, ...	28.35	134
Average mortality from 40 to 50 inclusive,	28.39	81
Average mortality from 50 to 62, ...	30.76	52

This table makes it clear that the change of life does not raise the mortality of ovariotomy; that it is attended with greater danger when performed after fifty, and is still more fatal in women under forty years of age. The practitioner will, however, bear in mind that when once ovariotomy has become desirable, it is not wise to defer it long.

MAMMARY IRRITATION AND SWELLING.—This is only noted in fourteen out of my 500 cases, though no doubt it was much more frequent. The breasts are swollen and painful, the nipples sore, and sometimes distil a milky or a glutinous fluid. Friction, pressure, or moving the arm, increases the sufferings, which may be appeased by constitutional treatment, by an atropia liniment, and by wearing cotton-wool next the skin. Spontaneous ecchymosis sometimes marks the breasts at this period, and Dr. Semple has published a case in which a bloody discharge from the nipples continued, every month, for five years after cessation. I attend a lady who for more than a year after the change of life had, every three weeks, a painless exudation of a considerable quantity of red serum, lasting for several days.

Velpeau thought neuralgia of the breast, as well as its neuromatic tumors, were most frequent at the change of life. A liniment or an ointment containing glycerine and sulphate of atropia is the best application in such cases.

NON-MALIGNANT MAMMARY TUMORS.—Velpeau attributed these to diseased menstruation at puberty and to the change of life, or to pregnancy, and diseases of the womb; and says truly that, after cessation, they cease to increase and often diminish, so their extirpation should not be determined upon too soon. Gardanne relates two cases in which the mammary tumor appeared at cessation, and was cured by leeches. My two cases yielded in a few weeks to leeches and applications of iodide of lead ointment. Mr. Erichsen finds unilocular cysts of the breast to be most frequent from forty-five to fifty.

Velpeau united in the following table 281 cases of hypertrophy, cysts, nodosities, and adenoid tumors of the breast, and found that they were said to have originated at the following ages:

Up to 30,	76
30 " 40,	64
40 " 50,	80
50 " 60,	19
60 " 80,	31
Age not noted,	11
	281

Cancer.—Galen observed, that cancer of the breast was frequent at the change of life, and Mr. Paget has lately shown that it occurs most frequently from forty-five to fifty years of age.

TUMOR OF THE MEATUS URINARIUS.—I have met with three cases of erectile tumor of the meatus urinarius, a disease thought by Sir C. M. Clarke to occur most frequently in the earlier part of woman's life; but I am confirmed in the contrary opinion by Mr. B. Norman, who has observed fifteen cases, eleven of which were in women during or after the change of life. Four of my five cases came under treatment after the ménopause, and in a case that I attended with Dr. Bennet, the tumor, successfully treated by him several years before the change, returned after the ménopause, and was so very hard that we thought it preferable to cut it away, which was skilfully done by my friend. At the time of the operation there was very little bleeding; and when, on the following morning, it became necessary to draw off the urine, I found it largely mixed with blood, and as this continued to be the case during the following days, I came to the conclusion that the blood had been oozing from the wounded urethra into the bladder. At all events, one application of the undiluted perchloride of iron prevented any subsequent mixture of blood with the urine. Diseases of the bladder and urethra so frequently afflict men from the fortieth to the sixtieth year, and women of the same age are so free from such diseases, that this may be viewed as compensating favorably for the many other diseases to which women are specially liable.

DISEASES OF THE KIDNEYS.—The forty-nine cases in which women were, for a few months, habitually subject to an increased amount of the urinary salts, are rather to be considered as instances of a critical evacuation from the blood than as proofs of diseased action, and the same applies to *Hæmaturia* —a rare disease—which has been observed by Chouffe, Menville, and Dusourd. My cases yielded to bleeding and mild treatment. The eight cases of pain in, and difficulty of, passing water, and those of incontinence of urine, soon yielded to diluents, baths, and mild measures.

The following case of inflammation of the pelvis and calices of the kidneys is instructive:

CASE 46.—The wife of a physician, who was born and had passed the first fifteen years of her life in India, enjoyed excellent health until the change of life, which unfortunately coincided with the sudden loss of a dear sister and an unusually cold spring. The result of which was a sluggish liver, dyspepsia, pains in the bladder, dysuria, and abundant deposits in the urine. As this condition did not abate, the husband consulted an eminent surgeon, who tested the urine by nitric acid, and said the patient was suffering from albuminuria. This diagnosis was unfortunately told her, for she had dabbled in medicine, and knew that albuminuria meant an ugly future, so she gave herself up to despair, made her will, settled the distribution of her trinkets, and kept her husband without sleep for two nights, which was decidedly useful, as it suggested to him the advisability of consulting Dr. Owen Rees. He also examined the urine, not neglecting to use the microscope, and he found there was pus in the urine, and he supposed it to be caused by a renal calculus. Two months of careful dieting, Vals water, and rest, removed pus from the urine and all symptoms of disease, and as there never was either persistent pain or paroxysms of pain in the region of the kidneys; as there was no bloody urine, and no calculus was ever passed—may be there was none—but merely inflammation of the pelvis and calices of the kidneys. Towards the following autumn the patient had a relapse, so she went to the south of France and derived so much benefit from passing the winter in a milder climate that she has continued to do so.

CHAPTER X.

DISEASES OF THE GASTRO-INTESTINAL ORGANS.

TABLE XXXI.

Liability to Diseases of the Gastro-intestinal Organs in 500 Women.

Monthly toothache and swollen gums,	1
Monthly water-brash,	5
Hæmatemesis,	4
Repeated vomiting of mucus,	31
Jaundice,	6
Long-continued biliousness, induced or increased,	55
Dyspepsia,	37
Monthly dyspepsia,	1
Obstinate constipation,	23
Frequent diarrhœa,	45
Monthly diarrhœa,	5
Entorrhagia,	20
Monthly blood in motions for six months,	2
Pus in motions,	3
Inflammation of the rectum,	3
Blind piles,	62
Bleeding piles,	24
Piles bleeding every month,	1
Swelled abdomen,	26
Total,	354

This table means that 354 kinds of gastro-intestinal suffering were noted in 500 women at the change of life, and many of the 354 presented several kinds of gastro-intestinal disturbance. The practical bearing of this table is the great liability to biliousness, dyspepsia, diarrhœa, and piles. Later in life, the

tendency to jaundice, biliousness, and dyspepsia diminishes, and appetite and digestion improve; there is also less tendency to lose blood by the bowels; piles cease to bleed, and generally subside in advanced life.

BILIARY AND DYSPEPTIC AFFECTIONS.—The liability to derangements of the biliary apparatus at this period has been noted by Burns, Gendrin, Meissner, Otterburg, and Aran; by Sir C. Mansfield Clarke, Sir J. Simpson, Dr. Evory Kennedy, and Dr. West. Hepatitis and jaundice have been observed by Gardanne, and Sir H. Halford mentions having seen abscess of the liver at cessation.

The late Dr. B. Lane's observations on the coincidence of the derangement of the biliary secretions at the change of life, are true to nature:—"Nothing can be more common than to find severe biliary derangement occurring at or about the period of menstrual cessation; and, looking at the great physiological change which then takes place in connection with hepatic development, it is naturally to be expected. A woman will complain of being bilious—there may be a bitter, oily taste in the mouth, a burning in the throat, frontal headache, nausea, and even vomiting, the urine high-colored, the bile abounding in the alvine dejections, and, perhaps, causing heat and a stinging sensation in the rectum, the tongue furred, a biliary tinge pervading the cutaneous surface."

The worst cases of disease at the change of life for which I am consulted have been ascribed to a torpid condition of the liver by other medical men; and though the preceding table shows clearly how liable women are to sickness, dyspepsia, and biliousness at this epoch, it cannot give an idea of the obstinacy of the biliary symptoms in many of these cases. Thus, P. K. was a strongly-built woman, of a sanguine temperament, in whom the menstrual flow had been irregular for the last eight months; till then she had enjoyed good health, but since, in spite of purgatives, alteratives, and tonics, I found it difficult to set right the gastro-intestinal functions, or to improve the appearance of the tongue, which was permanently coated with a yellow fur.

CASE 47.—*Jaundice.*—Mrs. W. is a tall, stout lady, with dark hair, forty-nine years of age, and the mother of thirteen chil-

dren. The menstrual flow appeared at twelve, and continued regular until it ceased suddenly at forty-seven. Six weeks afterwards the skin became yellow, and she suffered considerably in the region of the liver. She was soon cured, but every three or four months there was a return of jaundice. This lady is habitually low-spirited, and so drowsy that she can neither read nor do fancy work during the day, and is restless at night. She has often flushes and chills, but no perspirations. After diminishing the size of the engorged liver, and curing the actual attack of jaundice by blue pill and alkalies, the question was, how to prevent that congestion of the liver which had returned with a certain kind of periodicity, since the sudden cessation of menstruation. I gave blue pill and alkalies for a week every month, and I established a free determination of blood to the skin, so that it might diminish the congestion of the internal organs, by warm baths, prolonged for two hours every other day, and daily scruple doses of the comp. sulphur powder. I advised 2 oz. of blood to be taken from the arm every third or fourth month, as might be otherwise indicated. Gentle perspirations soon showed that the blood currents were steadily setting in a right direction, health became good, and for the last two years there had been no return of jaundice. The same plan of treatment succeeded equally well in the following case.

CASE 48.—*Repeated jaundice at cessation.*—Mrs. H., a robust lady, with a bilious look, consulted me in June, 1854, being then fifty-five. The menstrual flow came at fifteen, and continued regular until she was forty-eight, when it ceased suddenly. She was then troubled with piles, which bled freely every six or eight weeks. This went on for six months. When the piles ceased bleeding, her skin became yellow, and the liver was found extending several inches below the edge of the false ribs. She has had several slight fits of jaundice, and her motions are often black, offensive, and "burn" the passage. It should be observed that both this and the patient in the previous case, had never been particularly bilious before cessation. The cause of long-continued biliousness at the change of life, is the congestion of the portal system, no longer relieved by the menstrual flow, so that the liver is overworked.

Thus I have seen jaundice occur in young women from the sudden suppression of the menstrual flow, and have sometimes noticed a persistent loss of appetite for months, notwithstanding the administration of alteratives and tonics. It must also be noted that when uterine diseases occur at the change of life, they are more frequently attended by biliary derangement, and by the secretion of an enormous quantity of bile.

TREATMENT.—The frequency and tenacity of biliary and dyspeptic affections at this period, explain why purgatives have been considered the principal medicines required; but an occasional purgative will have little effect; a systematic plan of treatment must be resorted to, and calomel or blue pill associated with the comp. ext. of coloc., or with the soap and aloes pill, is well borne and often required. Since my last edition, there has been an attempt to prove that mercury does not promote the flow of bile, but I submit that experiments made on healthy dogs, do not apply to diseased men and women. It is a matter of daily experiment to find, that while various purgatives repeatedly taken, bring away no bile, one dose of calomel will cause yellow, burning bile to pass in the motions, so I consider calomel and blue pill to be indispensable for the treatment of diseases of the liver at the change of life. The only tonics that should be given while the liver is thus engorged, are the diluted mineral acids, taken alone, or in some slightly bitter infusion, three times a day, before meals, and immediately after them fifteen drops of liq. potassæ, in a wineglass of water, and one or two effervescing draughts, with citric acid and carb. of soda and potash, should be also taken during the day. They may be flavored with syrup of ginger, or syrup of orange-peel, or ten to fifteen drops of chloric ether. Instead of porter and beer Seltzer water with light wine should be advised. Prolonged tepid baths are useful, and an occasional small bleeding may favor the action of the remedies. The late Dr. Wright attributed great efficacy to hydrochlorate of ammonia, which he gave in a mixture with hydrochloric acid. I have seen cases which resisted all treatment cured by a course of mineral waters at Vichy, or at Homburg, or Kissingen; the action of the waters being admirably assisted by

early hours, plain diet, and the complete change of all the associations of life.

VOMITING.—This is not uncommon during the change of life, sometimes accompanying the menstrual flow, and replacing it at others. This symptom generally yields to morphia, a twelfth or a sixth of a grain of the acetate being given in an effervescing draught, and repeated until sleep be induced. A patient, who for years had suffered from vomiting at the menstrual periods, is always relieved by less than half a grain of the acetate, while two grains taken in the twenty-four hours, will not always quell the vomiting of another patient. One patient had no other symptom than water-brash, which appeared at cessation, and recurred every month for eight months. Hufeland and Menville speak of the liability of women to hæmatemesis, which occurred in four of my cases.

DIARRHŒA.—This has been noted as occurring in an habitual manner, at this period, by Gendrin, B. de Boismont, and Chambon. It may constitute the only symptom of cessation, and should always be considered a critical discharge, and Portal saw its suppression by active remedies bring on anasarca. The advantages and disadvantages of diarrhœa at the change of life are well shown in the following cases:

CASE 49.—*Chronic diarrhœa.*—A tall, stout, and florid lady, aged fifty-seven, showed an hemorrhagic tendency by the abundance of the menstrual flow, the liability to dysentery, and by her numerous confinements being always accompanied by a flooding. When fifty, the lady met with severe family misfortunes, flooding ensued, the menstrual flow ceased to be regular, occurring, even now, as a mere show, after nervous excitement. Soon after fifty, she suffered from erysipelas in the head; and as a result of this, of cessation, and of mental shock, the lady remained long in a very nervous state. Ever since the ménopause, for the last four years, this patient has had three or four motions every day without pain or any debilitating effects, the appetite and digestion continued excellent, and the increased mucous flow from the intestines sufficiently relieved the constitution, as the health remained good, notwithstanding the absence of perspiration until lately.

CASE 50.—*Diarrhœa aggravated by cessation.*—Sarah C. is a

thin, nervous, chlorotic-looking single woman, of forty-seven. The menstrual flow appeared at fourteen, and continued regular until six months back, when it became very irregular. Flushes, perspirations, nervousness, and irritability were then troublesome, and twice during this period she has had to leave her place on account of diarrhœa. She states that, ever since the menstrual flow first appeared, she has always had from three to six motions a day, but was always most troubled at the menstrual periods. Until lately, however, this state of the bowels never interfered with her health or appetite, but now, six motions occurring daily, completely incapacitated her for work, although they were unattended by pain. I moderated the diarrhœa by blue pill and chalk mixture, and then prescribed my usual remedies with success.

Dr. Cockerton, of Montgomery, consulted me respecting a lady, aged fifty-three, who, during the dodging time, suffered from dysentery, then flooding, on its subsidence, from great relaxation of the bowels, with racking pains in the lower part of the abdomen, which occurred regularly every morning, and were evidently connected with uterine disease. Chambon also has seen the constitution thoroughly shattered by diarrhœa at the change of life. I have met with women who, in advanced age, had several semi-fluid motions in the course of the day, without suffering in the least, and Dr. Day has met with similar cases.

Treatment.—I seek to restrain the diarrhœa by diet and abstinence, but if that be insufficient, chalk mixture should be given, and after that small doses of Dover's powder with blue pill made up into pills. Extra clothing and exercise, a warm bath, and, if the patient be plethoric, a small bleeding may be useful. The following cases will show the plan to be adopted in cases of Entorrhagia:

Case 51.—*Periodical entorrhagia.*—Miss M., thin, nervous, and chlorotic, consulted me in 1853, being then forty-eight. The menstrual flow appeared at fifteen, and continued regular until about three years ago. For a year the flow was sometimes more, at others less, and it suddenly ceased two years ago, after a succession of frights, which thoroughly shook her nervous system. Her health, good until cessation, has been

bad ever since. She is often troubled with cough, leucorrhœa, and loss of power in the lower limbs. She has become unusually nervous, feels, at times, as if she were going into fits, talks of strange sensations in the head, as "if she had taken something to make her silly." This nervous state is peculiarly marked every three months, when she menstruates by the bowels for about six days. Several times a day she feels great pain at the lower part of the abdomen, there is then anal tenesmus, and she passes a small quantity of blood and mucus. This has occurred for the last two years, and during all this time there have been no flushes nor perspirations. In this case, nature actually did for two years what I have sometimes recommended,—to take a small quantity of blood from the system. I gave her the comp. camph. mixture before, the carbonate of soda after meals, 3 grs. of blue pill, with 2 of ext. of hyosc., on alternate nights, and a warm bath for an hour, every other day. This was continued for about a month with great amendment of the nervous symptoms, and a week before the time for the passing of blood by the bowels, I had 4 oz. of blood taken from the arm, which prevented the hemorrhage. I then advised the mixture and carb. of soda to be taken as before, and so much of sulphur and borax as would insure a comfortable action of the bowels. In a few weeks gentle perspirations had become habitual, and afforded great relief. This patient took the syrup of citrate of quinia and iron, in 60-drop doses, twice a day for two months, and became comparatively strong. I had again 4 oz. of blood taken away before the hemorrhage was due, and lately, when I saw the patient, she was in good health.

CASE 52.—*Repeated entorrhagia and hæmoptysis.*—Miss G., a tall, delicate-looking lady, consulted me in 1852. The menstrual flow appeared at sixteen, and it had been no source of trouble until two years ago, when it became irregular, sometimes missing for two or three months, sometimes being scanty, at others so abundant as to amount to a flooding. After shivering and griping pains, this patient has sometimes passed considerable quantities of blood and mucus, and once she brought up a large quantity of blood from the lungs. Since cessation took place, the passing of blood from the bowels has not been

more frequent, and notwithstanding continuous flushes and perspirations, she is very nervous, is troubled by sensations at the pit of the stomach, as if some one were sitting there, has choking sensations never before experienced, is very low-spirited, has crying fits, and though sleeping pretty well at night, could do so all day. What, however, the patient most complains of is, frequent recurrence of pain at the lower part of the abdomen, and for the last few nights the legs, the pudenda, and the seat, are much swollen. This led me to anticipate a recurrence of the entorrhagia, so I ordered a hot linseed poultice to the lower part of the abdomen at night, and an ounce of castor oil to be taken in the morning, during which day she passed "blood and corruption," and continued to do so with a great deal of griping for five days, after which all her abdominal suffering vanished. All her life, this patient had never less than three motions a day; the menstrual periods always ending with five or six motions a day; this being the habit of the body, it is easy to understand that for the last year, ever since cessation, the system should seek relief by the intestinal surface. With a view of remedying this state, I ordered the co. camph. mixture before, and the carb. of soda after meals, 3 grs. of blue pill, 1 of ext. of gentian, and 1 of ext. of hyoscyamus, every other night; 10 grs. of Dover's powder every other night; a belladonna plaster to be applied every week to the pit of the stomach, and warm baths to be taken for an hour on the alternate nights. This treatment was continued with considerable advantage for a month, when the baths and plasters were omitted, and the pills were only taken occasionally. Two months after I first saw the patient, I had 4 oz. of blood taken from the arm, and this was repeated three months later. I last saw her about a year ago, and she was well; neither the hemorrhage nor the menstrual flow had returned.

Constipation.—This was observed in twenty-three cases, and yielded to the continued use of mild but varied purgatives. In some cases the patients suffered severely from colics, as was the case with Mrs. T., aged forty-seven; the menstrual flow coming at fifteen, had left gradually at forty-five. Ever since cessation she had been constipated, instead of relaxed, as before; and during the last year she has been troubled every two

or three weeks with colic, flatulence, and sometimes vomiting. These symptoms coming on every night with greater severity, I prescribed pills containing 1 grain of ext. of opium and 3 of c. ext. of colocynth. Two pills nightly were at first required to lull the pain, and then one sufficed. This plan of treatment was effectual, the bowels being afterwards kept moderately open by the habitual use of sulphur.

HÆMORRHOIDS.—Gardanne has mentioned the case of a lady in whom cessation occurred at forty-eight; and, until seventy-five, when he attended her, she lost monthly a large quantity of blood from piles, and suffered from signs of plethora until the evacuation took place; and Stahl has seen similar cases. Menville gives one, in which, for ten years after cessation, hæmorrhoids occurred monthly. Gendrin and B. de Boismont have likewise noticed continuous or intermittent hemorrhoidal fluxes at cessation. The table which heads this chapter shows how frequently I have met with piles. The hæmorrhoidal discharges, the diarrhœa, the biliary affections of the change of life, all arise from one common cause,—the unrelieved plethora of the portal system; and when we bear in mind that the organs of reproduction, as well as the intestines, are principally innervated by ganglionic nerves, that the spinal nerves of the womb and the intestines arise from the same part of the spinal cord, that the veins of the uterus communicate mediately with the portal system, and that the last portions of both canals are contiguous, it is not surprising that, when the uterine discharge is arrested, the nervous energy and the sanguineous current which used thereby to find vent, should flow to the intestinal surface.

TREATMENT.—Although critical, the hæmorrhoidal flow is so disagreeable, that it should not be permitted to endure longer than can be helped, and in most cases it can easily be remedied by following my general rules of treatment. The occasional removal of 3 ounces of blood from the arm is clearly indicated, so is the compound sulphur powder, so useful in hæmorrhoidal affections, and rectal sedative injections to allay the local irritation, which continually draws the blood within its morbid circle of attraction. Cooling and astringent lotions and ointments to the hæmorrhoidal tumors are most useful.

INFLAMMATION OF THE RECTUM.—Without being subject to piles, women sometimes feel great heat, weight, and tenesmus in the rectum. It will sometimes cause a difficulty of passing water, and a sensation as if a foreign body were in the vagina. With repose and cooling lotions, these symptoms generally abate; though intractable cases will sometimes occur like the following, which is a remarkable instance of severe suffering caused by the change of life.

CASE 53.—*Inflammation of the rectum.*—Charlotte O., the wife of a plumber in good circumstances, is a short, average-sized woman, with brown hair, flushed, puffy, and damp face, downcast looks, seems drowsy, and looks as if she had been drinking; was forty-four. The menstrual flow appeared at eighteen, after pains flying about her; and soon after its appearance she suddenly felt something shoot through the ears, and her neck became stiff. She has never since been able to turn her head freely; and when she tries to do so, she feels something crack. The menstrual flow came regularly, but a fright would at any time cause it to appear. She married at twenty-three, and seven months afterwards she flooded, and lost much blood for two months; since then the catamenia often lasted for three weeks, and were accompanied by a difficulty of passing water. She has consulted many doctors, but no accurate examination was ever made. She never conceived, and has had no serious illness until lately. Although happily married she has become more nervous, more easily excited by the everyday occurrences of life; without ever having had any hysterical attacks. For the last seven years she has been frequently troubled by uneasy sensations "of fulness and rawness" at the pit of the stomach, the weight of the bedclothes annoying her. The menstrual flow has been irregular for the last eight months, coming every two or three months, and twice she has been flooded. Since then, she has been more subject to headaches, and to pain at the nape of the neck. Now she is often light-headed, giddy, forgetful; and so drowsy, that she is obliged to lie down, but only dozes a little. She is more sensitive to all stimuli, starts at the least noise, sometimes gets out of bed to stop the ticking of the clock, and cannot bear to be spoken to. Her nights are bad; and of late, three or four

times a week, she is awoke suddenly as if by the ringing of a bell in her ears, then she faints off, and it often takes her husband half an hour to bring her to her senses. Since the menstrual flow stopped a year ago, the epigastric sensations, the flushes, and the sweats were very frequent. There was pain on micturition and passing stools, and always more or less leucorrhœa, with bearing-down pains. On examination, I found the bladder free from all undue pressure. The womb had the size, form, and appearance, of a healthy virgin womb. I therefore considered this to be a case of intense functional derangement, caused by the cessation of the menstrual flow, and ordered her to lose 8 ounces of blood, and to follow up the bleeding by the application of five leeches to each side of the neck; to take the c. camphor mixture before meals, 3 grs. of blue pill, and 2 of ext. of hyoscy. every night; also 10 grs. of Dover's powder. Warm baths were afterwards ordered, but discontinued, because the patient nearly fainted so soon as the water reached her waist. Pediluvia were frequently given, and the nape of the neck and back part of the head were rubbed with camp. liniment, containing 1 drachm of laudanum to the ounce. The patient improved under this treatment, and in the course of a few weeks she had no more nervous fits at night. The pills were then omitted, the Dover's powder only given every other night; the mixture was continued, and she was told to have 3 ounces of blood taken from her every month. I lost sight of this patient until August 26th, 1853, when she was again suffering from many of the symptoms previously described. Three months before, a fright brought on a flooding, which lasted three weeks. No menstrual flow since, but distressing pelvic pains. On examining the womb, I found it healthy, but pressure to the rectum gave intense pain; and she said she had passed a membranous substance from the bowels. The camphor mixture was ordered, a teaspoonful of sulphur and borax every night, a scruple of nitre in a little barley-water twice a day, and a large belladonna plaster to be applied to the pit of the stomach. Sept. 19th.—Tongue furred, very yellow, constipation, bearing-down pains, sensations "as of fire, in the back passage." On making a careful examination, there was no fistula or fissure, the sphincter was hot and

contracted, the rectum also felt hot, and the finger gave pain. The mixture was ordered before meals, carbonate of soda afterwards. Blue pill and hyoscyamus every night, to be followed by half an ounce of castor oil in the morning. Three times a day injections were to be made into the rectum, with half linseed-tea and half a strong decoction of poppy-heads; and a little later, with equal quantities of saturnine lotion and decoction of poppy-heads. Various other injections were tried to relieve the distressing symptoms which often returned; but nothing succeeded so well as making a full injection of tepid water, to cleanse the bowels, and then injecting an ounce of the following solution, with 2 ounces of warm water:

Lotio plumbi acetatis, ...	℥iv.
Tinct. hyoscyami, ...	℥iv.

Feb. 17th, 1854.—The menstrual flow had been absent for the previous eighteen months, when, two months ago, she had a pale red vaginal discharge, which returned the following month. She came to the dispensary on account of a relapse of the inflammation of the rectum, which yielded to the measures previously described. In May, 1856, I again saw the patient for a slight relapse; and as she complained of a yellow discharge, I examined, and found the vagina shorter and narrower, and the neck of the womb smaller than on a previous examination. Pressure on the rectum gave great pain, and indicated the seat of the disease. The patient soon got better; but during the five years I have watched this case, I have seldom met with a more distressing example of suffering caused by the change of life. Now her health is in every respect better; she is forty-eight, and there has been no menstrual flow for more than three years.

I have had several other cases of inflammation of the rectum, in which I have found the daily injection of one ounce of a lotion, containing sulphate of zinc and hydrocyanic acid, was very useful, and at night I made the patients apply to the sphincter, a small quantity of cold cream, to each ounce of which was added one grain of sulphate of atropia.

PERMANENTLY SWELLED ABDOMEN.—This condition, at the

change of life, is generally to be accounted for by an increased deposit of fat in the omentum and in the abdominal walls,—a physiological condition treated of at page 72. Sometimes the swelling is principally caused by distressing flatulent distension of the bowels, without diarrhœa or constipation. I have known this to recur every month for several years after cessation, lasting two or three days, and yielding to carminatives, tonics, and such measures as insured the gentle action of the bowels.

CHAPTER XI.

DISEASES OF THE SKIN AT THE CHANGE OF LIFE.

TABLE XXXII.

Liabilities of the Skin to Disease at the Change of Life in 500 *Women.*

Flushes,	287
Dry flushes,	14
Legs and feet burning, and very painful,	2
Hands painfully hot,	3
Distressing aching under the finger nails,	2
Peeling off of the nails,	4
Falling off of all the finger nails,	1
Perspirations,	201
Monthly perspirations,	2
Cold perspirations,	13
Sweats,	89
Undetermined cutaneous eruptions,	18
Nettle-rash,	5
Erysipelas,	4
Eczema brought on,	3
Eczema increased,	2
Ecchymosis,	3
Shingles,	1
Herpes circinatus,	1
Prurigo,	3
Pruritus, or itching without apparent lesion,	5
Œdematous, or swelled legs,	16
Monthly swelling of legs for three days for a year,	1
Œdematous, or puffy face,	3
Inflammation of legs, and painful distension of their superficial veins,	3
Carried forward,	686

Brought forward, ...	686
Varicose veins induced, ...	1
Varicose veins aggravated, ...	1
Ulcerated leg, ...	7
Boils in seat, and in other parts, ...	3
Abscess in finger, ...	2
Abscess in armpit, ...	2
Abscess in neck, ...	2
Abscess in groin, ...	1
Total, ...	705

Thus, 500 women divided 705 modes of slight or severe cutaneous suffering at this epoch, many suffering in various ways at the same time. The liability to cutaneous disease passes off in after-life; and though flushes and perspirations may occasionally occur, they are no longer a source of annoyance. Prurigo and eczema are, however, sometimes very troublesome to women in advanced age.

These affections may be registered under three heads,—flushes, sweats, and cutaneous affections. I shall be brief on the last, but as the flushes and sweats of the change of life have never been sufficiently studied, I shall devote a few lines to their pathological import, referring the reader to p. 76 for further details.

FLUSHES.—This is the popular name, and I adopt it, because it is short and expressive. "Hot blooms," is another expression, which faithfully indicates what really occurs. Flushes are mentioned by nosologists under the name of *ardor volaticus*, or *fugax*. Romberg correctly calls it one of the cutaneous hyperæsthesiæ, and notices its greatest frequency at the change of life. Flushes may be increased to a painful extent by external heat, over-clothing, hot rooms, hot drinks, and overfeeding, by the checking of diarrhœa or of leucorrhœa. Some feel so faint under their influence, that they must have air, or they would swoon. M. C. could drop down with weakness when the flushes came on. Dry heats are morbid flushes; they torment a patient without the subsequent relief of perspiration. The cheeks are not the only parts susceptible of burning sensations, for two patients complained most of the burning of

the legs and feet; cold water applications did not much abate the annoyance, but warm did; and at night they slept with their feet out of bed. Three others complained bitterly of similar sufferings in their hands, and of aching under their finger nails. The flushes are sometimes preceded by chilly sensations, and some women tremble with internal cold, and remain, for a long time, habitually cold, notwithstanding the flushing of the face. One patient continued in this state for seven years; she had slight flushes without perspiration, was very nervous, and often fainted. Others feel so cold that they approach the fire, reaction then soon coming on, they fly to the window. In such cases, the perspirations will be cold and clammy, denoting debility, and the congestion of some internal organ. When the flushes are thus anomalous, they are often preceded by ganglionic dysæsthesia; strange sensations, which have been said to resemble "pulses, like a live animal throbbing in the stomach," or "the fluttering of a bird;" sensations which vanish on the appearance of perspiration.

SWEATS.—Perspiration was carried to a morbid extent in seventy-nine out of 500 women, who often complained of heavy perspirations. They were constantly wiping the sweat off the face, their hair was often wet, they were obliged to change their linen twice a day, and although slightly covered, their bedclothes became soaked. Gardanne, Chambon, and B. de Boismont, notice the occurrence of sweats at this period, but the little importance attached to them is shown by the fact, that in an elaborate article, with a host of references, on idiopathic sweating, J. Frank merely quotes Tissot's having observed it at the change of life. It would seem that sweating ought to be more beneficial than perspiration, but a very accurate observer, Sanctorius, remarks: "That perspiration which is beneficial, and most clears the body of superfluous matter, is not what goes off with sweat, but that insensible steam or vapor which in winter exhales to about the quantity of fifty ounces in the space of one natural day." "Sweat is always from some violent cause; and as such—as static experiments demonstrate—it hinders the insensible exhalation of the digested perspirable matter."

The intensity of the force which impels the sweat from the

skin is shown, not only by the length of time it may last, but by its often resisting all the attemps made by women to diminish or suppress it. They wear less clothing, take cold drinks, place themselves in draughts, but still the impulse is stronger than their efforts, for they seldom succeed. In general, it is some internal focus of active congestion which checks perspiration, or renders it cold and clammy. When this occurs, great debility is felt, with an increase of epigastric pain in some, in others, pseudo-narcotism; which, as Dusourd remarks, is immediately relieved when the skin perspires. It is very strange that these sweats are sometimes prolonged for months, without weakening women, or preventing their becoming fat, though the fat often seems to be half liquid. Women of a nervous or chlorotic type, have habitually a cold clammy perspiration, like that coming from the blanched skin of those who are vomiting or in syncope; a passive permeability of the skin, determined by loss of nervous power.

TREATMENT.—I have shown the advantages of promoting perspiration to check the serious disturbance of the internal organs, how then should it be restrained so as to inconvenience the patient as little as possible? Blood is the fuel, the interstitial and molecular combustion of which keeps alive the continuous heat of the body. The relative superabundance of blood is often the cause of the superabundant heat, and therefore of the perspirations, as shown by the case related by J. Frank, of a man who became subject to excessive perspirations after the supression of an hæmorrhoidal discharge. Diminish the mass of blood by taking three or four ounces from the arm at two or three months' interval, and the sweats will also diminish. The irritability of the nervous system may be relieved by the sedative preparations already recommended. Baths are very useful. They should be tepid, and prolonged for an hour at least. Tissot recommends them highly, and their effects may be increased by adding from one-half a pint, to a pint of camphorated vinegar. The saline matters, which are otherwise removed by perspiration, must be directed to the kidneys, by giving the salines, as already indicated, the acidulated and effervescing drinks, and small doses of nitre and borax. I cannot too strongly recommend mineral acids for

those who suffer much from heats and sweating, for they tone the nerves as well as cool the blood. The greatest amount of testimony runs in favor of sulphuric acid, which I have found most effectual. Thus Pereira bears witness to the sedative action of sulphuric acid in distressing tingling of the skin; Hufeland gave Haller's acid elixir, which is a mixture of one part of sulphuric acid in volume with three parts of spirits of wine; other Germans give at the change of life, Mynsicht's elixir, in which sulphuric acid and alcohol are associated with aromatics. I order from 10 to 20 drops of the diluted acid to be taken in a wineglassful of cold water, three times a day, or else the acidum sulphuricum aromaticum of the British Pharmacopœia; but these remedies require time, and will not satisfy a patient whose cheeks burn repeatedly in the course of the day, and who wants something to give immediate relief. Then a lotion of 1 ounce of cherry-laurel to 5 of elder-flower water, may be tried, or water in which camphor has been allowed to float, or vinegar and water, or water containing 1 or 2 ounces of camphorated vinegar to the pint. Chomel advised the treating the hot cheeks by a kind of steam douche, and I have found it useful to do so two or three times a day; in the same way burning feet and hands are soothed by soaking them in hot water. Some patients have derived great benefit from using, with the powder puff, one of the following powders:

Flush Powder, No. 1.

Carmine,	½ gr. or less.
Nitrate of bismuth,	ʒj.
Camphor,	ʒss.
Oil of bitter almonds,	gtt. ij.
Starch,	ʒij.

Flush Powder, No. 2.

Carmine,	½ gr. or less.
Camphor,	ʒss.
Oxide of zinc,	ʒj.
Otto of roses,	gtt. j.
Starch,	ʒij.

Some describe with energy their sufferings in winter nights, when, bathed in perspiration, they are afraid of turning, lest they should be chilled by the damp cold, and have given me their warmest thanks for suggesting that a long, thin, flannel dress be worn over the night-gown, and that they should lie on

a horse-hair or a spring mattress, instead of on a feather bed. Suppressed perspiration may be recalled by a warm bath, by letting the patient sit, wrapped in a blanket, on a common cane chair, under which a lighted spirit-lamp is placed, and in ten or fifteen minutes the skin will perspire profusely. Gentle, continuous perspiration may be promoted by sulphur and sudorifics.

CUTANEOUS AFFECTIONS.—Out of 500 women, forty-one had some form of cutaneous disease, but whether the proportion would have been smaller in 500 men, between forty and fifty years of age, I cannot determine, though I have certainly found eczema very intractable and relapsing, and prurigo very troublesome at this epoch, and both complaints more common than would appear from my statistics. Dr. Ashwell thinks skin diseases by no means rare at the change of life. Dusourd and B. de Boismont say that lupus is frequent; and the latter observes that herpetic affections, long forgotten, then reappear. Gendrin, Gardanne, and myself have repeatedly seen erysipelas at this period, and a case is cited by Tissot of erysipelas of the face occurring fifteen times during the two first years after cessation, less frequently in the two next years, and only once during the fifth year. Mr. Erasmus Wilson, on the other hand, informs me, that he does not consider women more liable to cutaneous diseases at this critical period than at any other, though when such diseases do arise, they are peculiarly obstinate. Prurigo and eczema he deems the most frequent. Mr. Harvey has frequently seen eczematous eruption of the auricle, and behind the ear, begin at the change of life, last for many years, and resist all treatment, until at last it disappeared by a spontaneous effort of nature. This has occurred several times in my own practice. Mr. T. Hunt assures me that, the change of life has often been followed by acne rosacea, lichen in the face or elsewhere, prurigo, and especially prurigo pudendi. He says, that chronic, scaly affections of the skin, such as lepra and psoriasis, which have commenced before this critical period, are unaffected by it, and that cutaneous affections seldom disappear spontaneously at this epoch. A patient of mine had never had the slightest rash before the ménopause, whereas nettle-rash appeared four times in the year which followed ces-

sation ; I believe it, therefore, to have been caused by this crisis, as erysipelas was in Tissot's case. M. B., aged fifty, first menstruated between her eighteenth and nineteenth years, with little previous disturbance, and continued regular until twenty, when she married. She had nine children, the last when forty-four. At forty-eight, she had several floodings, but without much increase of pains in the head. The catamenia ceased at forty-nine; this was followed by no disturbance of health, except three months after, by a severe attack of nettle-rash, on the chest and body, which disappeared on the proper medicines being administered; twice, however, it has occurred at irregular periods, and she applied for relief, at the Farringdon Dispensary, for a fourth well-marked attack of the disease on the lower part of the body and the thighs. Alibert observed some cutaneous eruptions appear twice only in life—once before first menstruation, and again at its cessation. I have twice known both epochs to be preceded by an abundant eruption of boils, and Gardanne mentions the same occurrence. That form of lupus which attacks the vulva, and was confounded with cancer, until the distinction was clearly made by Huguier, is as frequent at the change of life as at any other period, but is not observed after fifty. Amongst the poor, ulceration of the leg, without being peculiarly intractable, is not an unfrequent complaint at this epoch. Œdematous legs I have frequently noticed, and I have had two cases of varicose veins occurring then for the first time. For the local treatment of prurigo, eczema, and other cutaneous affections of the pudenda, I refer to that of the affections determining nymphomania, p. 237. The practitioner will bear in mind that pathologists are adopting what has been long taught in Vienna and in Paris, that prurigo senilis depends on pediculi, and that the disease is therefore propagated by the patient's clothes. Patients occasionally take strange fancies about insects. A dispensary patient was intensely miserable for many months, because, said she, lice kept coming out of her body. I gave her sulphur baths, and I often tried to ascertain whether there was truth in the assertion, but I always found the skin perfectly clean, and without a rash. Another patient, who was very queer in

the head, for six months after the ménopause, had the same notion, and actually put some bugs in a bottle, and used to exhibit them as having come out from different parts of the body. I again bear witness to the admirable effects produced upon cutaneous affections by the external and internal exhibition of the mineral waters of Harrogate and Aix in Savoy.

CHAPTER XII.

OTHER AFFECTIONS OCCURRING AT THE CHANGE OF LIFE IN 500 WOMEN.

TABLE XXXIII.

Liability of 500 Women to other Affections at the Change of Life.

Gout,	3
Rheumatic fever,	3
Rheumatic joints,	7
Hypertrophy of the heart,	1
Subacute peritonitis,	1
Ascites,	1
Consumption, aggravated,	3
Bronchitis, aggravated,	4
Asthma, aggravated,	1
Hæmoptysis,	6
Ruptured varicose veins,	3
Epistaxis,	9
Chronic otorrhœa,	1
Total,	43

GOUT.—According to Hippocrates, women are not subject to gout until after cessation; but he alluded to Grecian women living in retirement. When women lead the life of men, they become to a certain extent, liable to their disorders; and, therefore, Seneca might have been justified in saying of the women of his time, that they were liable to gout "ob varii generis debachationes." As far as my experience goes, women are little subject to gout, but I have, like Chomel and Ferrus, ob-

served it at puberty and when menstruation was fully established, and most frequently after the ménopause, when it assumed an anomalous form, as noticed by Dr. Gairdner. Even then, it is a disease of rare occurrence, so much so that I do not remember more than four cases amongst women of the upper classes during the last twelve years, subsequent to my collecting from dispensary and other patients the statistics on which this work was originally founded.

The following table, extracted from the Registrar-General's Report, throws light on this subject:

TABLE XXXIV.

Relative Mortality from Gout in both Sexes at successive Periods.

Ages.	Males.	Females.
5	...	11
5 to 10		
10 " 15	...	212
15 " 20	67	
20 " 30	168	56
30 " 40	541	121
40 " 50	732	291
50 " 60	1148	152
60 " 70	458	103
70 " 80	186	
Total, . .	3300	946

This shows that women are most liable to gout at puberty and at the change of life; but before the menstrual flow is regularly established, gout generally assumes an anomalous character, being accompanied by singular nervous symptoms, of which I have seen some remarkable instances. At the change of life, and after cessation, this disease may follow its usual course, and Trousseau has observed that hysterical symptoms may be cut short by an attack of gout. It is curious to note that up to fifteen, no seeds of gout have been evolved in the male sex, whereas many had grown up in the female, and

that while in man, the liability to gout goes on increasing from fifteen to sixty, in women, puberty seems to sweep away its tendency, for there is none from fifteen to twenty, though after that age, when the body has attained its full size, the seeds develop themselves, gout becoming most frequent between forty and fifty.

RHEUMATIC FEVER.—The statistics of rheumatic affections likewise evince that from forty to fifty a change takes place in the female constitution, for up to forty more men than women die from rheumatic affections, while from forty to fifty the deaths from these affections are as 604 women to 295 men, and from fifty to sixty as 755 women to 338 men. This increased liability to rheumatism after the ménopause may, perhaps, depend on the skin being then more given to perspire, and on the greater frequency of checked perspiration. The rheumatism of those who are nursing can be thus accounted for.

ASCITES.—I have seen only two cases of this affection at the change of life, but I have very frequently noticed the pitting, on pressure, of both the lower limbs at this period. On referring to the Registrar-General's Reports, I find that more women, than men, die of dropsy from forty to fifty, in the proportion of nine to five; and from fifty to sixty, in the proportion of fourteen to six. Portal and Gardanne have both stated, that women were particularly subject to dropsical effusions of an obstinate nature at the change of life. Breschet, in his researches on *Hydropsies Actives*, relates the case of a lady: menstruation came at thirteen, and ceased at forty-eight, though the characteristic phenomena of cessation are said to have only appeared at fifty-four; namely, great debility, flushes, vertigo, headache. At fifty-five, after a fit of anger, the whole body swelled considerably, except the arms. There was fever, furred tongue, headache, oppression, and sediments in the urine. Twelve days after this, eighteen leeches were applied to the anus, and the swelling diminished; on the eighteenth day an emetic was given, and on the twenty-eighth all signs of effusion had disappeared. This case brings to my recollection another instance of dropsy, caused by severe and sudden mental perturbation. A gentleman, aged twenty-five, who had habitually enjoyed good health, was standing at the altar and about to be

married, when some one stepped forward to forbid the ceremony. On his return home his legs swelled, serum was effused in the cellular tissue, ascites appeared, the urine was albuminous, and in a few months the patient died. A post-mortem examination was not permitted.

CONSUMPTION.—On consulting those practitioners whose experience in pulmonary disorders enables them to speak authoritatively on the subject, I find them of my opinion, that the morbid influence of the change of life on consumption is not great. If consumption appear at this period, it has previously existed under a latent form, as in the three cases noted in my statistics, in which the disease was aggravated by the ménopause, and I have not met with another case during the last twelve years. I must observe, however, that Dubois mentions that two ladies who were saved from phthisis by the regular establishment of the menstrual flow, fell victims to that complaint at the change of life without any other apparent cause. B. de Boismont says, that in ten cases he has been the sad spectator of the rapid progress of consumption at this epoch, which had previously remained stationary for years. More recently, Dr. Emmett, of New York, has recorded his conviction that dysmenorrhœa, by causing the early cessation of menstruation, is a frequent cause of phthisis in comparatively young women; but this assertion does not accord with my own observation.

BRONCHITIS.—In four of my cases, habitual bronchitis dated from the change of life, and seemed to have been caused by it; and Bordeu has noted similar cases.

HÆMOPTYSIS.—This occurred to eight patients, and was evidently caused by the change of life arresting an habitual hemorrhage. Bordeu has also observed cessation to be followed by monthly attacks of congestion of the lungs, and by spitting of blood.

HEART-DISEASE.—The heart suffers very little at the change of life; my experience on this point again coincides with that of Dr. Quain, for out of my 500 cases, there was only one of hypertrophy with morbid sounds, in a woman, aged sixty, and she presented the only instance of *arcus senilis*.

EPISTAXIS.—This critical effort of nature may become a dis-

ease, and the nose may require plugging. Menville gives a case wherein slight epistaxis occurred repeatedly until the dodging time, when it became very abundant until the menstrual flow ceased. I have seen women subject to this complaint for from three to five years after cessation, but never to any great extent.

RUPTURED VARICOSE VEINS.—Stahl has observed this to occur at cessation. I have seen it in three instances, and I have repeatedly been told that after cessation the legs had swelled and were hard, hot, and red, the capillaries of the skin being greatly injected.

HYPERTROPHY OF THE THYROID GLAND.—In three patients, during the last few years, I have seen cessation followed by an increase of the thyroid gland to about treble its usual size. All three patients had long suffered from chronic uterine disease; two got well under the influence of iodine rubbed in and taken internally, and I lost sight of the other.

OTORRHŒA.—I have noticed this complaint to come on periodically with the menstrual flow, and the fact has not escaped Mr. Harvey's notice. M. S., aged fifty-two, suffered much from otorrhœa for two years previous to the first menstrual flow, very little from it while menstruation continued regular, but it returned with renewed pertinacity some months before cessation took place.

SPINAL DEVIATION.—B. de Boismont has related two cases in which very extensive deviation immediately followed the change of life, but in all probability a certain amount of deviation had occurred at puberty, and had remained stationary until the ménopause; and I have known this to happen once.

PTYALISM.—Abundant and long-continued salivation has been noticed by Bouchut as a symptom of cessation, but I have only noticed it to occur at that time in connection with very intense cerebral neuralgia.

INDEX.

Aconitina, 161
Aix in Savoy, 118, 282
Alkaline, 110
  waters, 118
Apathy at change of life, 190
Aphasia, 181
Aphonia, 225
Ardor volaticus, 276
Arsenic, 238
  in gangliopathy, 163
Ascites, 285
Atrophy of the breasts, 33
  ovarian, 33
  uterine, 33

Baths, 116, 125, 212
Belladonna, 160
Bichloride of mercury, 237
Biliary derangement, 263
Bleeding at the change of life, 102, 211
Blisters in gangliopathy, 160
Breasts, atrophy of, 33
  benignant tumors of, 259
  irritation of, 259
  malignant tumors of, 260
Bronchitis, 286

Camphor, 114, 161, 213
Cancer, mammary, 260
Cancer of the womb taken for the change of life, 58
  uterine, 255
Cardialgia, a misapplied term, 149
Castor, 115
Cerebral neuralgia, 168
  neuralgia, management of, 128
Cervix, its diseases, 245
  obliteration of, 250
  stricture of, 250
Cessation, 17
  comparative date of, 39
  date of, 37
  early causes of, 49
Cessation, late, 40
    causes of, 46
  taken for pregnancy, 60
Chalybeate waters, 118
Change of life a cause of insanity, 21
  a cure for uterine disease, 21
  a cure of insanity, 21, 22
  its curative influence. 20
  its morbid liabilities, 88
  its real diseases, 90
  the constitution strengthened by it, 23
Childbirth late in life, 45
Chloral, 115, 214
Chloroform, 115, 160
Chlorosis, its diagnosis from cessation, 54
Climacteric decay, 25
  disease, 17
  insanity, 184
Cœliac neuralgia, 155
Cold, a cause of gangliopathy, 153
Coma in relation to menstruation, 175
Conium, 114
Constipation, 269
Constitutional taints, causing diseases of change of life, 93
  weakness, a cause of diseases of cessation, 92
Consumption, 286
Critical periods, 19
Cutaneous affections, 280
  functions, hygiene of, 125

Deafness, 226
Debility, a prominent symptom of gangliopathy, 153
Delirium, 185
Demonomania, 198
  spinal, 287
Deviations, uterine, 252
Diarrhœa, 266
  at the change of life, 106

Diet, 123
Digestive functions, hygiene of, 123
Dipsomania, 197
Discharge, uterine, bloody, 231
mucus, 234
purulent, 235
sero-sanguinolent, 234
bloody, from breasts, 259
Diseases of cessation, blood theory of, 98
nerve theory of, 98
of the ménopause, prognosis of, 91
Displacements, uterine, 252
Diuretics, 109
Dodging time, 17
its duration, 65
Dyspepsia, 263
sinking, 150
Dysuria, 261

Eczema, 280
Electricity, 224, 226
Emetics, use and abuse, 162
Emotion, its influence on the ganglionic nerves, 151
Entorrhagia, 267
Epigastric remedies, 160
Epilepsy, 180
Epistaxis, 287
Erotomania, 239
Erysipelas, 281
Exercise, theory of, 125
Exfoliation, uterine, 249
Eyes, neuralgia of, 226

Faintness, 156
Fatty degeneration of the womb, 257
Fecundity, late, 40
Fibroids at the change of life, 56
Fibrous tumors, 254
Flannel, 125
Flooding, 230
Flushes, 76, 276
dry, 76
Flush powders, 279
Fungosities, uterine, 249
Furor uterinus, 239

Galvanism, 226
Ganglionic dysæsthesia, 142
hyperæsthesia, 139
nervous system, its physiology, 136
paralysis, 145, 153
theory of mental diseases, 206
Gangliopathy, causes of, 150, 209
Gangliopathy, definition of, 138
diagnosis of, 153
forms of, 139
symptoms of, 153, 206
termination of, 157, 208
treatment, 158
Gastralgia, a misapplied term, 149
Gout, 283

Hæmatocele, 255
Hæmaturia, 260
Hæmoptysis, 286
Hæmorrhoids, 270
Harrogate, 118, 282
Headache, 166
Heart disease, 286
Heat, a cause of gangliopathy, 153
chemical, 78
nervous, 78
Hemiplegia, 199
Hemorrhage at the change of life, 83
Henbane, 114, 161
Herpes pudendi, 287
Homicidal mania, 198
Hydatids, uterine, 257
Hydrochlorate of ammonia, 265
Hydrocyanic acid, 114
Hydropathic appliances, 212
Hypodermic injection, 257
Hypertrophy of the cervix, 245
Hypochondriasis, 188
Hysteria at the change of life, and after cessation, 178
term misapplied to gangliopathy, 146, 177
to pseudo-narcotism, 175
Hysterical asthma, 146

Ice in gangliopathy, 163
Impulse to deceive, 199
Indian hemp, 114, 161
Injections, intra-uterine, 233, 249, 250
vaginal, 247
Insanity, 183
Insomnia, 115, 127
Intra-uterine pessary, 252
Issues, 118

Jaundice, 263

Kidneys, disease of, 260
Kleptomania, 197

Labia, herpetic disease of, 287
inflammation of, 236
Leeches for diseases of cessation, 106

Leipothymia, 156
Lethargy in relation to menstruation, 175
Leucorrhœa, 234
at cessation, 82
of old women, 250
Lupulin, 115
Lupus, pudendal, 281

Mania, 187
Manual labor, 128
Marriage after the ménopause, 120, 122
at the change of life, 120
late in life, 42
Melancholia, 188
Mental adaptability, 129
disease, theory of, 201
power, loss of, 128
Menstrual eccentricities causing diseases of change of life, 93
flow, its sudden stoppage causing disease, 95
flow, termination of, 71
function, comparative duration of, 67
function, duration of, 66
Menstruation, diseases of, at cessation, 231
in relation to respiration, 75
late, 40
vicarious, 83
Mercury, 265
Metritis, internal, acute, 247
chronic, 249
Mineral acids, 110, 162, 265, 278
waters, 117, 265
Moral hygiene, 129
Morphia, 114
Mucous discharges at cessation, 82
Muscular system, hygiene of, 125

Natural history of disease at cessation, 101
Nervousness, 165
Nervous system, hygiene of, 126
Nettle-rash, 281
Neuralgia, cerebral, 167
lumbo-dorsal, 219
ocular, 226
of cutaneous nerves, 227
ovario-uterine, 240
pudendal, 240
Nitrate of silver in gangliopathy, 162
Nymphomania, 239

Obesity, 72
Opium, 111
Otorrhœa, 287
Ovarian evolution, 33
involution, 33
tumors, 257
Ovaries, pathology of, 252
physiology of, 38
Ovulation, 72

Pain, dorsal, 217
epigastric, 218
lumbo-dorsal, 217
rheumatic, 227
Paraplegia, 221
Perchloride of iron, 249, 260
Periodicity of cessation phenomena, 74
Perspiration, 277
at cessation, 76. 82
chemistry of, 80
Pessary, intra-uterine, 252
Physiology of the change of life, 31
Plasters, 115, 160
Poisons, causing gangliopathy, 158
Polypi, uterine, 254
Pregnancy after cessation, 69
chances of, 44
mistaken for cessation, 59
spurious, at the change of life, 61
Principles of hygiene, 119
Prolapsus, uterine, 253
Prurigo latens, 240
pudendi, 237, 280
Pseudo-narcotism, 170
Ptyalism, 287
Pudenda, inflammation of, 236
neuralgia of, 240
prurigo of, 237
Purgatives at the change of life, 106
Pyelitis, 261

Rectum, inflammation of, 271
Rheumatism, 285

Saline mineral waters, 118
Salivation, 287
Sciatica, 224
Sedatives, 110, 214
Self-absorption, 132
Sexual organs, hygiene of, 120
influence of their disuse on diseases of the change of life, 96
Single state, influence of, on diseases of the change of life, 96
Skin diseases, 280

Sleep, explanation of, 177
its apportionment, 127
Social position, its influence on diseases of the change of life, 96
Spermatorrhœa, its nervous symptoms ascribed to gangliopathy, 152
Spinal deviation, 287
Strychnia, 242
in gangliopathy, 163
Sudorifics, 115
Sugar in urine, 110, 155
Suicidal mania, 198
Sulphur, 108
Sulphuric acid, 110
Sulphurous waters, 117
Suppositories, 114
Sweats, 277
at cessation, 76
on division of ganglionic nerves, 79
Syncope, 156

Tea, 124
Temper, 127, 196
Temperamental peculiarities, a cause of diseases of change of life, 92
The change of life, its diagnosis, 53
Theories of diseases of cessation, 98
Theory of mental disease, 201
Thyroid gland, hypertrophy of, 287
Trades, their influence on diseases of the change of life, 97
Travelling, 128
Treatment of diseases of change of life, main indications, 102
Tumors, mammary, 259
Tumors, neuromatic, 259
of the meatus urinarius, 260
ovarian, 257
uterine, 254
Turkish baths, causing gangliopathy, 153

Ulceration of the cervix, its diagnosis from cessation, 54
of the os uteri, 246
Uncontrollable impulses, 193
Urea in urine, 126
Urinary deposits at cessation, 76
Uterine affections, causing diseases of cessation, 93
hydatids taken for change of life, 57
polypus, its diagnosis from cessation, 56
Uteromania, 239
Uterus, calcification of, 252
rupture of, 251

Vaginitis, 235
Vagus, neuralgia of, 150, 155
Varicose veins, rupture of, 287
Veratria, 161
Vomiting, 151, 266
Vulvitis, 236

Wine, 123
Woman, her power in society, 130
objects for her ambition, 130

Zinc in gangliopathy, 162
lotion, 236

THE END.

NOW READY.

THE PHYSICIAN'S VISITING LIST FOR 1875.

FOR VARIOUS STYLES AND PRICES, SEE PAGE 25 OF THIS CATALOGUE.

PHILADELPHIA,
January, 1875.

CATALOGUE

OF

LINDSAY & BLAKISTON'S

MEDICAL,

DENTAL AND PHARMACEUTICAL

PUBLICATIONS.

MESSRS. LINDSAY & BLAKISTON ask the attention of the Medical Profession to the extensive list and varied character of their publications and to the Classified Index of them annexed.

ALL THEIR PUBLICATIONS can be had from or through BOOKSELLERS in any of the large cities of the United States or Canada. When, for any reason, it is inconvenient thus to procure them, they will be furnished direct by mail or express upon receipt of a Post-office order, draft or check for the amount ordered.

IN ADDITION to their own publications, they keep on hand a full and complete assortment of all Medical Books published in the United States; and, by special arrangement with Messrs. J. & A. CHURCHILL and other Medical Publishers of London, they can supply many important English Medical Works at greatly reduced prices; such as are not on hand they can import promptly to order.

AS SPECIAL AGENTS OF THE SYDENHAM SOCIETY in the United States, they are prepared to receive Subscribers at Ten Dollars per Annum, and supply any of the back years. Complete lists of works published will be furnished upon application.

DEALERS IN MEDICAL BOOKS will be supplied on the most favorable terms, and will be furnished with copies of this Catalogue, without charge, for distribution among their customers if desired.

CLASSIFIED INDEX

TO

LINDSAY & BLAKISTON'S PUBLICATIONS.

ANATOMY.

Rindfleisch's Text-Book of Pathological Histology..... 28
Wilson's Anatomist's Vade Mecum..... 37
Handy's Text-Book of Anatomy..... 18
Hilles's Pocket Anatomist..... 19
Jones and Sieveking's Pathological Anatomy..... 20
Holden's Manual of Dissections..... 18
" Human Osteology..... 18
Wilks & Moxon's Pathological Anatomy.. 36

BRAIN AND NERVOUS SYSTEM.

Bucknill and Tuke's Psychological Medicine..... 9
Radcliffe on Epilepsy, Paralysis, &c..... 29
Tuke's Influence of the Mind on the Body 35
Elam on Cerebria..... 15
Sheppard on Madness..... 32
Sankey's Lectures on Mental Diseases.... 31
Van der Kolk's Pathology and Therapeutics of Mental Diseases..... 63

CHEST, HEART, THROAT, ETC.

Waters on the Chest..... 38
Fothergill on the Heart..... 15
Stokes on the Heart and Aorta..... 31
Cohen on Inhalation..... 11
Greenhow on Bronchitis..... 17
Mackenzie on the Throat and Nose.....
Mackenzie on Growths in the Larynx..... 22
Mackenzie on the Laryngoscope in Diseases of the Throat..... 22
Mackenzie's Pharmacopœia of the Hospital for Diseases of the Throat..... 22
Thorowgood on Asthma..... 35
Barth and Roger on Auscultation and Percussion..... 7
Dobell on Winter Cough..... 13
Ruppaner's Laryngoscopy..... 30
Cohen on Croup..... 11

CHILDREN (DISEASES OF).

Meigs and Pepper's Practical Treatise on Diseases of Children..... 23
Tanner and Meadows's Diseases of Infancy and Childhood..... 33
Ellis's Practical Manual of the Diseases of Children..... 15
Hillier's Clinical Treatise on Children ... 18
Holmes's Surgical Diseases of Children.. 19

CANCER.

Marsden's New Mode of Treating Cancer 25
Arnott on Cancer..... 6

CHEMISTRY, BOTANY, ETC.

Bloxam's Chemistry, Inorganic & Organic 8
" Laboratory Teaching..... 8
Murphy's Review of Chemistry..... 23
Reese's Syllabus of Chemistry..... 29
Darlington's Flora Cestrica..... 14
Bentley and Trimen's Medicinal Plants..

DEFORMITIES.

Adams on Club-Foot..... 6
Brodhurst on Deformities..... 9
Prince's Plastic and Orthopedic Surgery. 27
" Galvano-Therapeutics..... 27

DENTAL SCIENCE.

Harris's Principles & Practice of Dentistry 18
" Dictionary of Dental Surgery... 18
Richardson's Mechanical Dentistry..... 29
Taft's Operative Dentistry..... 33
Tomes's Dental Surgery..... 35
" Dental Anatomy and Physiology 35
Wedl's Dental Pathology..... 37
Leber and Rottenstein on Dental Caries. 21
Coles's Mechanical Dentistry..... 12
" Deformities of the Mouth..... 12
Heath's Injuries and Diseases of the Jaws 19
Fox on the Human Teeth..... 16
Robertson on Extracting Teeth..... 29
British Journal of Dental Science..... 7

DICTIONARIES.

Harris's Dictionary of Dental Surgery and Medical Terminology..... 18
Sweringen's Pharmaceutical Lexicon..... 32
Cooper's Surgical Dictionary..... 11
Cleaveland's Pronouncing Medical Lexicon 12

EYE AND EAR.

Soelberg Wells on Diseases of the Eye... 38
" on Long, Short, and Weak Sight..... 38
Lawson's Diseases and Injuries of the Eye 21
Macnamara's Manual of Diseases of the Eye..... 22
Dixon's Guide to Diseases of the Eye..... 14
Walton's Surgery and Diseases of the Eye 38
Liebreich's Ophthalmoscopic Atlas..... 21
Jones on Defects of Sight and Hearing... 20
Power's Student's Guide to Diseases of the Eye..... 26
Dalby on Diseases and Injuries of the Ear 15
Toynbee on the Ear, by Hinton..... 34
Allen's Aural Catarrh.....

ELECTRICITY.

Tibbitts's Hand-Book of Medical Electricity 35
Althaus's Medical Electricity 6
Reynolds's Clinical Uses of Electricity ... 28
Duchenne's Localized Electrization 14

FEMALES (DISEASES OF).

Hewitt's Diagnosis, Pathology and Treatment of the Diseases of Women 17
Byford's Medical and Surgical Diseases of Women 9
Byford on the Uterus 9
Atthill's Clinical Lectures on Diseases of Women 6
Dillenberger's Handy-Book of Women and Children's Diseases 14
Agnew's Laccrations of the Female Perineum 6
Tilt's Change of Life in Women 34
Savage's Female Pelvic Organs 32
" Nature of the Surgical Diseases of the Female Pelvic Organs 32
Scanzoni's Diseases of Women 31
Hodge on Fœticide and Abortion 20

FEVERS.

Stillé's Epidemic Meningitis 31
Flint on Continued Fever 16

FORENSIC MEDICINE & TOXICOLOGY.

Woodman and Tidy's Hand-Book of Forensic Medicine 38
Tanner's Memoranda of Poisons 33

GENERATIVE & URINARY ORGANS, SYPHILIS, ETC.

Acton on the Reproductive Organs 7
" on Prostitution 7
Black on the Functional Diseases of the Renal, Urinary & Reproductive Organs 10
Harley on the Urine & its Derangements 17
Legg on Examination of the Urine 21
Thompson on the Urinary Organs 34
" on Calculous Diseases 34
Lewin on the Treatment of Syphilis 22
Durkee on Gonorrhœa and Syphilis 14
Parker's Modern Treatment of Syphilis. 27
Gant's Irritable Bladder 16
Buzzard's Syphilitic Nervous Affections. 7
Tyson on Examination of Urine 33

HYGIENE AND POPULAR MEDICINE.

Parkes's Practical Hygiene 26
Wilson's Hand-Book of Hygiene 37
Hufeland's Art of Prolonging Life 19
Chavasse's Mental Culture and Training of Children 11
Ryan's Philosophy of Marriage 28
Walker on Intermarriage 38
Routh's Infant Feeding .....
Veitch's Hand-Book for Nurses .....

KIDNEYS AND THE LIVER.

Beale on Kidney Diseases, Urinary Deposits and Calculous Disorders 8
Basham's Diagnosis of Kidney Diseases .. 7
Ward on the Liver and Intestinal Canal, 37
Habershon on the Liver 17

MATERIA MEDICA AND THERAPEUTICS.

Biddle's Materia Medica for Students 9
Waring's Practical Therapeutics 36
Headland on the Action of Medicines 19
Brunton's Experimental Investigation into the Action of Medicines 10
Thorowgood's Student's Guide to Materia Medica 34
Beasley's Book of 3000 Prescriptions 10
Pereira's Physician's Prescription Book .. 26
Wythe's Pocket, Dose and Symptom Book 36
Fothergill on the Action of Digitalis 15
Bouchardat's Abstract of Therapeutics, &c. 7
Philip's Materia Medica and Therapeutics.

MICROSCOPICAL.

Beale's How to Work the Microscope 8
Carpenter on the Microscope and its Revelations 11
Beale's Microscope in Medicine 8
Martin's Microscopical Mounting 24

MANUALS, ETC., FOR STUDENTS.

Mendenhall's Manual of Examinations ... 23
Chew on Medical Education 12
Cleaveland's Pronouncing Medical Lexicon 12
Pereira's Pocket Prescription Book 26
Wythe's Pocket, Dose and Symptom Book 36

MISCELLANEOUS.

Allingham on the Rectum 5
Basham on Dropsy 7
Birch on Constipation 9
Clarke's Diseases of the Tongue 11
Carson's University of Pennsylvania 11
Cobbold on Worms 12
Dunglison's History of Medicine 15
Gross's Medical Biography 16
Holden on the Sphygmograph 20
Liveing on Megrim, Sick-Headache, &c.. 21
Pennsylvania Hospital Reports 26
Physician's Visiting List 25
" Case Record and Prescription Blanks 27
Ribl and O'Conner's Physician's Account Book 30
Ross's Graft Theory of Disease 29
Reports on the Progress of Medicine, &c. 25
Sieveking on Life Assurance 30
Sydenham Society's Publications (new).. 31
" " " (old)... 32
Wright on Headaches .....

OBSTETRICS.

Cazeaux's Text-Book of Obstetrics..... 13
Meadows's Manual of Midwifery..... 24
Schultze's Lecture Diagrams..... 31
Hodge on Fœticide and Abortion..... 20
Rigby's Obstetric Memoranda..... 30
Roberts's Student's Guide to Midwifery... 29
Tyler Smith's Obstetrics..... 34
Clay's Hand-Book of Obstetric Surgery.. 12

PRACTICE OF MEDICINE.

Aitken's Science & Practice of Medicine. 5
Roberts's Theory & Practice of Medicine. 28
Tanner's Practice of Medicine..... 33
Trousseau's Clinical Medicine..... 34
Fagge's Principles and Practice of do..... 15
Maxson's Practice of Medicine..... 23
Chambers's Clinical Lectures..... 12
Foster's Lectures and Essays on Clinical Medicine..... 16

PATHOLOGY.

Paget's Surgical Pathology..... 26
Wedl's Dental Pathology..... 37
Virchow's Cellular Pathology..... 36
Stillé's General Pathology..... 31

PHYSIOLOGY.

Sanderson's Physiological Hand-Book ... 30
Marshall's Physiological Diagrams..... 23
" " Anatomy..... 23
Reese's Analysis of Physiology..... 29
Tyson's Cell Doctrine..... 33
Beale on Disease Germs..... 8
" Bioplasm, or Physiology of Life.... 8
" Protoplasm, or Matter and Life..... 8
Carpenter's Human Physiology..... 11

PHARMACEUTICAL.

Sweringen's Pharmaceutical Lexicon..... 32
Beasley's Druggist's Receipt Book..... 10
" Book of 3000 Prescriptions..... 10
" Pocket Formulary..... 10
Cooley's Cyclopedia of Practical Receipts 13
Branston's Hand-Book of do..... 10
Reese's American Medical Formulary.... 29
Lescher's Elements of Pharmacy..... 21
Squire's Companion to the British Pharmacopœia..... 32
Proctor's Practical Pharmacy..... 27
Squire's Hospital Pharmacopœias.....

RHEUMATISM, GOUT, ETC.

Garrod on Gout and Rheumatic Gout.....
Adams on Rheumatic and Strumous Diseases.....
Adams on Rheumatic Gout..... 6
Hood on Gout and Rheumatism..... 20

SURGERY.

Harris's Dental Surgery..... 18
Norris's Contributions to Surgery..... 25
Paget's Surgical Pathology..... 26
Swain's Hand-Book for Surgical Injuries 30
Prince's Plastic and Orthopedic Surgery. 27
Clark's Outlines of Surgery and Surgical Pathology..... 13
Hewson's Use of Earth in Surgery..... 20
Druitt's Surgeon's Vade Mecum..... 14
Maunder's Operative Surgery..... 24
Heath's Minor Surgery..... 19
Cooper's Surgical Dictionary..... 11
Thompson's Lithotomy and Lithotrity ... 34
Haucock on the Foot and Ankle..... 20

STIMULANTS AND NARCOTICS.

Anstie on Stimulants and Narcotics..... 7
Sansom on Chloroform..... 31
Miller on Use and Abuse of Alcohol..... 24
Lizar on Use and Abuse of Tobacco..... 22

SCIENTIFIC.

Hardwich and Dawson's Photography ... 19
Overman's Practical Mineralogy..... 25
Ott on the Manufacture of Soap..... 25
Peisse's Whole Art of Perfumery..... 27
Piggott on Copper Mining, &c..... 27
Beeton's Book of Household Management 10

STOMACH, DIGESTION, ETC.

Fenwick on the Stomach..... 16
Leared on Digestion..... 21
Birch on Constipation..... 9

SKIN AND HAIR.

Wilson on the Skin and Hair..... 36
Godfrey on the Hair..... 16
Anderson on Eczema..... 7

MEDICAL, DENTAL,
PHARMACEUTICAL AND SCIENTIFIC BOOKS

PUBLISHED BY

LINDSAY & BLAKISTON, Philadelphia.

AITKEN (WILLIAM), M. D.,

Professor of Pathology in the Army Medical School, &c.

THE SCIENCE AND PRACTICE OF MEDICINE. THIRD American, from the Sixth London Edition. Thoroughly Revised, Remodelled, many portions Rewritten, with Additions almost equal to a Third Volume, and numerous additional Illustrations, without any increase in bulk or price. Containing a Colored Map showing the Geographical Distribution of Disease over the Globe, a Lithographic Plate, and nearly 200 Illustrations on Wood.

Two volumes, royal octavo, bound in cloth, price, . . $12.00
" " " " leather, . . 14.00

For eighteen months Dr. Aitken has been engaged in again carefully revising this *Great Work*, and adding to it many valuable additions and improvements, amounting in the aggregate almost to a volume of new matter, included in which will be found the adoption and incorporation in the text of the "*New Nomenclature of the Royal College of Physicians of London;*" to which are added the *Definitions* and the Foreign Equivalents for their English names; the New Classification of Disease as adopted by the Royal College of Physicians, &c.

The American editor, MEREDITH CLYMER, M. D., has also added to it many valuable articles, with special reference to the wants of the AMERICAN PRACTITIONER.

The work is now, by almost universal consent, both in England and the United States, acknowledged to be in advance of all other works on *The Science and Practice of Medicine.* It is a most thorough and complete TEXT-BOOK for students of medicine, following such a systematic arrangement as will give them a consistent view of the main facts, doctrines, and practice of medicine, in accordance with accurate physiological and pathological principles and the present state of science. For the practitioner it will be found equally acceptable as a work of reference.

ALLINGHAM (WILLIAM), F. R. C. S.,

Surgeon to St. Mark's Hospital for Fistula, &c.

FISTULA, HÆMORRHOIDS, PAINFUL ULCER, STRICTURE, PROLAPSUS, and other Diseases of the Rectum, their Diagnosis and Treatment. Second Edition, Revised and Enlarged by the Author. Price $2.00

This book has been well received by the Profession; the first edition sold rapidly; the present one has been revised by the author, and some additions made, chiefly as to the mode of treatment.

The *Medical Press and Circular*, speaking of it, says: "No book on this special subject can at all approach Mr. Allingham's in precision, clearness, and practical good sense."

The London Lancet: "As a practical guide to the treatment of affections of the lower bowel, this book is worthy of all commendation."

The Edinburgh Monthly: "We cordially recommend it as well [illegible] *of Physicians and Surgeons.*"

ATTHILL (LOMBE), M. D.,

Fellow and Examiner in Midwifery, King and Queen's College of Physicians, Dublin.

CLINICAL LECTURES ON DISEASES PECULIAR TO WOMEN. Second Edition, Revised and Enlarged, with Six Lithographic Plates and other Illustrations on Wood. Price $2.25

The value and popularity of this book is proved by the rapid sale of the first edition, which was exhausted in less than a year from the time of its publication. It appears to possess three great merits: First, It treats of the diseases very common to females. Second, It treats of them in a thoroughly clinical and practical manner. Third, It is concise, original, and illustrated by numerous cases from the author's own experience. His style is clear and the volume is the result of the author's large and accurate clinical observation recorded in a remarkable, perspicuous, and terse manner, and is conspicuous for the best qualities of a practical guide to the student and practitioner. — *British Medical Journal.*

ADAMS (WILLIAM), F. R. C. S.,

Surgeon to the Royal Orthopedic and Great Northern Hospitals.

CLUB-FOOT: ITS CAUSES, PATHOLOGY, AND TREATMENT. Being the Jacksonian Prize Essay of the Royal College of Surgeons. A New Revised and Enlarged Edition, with 106 Illustrations engraved on Wood, and Six Lithographic Plates. A large Octavo Volume. Price $6.00

ADAMS (ROBERT), M. D.,

Regius Professor of Surgery in the University of Dublin, &c., &c.

RHEUMATIC GOUT, OR CHRONIC RHEUMATIC ARTHRITIS OF ALL THE JOINTS. The Second Edition. Illustrated by numerous Woodcuts, and a quarto Atlas of Plates. 2 Volumes. Price $8.50

ALTHAUS (JULIUS), M.D.,

Physician to the Infirmary of Epilepsy and Paralysis.

A TREATISE ON MEDICAL ELECTRICITY, Theoretical and Practical, and its Use in the Treatment of Paralysis, Neuralgia, and other Diseases. Third Edition, Enlarged and Revised, with One Hundred and Forty-six Illustrations. In one volume octavo. Price . $6.00

In this work both the scientific and practical aspects of the subject are ably, concisely, and thoroughly treated. It is much the best work treating of the remedial effects of electricity in the English language. — *New York Medical Record.*

ARNOTT (HENRY), F.R.C.S.

CANCER: its Varieties, their Histology and Diagnosis. With Five Lithographic Plates and Twenty-two Wood Engravings. Price $2.25

AGNEW (D. HAYES), M.D.,

Professor of Surgery in the University of Pennsylvania.

THE LACERATIONS OF THE FEMALE PERINEUM, AND VESICO-VAGINAL FISTULA, their History and Treatment, with *numerous* Illustrations. Octavo. Price $2.00

Prof. Agnew has been a most indefatigable laborer in this department, and his work stands *deservedly high* in the estimation of the profession. It is well illustrated, and full descriptions of the operations and instruments employed are given. — Canada Lancet.

ACTON (WILLIAM), M.R.C.S., ETC.

THE FUNCTIONS AND DISORDERS OF THE REPRODUCTIVE ORGANS. In Childhood, Youth, Adult Age, and Advanced Life, considered in their Physiological, Social, and Moral Relations. Third American from the Fifth London Edition. Carefully revised by the Author, with additions. $3.00

Mr. Acton has done good service to society by grappling manfully with sexual vice, and we trust that others, whose position as men of science and teachers enable them to speak with authority, will assist in combating and arresting the evils which it entails. The spirit which pervades his book is one which does credit equally to the head and to the heart of the author. — *British and Foreign Medico-Chirurgical Review.*

SAME AUTHOR.

PROSTITUTION: Considered in its Moral, Social, and Sanitary Aspects. Second Edition, Enlarged. Price $5.00

ANSTIE (FRANCIS E.), M.D.,

Lecturer on Materia Medica and Therapeutics, etc.

STIMULANTS AND NARCOTICS. Their Mutual Relations, with Special Researches on the Action of Alcohol, Ether, and Chloroform on the Vital Organism. Octavo. $3.00

ANDERSON (M'CALL), M.D.,

Professor of Clinical Medicine in the University of Glasgow, &c.

ECZEMA. The Pathology and Treatment of the various Eczematous Affections or Eruptions of the Skin. The Third Revised and Enlarged Edition. Octavo. Price $3.00

BUZZARD (THOMAS), M. D.,

Physician to the National Hospital for Paralysis and Epilepsy.

CLINICAL ASPECTS OF SYPHILITIC NERVOUS AFFECTIONS. 12mo. Cloth. Price $1.75

BASHAM (W. R.), M.D., F.R.C.P.,

Senior Physician to the Westminster Hospital, &c.

AIDS TO THE DIAGNOSIS OF DISEASES OF THE KIDNEYS. With Ten large Plates. Sixty Illustrations. Price . $2.00

SAME AUTHOR.

ON DROPSY, AND ITS CONNECTION WITH DISEASES OF THE KIDNEYS, HEART, LUNGS AND LIVER. With Sixteen Plates. Third Edition. Octavo. $5.00

M. BARTH AND M. HENRI ROGER.

A MANUAL OF AUSCULTATION AND PERCUSSION. A new Translation, from the Sixth French Edition. . . . $1.25

BOUCHARDAT (A.).

ANNUAL ABSTRACT OF THERAPEUTICA, PHARMACY, AND TOXICOL

M. J. De Rosset, M. D. . .

BEALE (LIONEL S.), M.D.

DISEASE GERMS: AND ON THE TREATMENT OF DISEASES CAUSED BY THEM.

PART I.—SUPPOSED NATURE OF DISEASE GERMS.
PART II.—REAL NATURE OF DISEASE GERMS.
PART III.—THE DESTRUCTION OF DISEASE GERMS.

Second Edition, much enlarged, with Twenty-eight full-page Plates, containing 117 Illustrations, many of them colored. Demy Octavo. Price $5.00

This new edition, besides including the contents revised and enlarged of the two former editions published by Dr. Beale on Disease Germs, has an entirely new part added on "The Destruction of Disease Germs."

SAME AUTHOR.

BIOPLASM. A Contribution to the Physiology of Life, or an Introduction to the Study of Physiology and Medicine, for Students. With Numerous Illustrations. Price $3.00

This volume is intended as a TEXT-BOOK for Students of Physiology, explaining the nature of some of the most important changes which are characteristic of and peculiar to living beings.

PROTOPLASM, OR MATTER AND LIFE. Third Edition, very much Enlarged. Nearly 350 pages. Sixteen Colored Plates. One volume. Price $4.50

PART I. DISSENTIENT. PART II. DEMONSTRATIVE. PART III. SUGGESTIVE.

HOW TO WORK WITH THE MICROSCOPE. Fourth Edition, containing 400 Illustrations, many of them colored. Octavo. Price $7.50

This work is a complete manual of microscopical manipulation, and contains a full description of many new processes of investigation, with directions for examining objects under the highest powers, and for taking photographs of microscopic objects.

ON KIDNEY DISEASES, URINARY DEPOSITS, AND CALCULOUS DISORDERS. Including the Symptoms, Diagnosis, and Treatment of Urinary Diseases. With full Directions for the Chemical and Microscopical Analysis of the Urine in Health and Disease. The Third Edition. Seventy Plates, 415 figures, copied from Nature. Octavo. Price $10.00

THE USE OF THE MICROSCOPE IN PRACTICAL MEDICINE. For Students and Practitioners, with full directions for examining the various secretions, &c., in the Microscope. Fourth Edition. 500 Illustrations. Octavo. Preparing.

BLOXAM (C. L.),

Professor of Chemistry in King's College, London.

CHEMISTRY, INORGANIC AND ORGANIC. With Experiments and a Comparison of Equivalent and Molecular Formulæ. With 276 Engravings on Wood. Second Edition, carefully revised. Octavo. Price, in cloth, $4.50; leather, ... $5.50

SAME AUTHOR.

LABORATORY TEACHING; OR PROGRESSIVE EXERCISES *IN* PRACTICAL CHEMISTRY. Third Edition. With *Eighty-nine* Engravings. Crown Octavo. Price . . . $2.00

BRODHURST (B. E.), F.R.C.S.,

Surgeon to the Orthopedic Department of St. George's Hospital, &c.

THE DEFORMITIES OF THE HUMAN BODY. A System of Orthopœdic Surgery. With numerous Illustrations. Octavo. Price $3.00

BIRCH (S. B.), M.D.,

Member of the Royal College of Physicians, &c.

CONSTIPATED BOWELS; the Various Causes and the Different Means of Cure. Third Edition. Price $1.00

BUCKNILL (JOHN CHARLES), M.D., & TUKE (DANIEL H.), M.D.

A MANUAL OF PSYCHOLOGICAL MEDICINE: containing the Lunacy Laws, the Nosology, Œtiology, Statistics, Description, Diagnosis, Pathology (including Morbid Histology), and Treatment of Insanity. Third Edition, much enlarged, with Ten Lithographic Plates, and numerous other Illustrations. Octavo. Price $8.00

This edition contains upwards of 200 pages of additional matter, and, in consequence of recent advances in Psychological Medicine, several chapters have been rewritten, bringing the Classification, Pathology, and Treatment of Insanity up to the present time.

There are ten lithographic plates representing the handwriting of the insane and the morbid cerebral changes revealed by the microscope, assisted by wood-engravings indicating the classification of the convolutions of the brain.

Thirty tracings of the pulse in various forms of insanity, made by the Sphygmograph, have also been added.

BIDDLE (JOHN B.), M. D.,

Professor of Materia Medica and Therapeutics in the Jefferson Medical College, Philadelphia, &c.

MATERIA MEDICA, FOR THE USE OF STUDENTS. With Illustrations. Sixth Edition, Revised and Enlarged. Price $4.00

This new and thoroughly revised edition of Professor Biddle's work has incorporated in it all the improvements as adopted by the New United States Pharmacopœia just issued. It is designed to present the leading facts and principles usually comprised under this head as set forth by the standard authorities, and to fill a vacuum which seems to exist in the want of an elementary work on the subject. The larger works usually recommended as text-books in our Medical schools are too voluminous for convenient use. This will be found to contain, in a condensed form, all that is most valuable, and will supply students with a reliable guide to the course of lectures on Materia Medica as delivered at the various Medical schools in the United States.

BYFORD (W. H.), A.M., M.D.,

Professor of Obstetrics and Diseases of Women and Children in the Chicago Medical College, &c.

PRACTICE OF MEDICINE AND SURGERY. Applied to the Diseases and Accidents incident to Women. Second Edition, Revised and Enlarged. Octavo. Price, cloth, $5.00; sheep . . $6.00

This work treats well-nigh all the diseases incident to women, diseases and accidents of the vulva and perineum, stone in the bladder, inflammation of the vagina, menstruation and its disorders, the uterus and its ailments, ovarian tumors, diseases of the mammæ, puerperal convulsions, phlegmasia alba dolens, puerperal fever, &c. Its scope is thus of the most extended character, yet the observations are concise, but convey much practical information. —*London Lancet.*

SAME AUTHOR.

ON THE CHRONIC INFLAMMATION AND DISPLACEMENT OF THE UNIMPREGNATED UTERUS. A New, Enlarged, and Thoroughly Revised Edition, with Numerous Illustrations. Octavo. $3

Dr. Byford writes the exact present state of medical knowledge on the subjects presented in his book, and does this so clearly, so concisely, that the diseases of the uterus will always meet the appeal of the popular standard work. — Buffalo

BLACK (D. CAMPBELL), M. D.,

L. R. C. S. Edinburgh, Member of the General Council of the University of Glasgow, &c., &c.

THE FUNCTIONAL DISEASES OF THE RENAL, URINARY, and Reproductive Organs, with a General View of Urinary Pathology. Price $2.50

CONTENTS.

Chap. 1. On the Conditions that affect the Secretion of the Urine, with special reference to Suppression.
" 2. Retention of Urine; its Varieties, Causes, and Treatment.
" 3. Irritable Bladder, Strangury.
Chap. 4. On the Pathology and Treatment of Nocturnal Enuresis, and Spermatic Incontinence.
" 5. Sterility in the Male.
" 6. Male Impotence.
" 7. Anomalous Urethral Discharges.

The style of the author is clear, easy, and agreeable, . . . his work is a valuable contribution to medical science, and being penned in that disposition of unprejudiced philosophical inquiry which should always guide a true physician, admirably embodies the spirit of its opening quotation from Professor Huxley. — *Philada. Med. Times.*

BEASLEY (HENRY).

THE BOOK OF PRESCRIPTIONS. Containing over 3000 Prescriptions, collected from the Practice of the most Eminent Physicians and Surgeons — English, French, and American; comprising also a Compendious History of the Materia Medica, Lists of the Doses of all Officinal and Established Preparations, and an Index of Diseases and their Remedies. Fourth Edition, Revised and Enlarged. Price, $2.50

This NEW edition of Dr. Beasley's Prescription Book, although presented in a much more compact form and at a greatly reduced price, has been thoroughly revised, and an account of all the new medicines lately introduced, with the formulas of the new Pharmacopœias added. Carefully selecting from the mass of materials at his disposal, the author has aimed to compile a volume sufficiently comprehensive, in which both physician and druggist, prescriber and compounder, may find under the head of each remedy the manner in which that remedy may be most effectively administered, or combined with other medicines in the treatment of disease. The alphabetical arrangement of the book renders this easy. A short description of each medicine is also given, and a list of the doses in which its several preparations may be prescribed.

BY SAME AUTHOR.

THE POCKET FORMULARY: A Synopsis of the British and Foreign Pharmacopœias. Ninth Revised Edition. Price . $2.50

THE DRUGGIST'S GENERAL RECEIPT BOOK AND VETERINARY FORMULARY. Seventh Edition. Price. . . $3.50

BRUNTON (T. LAUDER), M.D., D.Sc.,

Lecturer on Materia Medica in the Medical College of St. Bartholomew's Hospital.

EXPERIMENTAL INVESTIGATION OF THE ACTION OF MEDICINES: A Hand-Book of Practical Pharmacology, with Engravings. Preparing.

BRANSTON (THOMAS F.).

HAND-BOOK OF PRACTICAL RECEIPTS. For the Chemist, *Druggist,* &c.; with a Glossary of Medical and Chemical Terms. $1.50

BEETON (MRS.).

BOOK OF HOUSEHOLD MANAGEMENT. Colored and other

COHEN (I. SOLIS), M. D.

Lecturer on Laryngoscopy and Diseases of the Throat and Chest in Jefferson Medical College.

ON INHALATION. ITS THERAPEUTICS AND PRACTICE. Including a Description of the Apparatus employed, &c. With Cases and Illustrations. Price $2.50

SAME AUTHOR.

CROUP. In its Relations to Tracheotomy. Price . . $1.00

CARSON (JOSEPH), M. D.,

Professor of Materia Medica and Pharmacy in the University.

A HISTORY OF THE MEDICAL DEPARTMENT OF THE UNIVERSITY OF PENNSYLVANIA, from its Foundation in 1765: with Sketches of Deceased Professors, &c. $2.00

The history of the University of Pennsylvania has a national as well as a local interest, from the early date of its origination, and the connection with it of men of illustrious public reputation, such as Drs. Franklin, Rush, Physick, Gibson, Dewees, Chapman, Wood, &c., &c. For the labor and love which he has spent in preparing this most interesting and valuable work, Prof. Carson has earned the gratitude of the alumni of the University, and of all others interested in medical education in this country. — *American Journal of Medical Science.*

CARPENTER (W. B.), M. D., F. R. S.

THE MICROSCOPE AND ITS REVELATIONS. The Fifth London Edition, Revised and Enlarged, with more than 500 Illustrations. $5.50

SAME AUTHOR.

PRINCIPLES OF HUMAN PHYSIOLOGY. The Seventh Revised and Enlarged Edition. With nearly 300 Illustrations on Steel and Wood. Edited by Mr. HENRY POWER. Octavo. . . $11.25

CHAVASSE (P. HENRY), F. R. C. S.,

Author of Advice to a Wife, Advice to a Mother, &c.

APHORISMS ON THE MENTAL CULTURE AND TRAINING OF A CHILD, and on various other subjects relating to Health and Happiness. Addressed to Parents. Price . . . $1.50

Dr. Chavasse's works have been very favorably received and had a large circulation, the value of his advice to WIVES and MOTHERS having thus been very generally recognized. This book is a sequel or companion to them, and it will be found both valuable and important to all who have the care of families, and who want to bring up their children to become useful men and women. It is full of fresh thoughts and graceful illustrations.

CLARKE (W. FAIRLIE), M. D.,

Assistant Surgeon to Charing Cross Hospital.

CLARKE'S TREATISE ON DISEASES OF THE TONGUE. With Lithographic and Wood-cut Illustrations. Octavo. Price $5.00

It contains The Anatomy and Physiology of the Tongue, Importance of its Minute Examination, Its Congenital Defects, Atrophy, Hypertrophy, Parasitic Diseases, Inflammation, Syphilis and its effects, Various Tumors to which it is subject, Accidents, Injuries, &c., &c.

COOPER (S.).

A DICTIONARY OF PRACTICAL SURGERY AND [illegible] CLOPÆDIA OF SURGICAL SCIENCE. New Edition down to the present time. By SAMUEL A. LANE, F. R. C. S. other eminent Surgeons. In two vols., of over 1000 P

DIXON (JAMES), F.R.C.S.,

Surgeon to the Royal London Ophthalmic Hospital, &c.

A GUIDE TO THE PRACTICAL STUDY OF DISEASES OF THE EYE, with an Outline of their Medical and Operative Treatment, with Test Types and Illustrations. Third Edition, thoroughly Revised, and a great portion Rewritten. Price $2.50

Mr. Dixon's book is essentially a practical one, written by an observant author, who brings to his special subject a sound knowledge of general Medicine and Surgery.—*Dublin Quarterly.*

DILLNBERGER (DR. EMIL).

A HANDY-BOOK OF THE TREATMENT OF WOMEN AND CHILDREN'S DISEASES, according to the Vienna Medical School. Part I. The Diseases of Women. Part II. The Diseases of Children. Translated from the Second German Edition, by P. NICOL, M.D. Price $1.75

Many practitioners will be glad to possess this little manual, which gives a large mass of practical hints on the treatment of diseases which probably make up the larger half of every-day practice. The translation is well made, and explanations of reference to German medicinal preparations are given with proper fulness. — *The Practitioner.*

DARLINGTON (WILLIAM), M.D.

FLORA CESTRICA; OR, HERBORIZING COMPANION. Containing all the Plants of the Middle States, their Linnæan Arrangement, a Glossary of Botanical Terms, a complete Index, &c. Third Edition. 12mo. $2.25

DUCHENNE (DR. G. B.).

LOCALIZED ELECTRIZATION AND ITS APPLICATION TO PATHOLOGY AND THERAPEUTICS. Translated by HERBERT TIBBITS, M.D. With Ninety-two Illustrations. Price . $3.00

Duchenne's great work is not only a well-nigh exhaustive treatise on the medical uses of Electricity, but it is also an elaborate exposition of the different diseases in which Electricity has proved to be of value as a therapeutic and diagnostic agent.

PART II., illustrated by chromo-lithographs and numerous wood-cuts, is preparing.

DURKEE (SILAS), M.D.,

Fellow of the Massachusetts Medical Society, &c.

GONORRHŒA AND SYPHILIS. The Fifth Edition, Revised and Enlarged, with Portraits and Eight Colored Illustrations. Octavo. Price $5.00

Dr. Durkee's work impresses the reader in favor of the author by its general tone, the thorough honesty everywhere evinced, the skill with which the book is arranged, the manner in which the facts are cited, the clever way in which the author's experience is brought in, the lucidity of the reasoning, and the care with which the therapeutics of venereal complaints are treated.—*Lancet.*

DRUITT (ROBERT), F.R.C.S.

THE SURGEON'S VADE-MECUM. A Manual of Modern Surgery. The Tenth Revised and Enlarged Edition, with 350 Illustrations. $5.00

DALBY (W. B.), F. R. C. S.,

Aural Surgeon to St. George's Hospital.

LECTURES ON THE DISEASES AND INJURIES OF THE EAR. Delivered at St. George's Hospital. With Illustrations. Price $1.50

This admirable little volume by Mr. Dalby, the accomplished aural surgeon to St. George's Hospital, consists of eleven lectures delivered by him at that institution. With a modest aim, this work, the latest issued by the English press on Aural Surgery, is happy in conception and pleasantly written; further, it shows that its author is thoroughly *au fait* in his specialty. The subject of which the volume treats is handled in a terse style, and this, if we mistake not, will make it acceptable to the student and practitioner who have a just horror of unnecessary details. In conclusion, we hope that we have succeeded in interesting our readers in the volume. We cordially recommend it as a trustworthy guide in the treatment of the affections of the ear. The book is moderate in price, beautifully illustrated by wood-cuts, and got up in the best style. — *Glasgow Medical Journal.*

DUNGLISON (ROBLEY), M. D.,

Late Professor of Institutes of Medicine, &c., in the Jefferson Medical College.

A HISTORY OF MEDICINE, from the Earliest Ages to the Commencement of the Nineteenth Century. Edited by his son, RICHARD J. DUNGLISON, M.D. $2.50

ELLIS (EDWARD), M. D.

Physician to the Victoria Hospital for Sick Children, &c.

A PRACTICAL MANUAL OF THE DISEASES OF CHILDREN, with a Formulary. Second Edition, Revised and Improved. One volume. $2.75

The AUTHOR, in issuing this new edition of his book, says: "I have very carefully revised each chapter, adding several new sections, and making considerable additions where the subjects seemed to require fuller treatment, without, however, sacrificing conciseness or unduly increasing the bulk of the volume."

ELAM (CHARLES), M. D., F. R. C. P.

ON CEREBRIA AND OTHER DISEASES OF THE BRAIN. Octavo. $2.50

FOTHERGILL (J. MILNER), M. D.

THE HEART AND ITS DISEASES, AND THEIR TREATMENT. With Illustrations. Octavo. Price . . . $5.00

This work gives to the reader a concise view of Cardiac Diseases, uniting the most recent information as to the cause of heart-disease, with German Pathology and the latest advances in Therapeutics. It is designed to fill the gap between our standard works and the present position of our knowledge in diseases of the heart.

BY SAME AUTHOR.

DIGITALIS. Its Mode of Action and its Use, illustrating the Effect of Remedial Agents over Diseased Conditions of the Heart. Price $1.25

FAGGE (C. HILTON), M. D., F. R. C. P.,

Senior Assistant Physician and Demonstrator of Morbid Anatomy at Guy's Hospital.

THE PRINCIP[illegible]TICE OF MEDICINE.

In prepa

FOX (JOSEPH), D.D.S.,

Lecturer on the Structure and Diseases of the Teeth at Guy's Hospital.

THE NATURAL HISTORY, DISEASES AND STRUCTURE OF THE HUMAN TEETH, with 250 Illustrations. Price . $4.00

FOSTER (BALTHAZAR), M.D.,

Professor of Medicine in Queen's College.

LECTURES AND ESSAYS ON CLINICAL MEDICINE. Revised and Enlarged by the Author. With Engravings. Octavo. Price $3.50

FULLER (HENRY WILLIAM), M.D.,

Senior Physician to St. George's Hospital.

RHEUMATISM, RHEUMATIC GOUT, AND SCIATICA, their Symptoms, Pathology and Treatment. The Fourth Revised and Enlarged Edition. Preparing.

FENWICK (SAMUEL), M.D., F.R.C.P.

THE MORBID STATES OF THE STOMACH AND DUODENUM, AND THEIR RELATIONS TO THE DISEASES OF OTHER ORGANS. With Ten Plates. $5.00

FLINT (AUSTIN), M.D.,

Professor of the Principles and Practice of Medicine, &c., Bellevue Hospital College, New York.

CLINICAL REPORTS ON CONTINUED FEVER. Based on an Analysis of One Hundred and Sixty-four Cases, with Remarks on the Management of Continued Fever; the Identity of Typhus and Typhoid Fever; Diagnosis, &c., &c. Octavo. Price . . $2.00

GANT (FREDERICK J.), F.R.C.S.,

Surgeon to the Royal Free Hospital, &c.

THE IRRITABLE BLADDER. Its Causes and Curative Treatment; including a Practical View of Urinary Pathology, Deposits, and Calculi. Third Edition, Revised and Enlarged. With New Illustrations. Price $2.50

The fact that a third edition of this book has been required seems to be sufficient proof of its value. The author has carefully revised and added such additional matter as to make it more complete and practically useful.

GODFREY (BENJAMIN), M.D., F.R.A.S.

THE DISEASES OF HAIR: a Popular Treatise upon the Affections of the Hair System. $1.50

GROSS (SAMUEL D.), M.D.,

Professor of Surgery in the Jefferson Medical College, Philadelphia, &c.

AMERICAN MEDICAL BIOGRAPHY OF THE NINETEENTH *CENTURY*. With a Portrait of BENJAMIN RUSH, M.D. Octavo. $3.50

GREENHOW (E. HEADLAM), M. D.,

Fellow of the Royal College of Physicians, &c.

ON CHRONIC BRONCHITIS, Especially as Connected with Gout, Emphysema, and Diseases of the Heart. Price . . . $2.00

Of all works yet written on Chronic Bronchitis, this is undoubtedly the best. The style is clear and to the point, and the principles of pathology and treatment eminently correct and practical. It is a positive addition to our medical literature.—*Journal Psychological Medicine.*

HARLEY (GEORGE), M. D., F. R. C. P.,

Physician to University College Hospital.

THE URINE AND ITS DERANGEMENTS: With the Application of Physiological Chemistry to the Diagnosis and Treatment of Constitutional as well as Local Diseases; being a Course of Lectures delivered at University College. With Engravings. Price $2.75

CONTENTS.

1. What is Urine?
2. Changes in the Composition of the Urine, induced by Food, Drink, Medicine, and Disease.
3. Urea, Ammonæmia, Uræmia.
4. Uric Acid.
5. Hippuric Acid, Chloride of Sodium.
6. Urohæmatin, Abnormal Pigments in Urine.
7. Phosphoric Acid, Phosphatic Gravel and Calculi.
8. Oxalic Acid, Oxaluria, Mulberry Calculi.
9. Inosite in Urine, Creatin and Creatinine, Cholesterin, Cystin, Xanthin, Leucin, Tyrosin.
10. Diabetes Mellitus.
11. Albuminuria.

On the whole, we have here a valuable addition to the library of the practising physician; not only for the information which it contains, but also for the suggestive way in which many of the subjects are treated, as well as for the fact that it contains the ideas of one who thoroughly believes in the future capabilities of Therapeutics based on Physiological facts, and in the important service to be rendered by Chemistry to Physiological investigation.

American Journal of the Medical Science.

HABERSHON (S. O.), M. D.,

Physician to Guy's Hospital, &c.

ON THE DISEASES OF THE LIVER. Their Pathology and Treatment. Being the Lettsonian Lectures, delivered at the Medical Society of London, 1872. Price $1.50

These Lectures contain within a brief compass a large amount of information and many practical suggestions that cannot fail to be of great value to every practitioner.

Dublin Medical Journal.

HEWITT (GRAILY), M. D.,

Physician to the British Lying-in Hospital, and Lecturer on Diseases of Women and Children, &c.

THE DIAGNOSIS, PATHOLOGY, AND TREATMENT OF DISEASES OF WOMEN, including the Diagnosis of Pregnancy. Founded on a Course of Lectures delivered at St. Mary's Hospital Medical School. The Third Edition, Revised and Enlarged, with new Illustrations. Octavo. Price in Cloth . . . $5.00

" Leather . . . 6.00

This new edition of Dr Hewitt's book has been so much modified, that it may be considered substantially a new book; very much of the matter has been entirely rewritten, and the whole work has been rearranged in such a manner as to present a most decided improvement over previous editions. Dr. Hewitt is the leading clinical teacher on Diseases of Women in London, and the characteristic attention paid to Diagnosis by him has given his work great popularity there. It may unquestionably be considered the most valuable guide to correct Diagnosis to be found in the English language.

HILLIER (THOMAS), M.D.,

Physician to the Hospital for Sick Children, &c.

A CLINICAL TREATISE ON THE DISEASES OF CHILDREN.
Octavo. Price $3.00

We have said enough to indicate and illustrate the excellence of Dr. Hillier's volume. It is eminently the kind of book needed by all medical men who wish to cultivate clinical accuracy and sound practice. — *London Lancet.*

HOLDEN (LUTHER), F.R.C.S.

A MANUAL OF THE DISSECTION OF THE HUMAN BODY.
With Notes and Additions. Illustrated. $5.00

SAME AUTHOR.

HUMAN OSTEOLOGY: with numerous Plates, showing the Attachment of the Muscles, &c., &c. Fourth Edition. Octavo. $6.50

HARRIS (CHAPIN A.), M. D., D. D. S.

Late President of and Professor of the Principles and Practice of Dental Surgery in the Baltimore College, &c.

THE PRINCIPLES AND PRACTICE OF DENTISTRY. Tenth Revised Edition. In great part rewritten, rearranged, and with many new and important Illustrations. Including — 1. Dental Anatomy and Physiology. 2. Dental Pathology and Therapeutics. 3. Dental Surgery. 4. Dental Mechanics. Edited by P. H. AUSTEN, M.D., Professor of Dental Science and Mechanism in the Baltimore College of Dental Surgery. With nearly 400 Illustrations, including many new ones made especially for this edition. Royal octavo. Price, in cloth, $6.50; in leather $7.50

This new edition of Dr. Harris's work has been thoroughly revised in all its parts — more so than any previous edition. So great have been the advances in many branches of dentistry, that it was found necessary to rewrite the articles or subjects, and this has been done in the most efficient manner by Professor Austen, for many years an associate and friend of Dr. Harris, assisted by Professor Gorgas and Thomas S. Latimer, M. D. The publishers feel assured that it will now be found the most complete text-book for the student and guide for the practitioner in the English language.

SAME AUTHOR.

A DICTIONARY OF MEDICAL TERMINOLOGY, DENTAL SURGERY, AND THE COLLATERAL SCIENCES. Third Edition, Carefully Revised and Enlarged, by FERDINAND J. S. GORGAS, M. D., D.D.S., Professor of Dental Surgery in the Baltimore College, &c., &c. Royal octavo. Price, in cloth, $6.50; in leather . . $7.50

The many advances in Dental Science rendered it necessary that this edition should be thoroughly revised, which has been done in the most satisfactory manner by Professor Gorgas, Dr. Harris's successor in the Baltimore Dental College, he having added nearly three thousand new words, besides making many additions and corrections. The doses of the more prominent medicinal agents have also been added, and in every way the book has been greatly improved, and its value enhanced as a work of reference.

HANDY (WASHINGTON R.), M.D.

Late Professor of Anatomy, &c., in the Baltimore College.

A TEXT-BOOK OF ANATOMY, AND GUIDE TO DISSECTIONS. For the Use of Students of Medicine and Dental Surgery. With 312 Illustrations. Octavo. Price $4.00

Dr. Handy's work was prepared with special reference to the wants of the Student and *Practitioner of* Dental Surgery. Directing particular attention to the Mouth, it shows step *by step the* important Anatomical and Physiological relations which it has with each and *all the organs* and functions of the general system.

HARDWICH AND DAWSON.

HARDWICH'S MANUAL OF PHOTOGRAPHIC CHEMISTRY.

With Engravings. Eighth Edition. Edited and Rearranged by G. DAWSON, Lecturer on Photography, &c., &c. 12mo. . . . $2.00

The object of the Editor has been to give practical instruction in this fascinating art, and to lead the novice from first principles to the higher branches, impressing him with the value of care and exactness in every operation.

HEADLAND (F. W.), M. D.,

Fellow of the Royal College of Physicians, &c., &c.

ON THE ACTION OF MEDICINES IN THE SYSTEM.

Sixth American from the Fourth London Edition. Revised and Enlarged. Octavo. Price $3.00

Dr. Headland's work gives the only scientific and satisfactory view of the action of medicine; and this not in the way of idle speculation, but by demonstration and experiments, and inferences almost as indisputable as demonstrations. It is truly a great scientific work in a small compass, and deserves to be the hand-book of every lover of the Profession. It has received the approbation of the *Medical Press*, both in this country and in Europe, and is pronounced by them to be the most *original* and practically useful work that has been issued for many years.

HILLES (M. W.),

Formerly Lecturer on Anatomy, &c., at Westminster Hospital.

THE POCKET ANATOMIST.

Being a Complete Description of the Anatomy of the Human Body; for the Use of Students. Price, in cloth, $1.00; in Pocket-book form $1.25

HEATH (CHRISTOPHER), F.R.C.S.,

Surgeon to University College Hospital, &c.

INJURIES AND DISEASES OF THE JAWS.

The Jacksonian Prize Essay of the Royal College of Surgeons of England, 1867. Second Edition, Revised, with over 150 Illustrations. Octavo. Price, $5.00

SAME AUTHOR.

A MANUAL OF MINOR SURGERY AND BANDAGING,

for the Use of House Surgeons, Dressers, and Junior Practitioners. With a Formulæ and Numerous Illustrations. 16mo. Price . $2.25

HOLMES (T. M. A.),

Surgeon and Lecturer on Surgery to St. George's Hospital, &c.

THE SURGICAL TREATMENT OF THE DISEASES OF INFANCY AND CHILDHOOD.

Second Edition, Revised and Enlarged, containing Seven large Colored Plates and over One Hundred other Illustrations. Price $5.00

HUFELAND (C. W.), M. D.

THE ART OF PROLONGING LIFE.

Edited by ERASMUS WILSON, M. D., F. R. S., &c. 12mo. Cloth. $1.25

The highly practical character of Dr. Hufeland's book, the sound advice which it contains, and its elevated moral tone, recommend it for extensive circulation both among *professional* and *non-professional* readers.

HEWSON (ADDINELL,) M. D.

Attending Surgeon Pennsylvania Hospital, &c.

EARTH AS A TOPICAL APPLICATION IN SURGERY. Being a full Exposition of its use in all the Cases requiring Topical Applications admitted in the Surgical Wards of the Pennsylvania Hospital during a period of Six Months. With Four full-page Illustrations.

CONTENTS.

Preface; Introduction; Histories of Cases; Comments as to the Effects of the Contact of the Earth; Its Effects on Pain; Its Power as a Deodorizer; Its Influence over Inflammation; Its Influence over Putrefaction; Its Influence over the Healing Processes; Modus Operandi of the Earth; As a Deodorizer and other Putrefaction; In its Effects on Living Parts.

Price, ... $2.50

It presents the results of researches by the author into the action of Earth as a surgical dressing, and embraces the histories of over ninety cases which occurred in the wards of the Pennsylvania Hospital some three years since, but whose publication has been delayed, for the double purpose of weighing them by subsequent experience, and of interpreting their meaning by a careful study of the various subjects which they involve.

HODGE (HUGH L.), M. D.

Emeritus Professor in the University of Pennsylvania.

HODGE ON FŒTICIDE, OR CRIMINAL ABORTION.

Fourth Edition. Price, in paper covers, ... $0.30
" flexible cloth, ... 0.50

This little book is intended to place in the hands of professional men and others the means of answering satisfactorily and intelligently any inquiries that may be made of them in connection with this important subject.

HOLDEN (EDGAR), A. M., M. D.,

Of Newark, New Jersey.

CONTAINING THREE HUNDRED ILLUSTRATIONS.

THE SPHYGMOGRAPH. Its Physiological and Pathological Indications. The Essay to which was awarded the Stevens Triennial Prize in the College of Physicians and Surgeons in New York, April, 1873. Illustrated by Three Hundred Engravings on Wood. One volume octavo. Price. $3.00

HOOD (P.), M.D.

A TREATISE ON GOUT, RHEUMATISM, AND THE ALLIED AFFECTIONS. Crown octavo. $4.25

HANCOCK (HENRY), F.R.C.S.

ON THE OPERATIVE SURGERY OF THE FOOT AND ANKLE. Numerous Illustrations. Octavo. . . . $6.00

JONES (T. WHARTON), F.R.S.

DEFECTS OF SIGHT AND HEARING. Their Nature, Causes, Prevention, &c. Second Edition. Price $1.25

JONES, SIEVEKING, AND PAYNE.

A MANUAL OF PATHOLOGICAL ANATOMY. By C. HANDFIELD JONES, M. D., F. R. S., Physician to St. Mary's Hospital; and EDWARD H. SIEVEKING, M.D., F.R.C.P., Physician to St. Mary's Hospital. A New and Enlarged Edition. Edited by J. F. PAYNE, M.B., F.R.C.P., Assistant Physician and Lecturer on Morbid Anatomy at St. Thomas's Hospital. With Numerous Illustrations. $6.00

LAWSON (GEORGE), F.R.C.S.,

Surgeon to the Royal London Ophthalmic Hospital.

DISEASES AND INJURIES OF THE EYE, THEIR MEDICAL AND SURGICAL TREATMENT. Containing a Formulary, Test Types, and Numerous Illustrations. Price $2.50

This Manual is admirably clear and eminently practical. The reader feels that he is in the hands of a teacher who has a right to speak with authority, and who, if he may be said to be positive, is so from the fulness of knowledge and experience, and who, while well acquainted with the writings and labors of other authorities on the matters he treats of, has himself practically worked out what he teaches. — *London Medical Times and Gazette.*

LEBER & ROTTENSTEIN (DRS.).

DENTAL CARIES AND ITS CAUSES. An Investigation into the Influence of Fungi in the destruction of the Teeth, translated by THOMAS H. CHANDLER, D.M.D, Professor of Mechanical Dentistry in the Dental School of Harvard University. With Illustrations. Octavo. Price $1.50

This work is now considered the best and most elaborate work on Dental Caries. It is everywhere quoted and relied upon as authority by the profession, who have seen it in the original, and by authors writing on the subject.

LEGG (J. WICKHAM), M. D.

Member of the Royal College of Physicians, &c.

A GUIDE TO THE EXAMINATION OF THE URINE. For the Practitioner and Student. Third Edition. 16mo. Cloth. Price, $0.75

Dr. Legg's little manual has met with remarkable success; the speedy exhaustion of two editions has enabled the author to make certain emendations which add greatly to its value. It can confidently be commended to the student as a safe and reliable guide.

LEARED (ARTHUR), M.D., F.R.C.P.

IMPERFECT DIGESTION: ITS CAUSES AND TREATMENT. The Fifth Edition, Revised and Enlarged. $1.75

LESCHER (F. HARWOOD).

THE ELEMENTS OF PHARMACY. For Students. The Fourth Edition, Revised and Enlarged. Octavo. $3.00

LIEBREICH (DR.).

ATLAS OF OPHTHALMOSCOPY: Representing the Normal and Pathological Conditions of the Fundus Oculi as seen with the Ophthalmoscope. Composed of Twelve Chromo-lithographic Plates (containing Fifty-nine Figures), accompanied by an Explanatory Text, translated into English. Second Edition, Enlarged and Revised. 4to. $15.00

LIVEING (EDWARD), M.D.

ON MEGRIM, SICK-HEADACHE, AND SOME ALLIED DISORDERS. With Colored Plate. Octavo. . . . $6.00

LEWIN (DR. GEORGE).

Professor at the Fr.-Wilh. University, and Surgeon-in-Chief of the Syphilitic Wards and Skin Diseases of the Charity Hospital, Berlin.

THE TREATMENT OF SYPHILIS by Subcutaneous Sublimate Injections. With a Lithographic Plate illustrating the Mode and Proper Place of administering the Injections, and of the Syringe used for the purpose. Translated by CARL PRŒGLER, M.D., late Surgeon in the Prussian Service, and E. H. GALE, M.D., late Surgeon in the United States Army. Price $2.25

The great number of cases treated, some fourteen hundred, within a period of four years, in the wards of the Charity Hospital, Berlin, only twenty of which were returned on account of Syphilitic relapses, certainly entitles the method of treatment advocated by this distinguished syphilographer to the attention of all physicians under whose notice syphilitic cases come.

LIZARS (JOHN), M. D.

Late Professor of Surgery in the Royal College of Surgeons, Edinburgh.

THE USE AND ABUSE OF TOBACCO. From the Eighth Edinburgh Edition. 12mo. Price, in flexible cloth, . $0.60

This little work contains a History of the introduction of Tobacco, its general characteristics; practical observations upon its effects on the system; the opinion of celebrated professional men in regard to it, together with cases illustrating its deleterious influence, &c., &c.

MACNAMARA (C.).

Surgeon to the Ophthalmic Hospital, and Professor of Ophthalmic Medicine in the Medical College, Calcutta.

MANUAL OF THE DISEASES OF THE EYE. The Second Edition, carefully Revised; with Additions, and numerous Colored Plates, Diagrams of the Eye, many Illustrations on Wood, Snellen's Test Types, &c., &c. Price $5.00

"This work when first published took its place in medical literature as the most complete, condensed, and well-arranged manual on ophthalmic surgery in the English language. Arranged especially for medical students, it became, however, the work of reference for the busy practitioner, who could obtain nearly all that was best worth knowing on this subject, tersely stated, and easily found by the aid of the excellent marginal notes on the contents of the paragraphs." — *Philadelphia Medical Times.*

MACKENZIE (MORELL), M. D.

Physician to the Hospital for Diseases of the Throat, London, &c.

GROWTHS IN THE LARYNX. Their History, Causes, Symptoms, Diagnosis, Pathology, Prognosis, and Treatment. With Reports and Analysis of One Hundred Consecutive Cases treated by the Author; and a Tabular Statement of every published case treated since the invention of the Laryngoscope. With numerous Colored and other Illustrations. Octavo. Price $3.00

Dr. Mackenzie's position has given him great advantages and a large experience in the treatment of Diseases of the Throat, and for many years he has been regarded as a leading authority in this department of Surgery. The Illustrations have been prepared with great care and expense.

OTHER WORKS BY SAME AUTHOR.

THE LARYNGOSCOPE IN DISEASES OF THE THROAT. With an Appendix on Rhinoscopy, and an Essay on Hoarseness and Loss of Voice. With Additions by J. SOLIS COHEN, and Numerous Illustrations on Wood and Stone. Price $3.00

PHARMACOPŒIA OF THE HOSPITAL for Diseases of the Throat; with One Hundred and Fifty Formulæ for Gargles, &c., &c. *Price* $1.25

MEIGS AND PEPPER.

A PRACTICAL TREATISE ON THE DISEASES OF CHILDREN. By J. FORSYTH MEIGS, M.D., Fellow of the College of Physicians of Philadelphia, &c., &c., and WILLIAM PEPPER, M.D., Physician to the Philadelphia Hospital, &c. Fifth Edition, thoroughly Revised and greatly Enlarged, forming a Royal Octavo Volume of over 1000 pages. Price, bound in cloth, $6.00; leather . . . $7.00

It is the most complete work on the subject in our language. It contains at once the results of personal, and the experience of others. Its quotations from the most recent authorities, at home and abroad, are ample, and we think the authors deserve congratulations for having produced a book unequalled for the use of the student and indispensable as a work of reference for the practitioner. — *American Medical Journal.*

MURPHY (JOHN G.), M.D.

A REVIEW OF CHEMISTRY FOR STUDENTS. Adapted to the Courses as Taught in the Principal Medical Schools in the United States. $1.25

MENDENHALL (GEORGE), M.D.,

Professor of Obstetrics in the Medical College of Ohio, &c.

MEDICAL STUDENT'S VADE MECUM. A Compendium of Anatomy, Physiology, Chemistry, the Practice of Medicine, Surgery, Obstetrics, Diseases of the Skin, Materia Medica, Pharmacy, Poisons, &c., &c. Eleventh Edition, Revised and Enlarged, with 224 Illustrations. $2.50

MAXSON (EDWIN R.), M.D.,

Formerly Lecturer on the Practice of Medicine in the Geneva Medical College, &c.

THE PRACTICE OF MEDICINE. $4.00

MARSHALL (JOHN), F.R.S.,

Professor of Surgery, University College, London.

PHYSIOLOGICAL DIAGRAMS. Life-size, and Beautifully Colored. An Entirely New Edition, Revised and Improved, illustrating the whole Human Body, each Map printed on a single sheet of paper, seven feet long and three feet nine inches broad.

No. 1. The Skeleton and Ligaments.
No. 2. The Muscles, Joints, and Animal Mechanics.
No. 3. The Viscera in Position. — The Structure of the Lungs.
No. 4. The Organs of Circulation.
No. 5. The Lymphatics or Absorbents.
No. 6. The Digestive Organs.
No. 7. The Brain and Nerves.
No. 8. The Organs of the Senses and Organs of the Voice. Plate 1.
No. 9. The Organs of the Senses. Plate 2.
No. 10. The Microscopic Structure of the Textures. Plate 1.
No. 11. The Microscopic Structure of the Textures. Plate 2.

Price of the Set, Eleven Maps, in Sheets, ... $50.00
" " " " handsomely Mounted on Canvas, with Rollers, and varnished, ... $80.00
An Explanatory Key to the Diagram. Price 50

SAME AUTHOR.

DESCRIPTION OF THE HUMAN BODY. Its Structure and Functions. Illustrated by Physiological Diagrams, Designed for the Use of Teachers in Schools, Students of Medicine, &c. New Edition. *A Quarto Volume of Text and a Folio Volume containing 193 Colored Illustrations.* Price $1

MAUNDER (C. F.), F. R. C. S.

Surgeon to the London Hospital; formerly Demonstrator of Anatomy at Guy's Hospital.

OPERATIVE SURGERY. Second Edition, with One Hundred and Sixty-four Engravings on Wood.

CONTENTS.

Chap. 1. Compress, Splint, Bandage Strapping.
" 2. Ligature.
" 3. Operations on the Vascular System.
" 4. Operations on Arteries.
" 5. Ligature of special ditto.
" 6. Operations on the Bones.
Chap. 7. Operations on the Surface of the Body.
" 8. Amputation.
" 9. Lower Extremity.
" 10. Upper ditto.
" 11. Special Operations.

Price $2.50

MARTIN (JOHN H.).

Author of Microscopic Objects, &c.

A MANUAL OF MICROSCOPIC MOUNTING. With Notes on the Collection and Examination of Objects, and upwards of One Hundred Illustrations on Stone and Wood, drawn by the Author. Price $3.00

"This book is more than its title indicates. It gives a description of the apparatus necessary for microscopical research, as well as the methods of preparation and preserving the various objects. It is a complete and well-illustrated work on its subject, which is daily becoming more valuable to the scientist and more cultivated as an elegant and interesting study." — *Scientific American.*

MEADOWS (ALFRED), M. D.

Physician to the Hospital for Women, and to the General Lying-in Hospital, &c.

MANUAL OF MIDWIFERY. A New Text-Book. Including the Signs and Symptoms of Pregnancy, Obstetric Operations, Diseases of the Puerperal State, &c., &c. First American from the Second London Edition. With numerous Illustrations. Price $3.00

This book is especially valuable to the Student as containing in a condensed form a large amount of valuable information on the subject which it treats. It is also clear and methodical in its arrangement, and therefore useful as a work of reference for the practitioner. The Illustrations are numerous and well executed.

MILLER (JAMES), F. R. C. S.

Professor of Surgery University of Edinburgh.

ALCOHOL, ITS PLACE AND POWER. From the Nineteenth Glasgow Edition. 12mo. Cloth flexible. Price $0.75

This work was prepared by Professor Miller at the special request of the Scottish Temperance League, who were anxious to have a work of high authority, presenting the medical view of the subject that could be freely disseminated among all classes.

MILLER AND LIZARS.

ALCOHOL: Its Place and Power. By JAMES MILLER, F.R.S.E., late Professor of Surgery in the University of Edinburgh, &c.—THE USE AND ABUSE OF TOBACCO. By JOHN LIZARS, late Professor to the Royal College of Surgeons, &c. The Two Essays in One Volume. *12mo.* $1.00

MARSDEN (ALEXANDER), M.D.

A NEW AND SUCCESSFUL MODE OF TREATING CERTAIN FORMS OF CANCER. Second Edition, Colored Plates. $3.50

NORRIS (GEORGE W.), M. D.

Late Surgeon to the Pennsylvania Hospital, &c.

CONTRIBUTIONS TO PRACTICAL SURGERY, including numerous Clinical Histories, Drawn from a Hospital Service of Thirty Years. In one volume, Octavo. Price $4.00

OTT (ADOLPH),

Practical and Analytical Chemist.

ON SOAPS AND CANDLES. Including the Most Recent Discoveries in the Manufacture of all kinds of Ordinary Hard, Soft, and Toilet Soaps, and Tallow and Composite Candles. With Illustrations. Price $2.50

OVERMAN (FREDERICK),

Mining Engineer, &c.

PRACTICAL MINERALOGY, ASSAYING AND MINING. With a Description of the Useful Minerals, and Instructions for Assaying, according to the Simplest Methods. $1.25

PHYSICIAN'S VISITING LIST, PUBLISHED ANNUALLY.

SIZES AND PRICES.

For 25 Patients weekly.	Tucks, pockets, and pencil,	.	.	.	$1.00
50	"	"	"	"	"	.	.	.	1.25
75	"	"	"	"	"	.	.	.	1.50
100	"	"	"	"	"	.	.	.	2.00
50	"	" 2 vols.	Jan. to June / July to Dec.	"	.	.	.	2.50
100	"	" 2 vols.	Jan. to June / July to Dec.	"	.	.	.	3.00

INTERLEAVED EDITION.

For 25 Patients weekly, interleaved, tucks, pockets, &c.,	.	.	1.50
50	"	"	"	"	"	.	.	1.75
50	"	" 2 vols.	Jan. to June / July to Dec.	"	"	.	.	3.00

This Visiting List has now been published *Twenty-four Years*, and has met with such uniform and hearty approval from the Profession, that the demand for it has steadily increased from year to year.

POWER, HOLMES, ANSTIE, AND BARNES.

REPORTS ON THE PROGRESS OF MEDICINE AND SURGERY, PHYSIOLOGY, OPHTHALMIC MEDICINE, MIDWIFERY, DISEASES OF WOMEN AND CHILDREN, MATERIA MEDICA, &c. Edited for the Sydenham Society of London. Octavo. Price $2.00

PARKES (EDWARD A.), M.D.,

Professor of Military Hygiene in the Army Medical School, &c.

A MANUAL OF PRACTICAL HYGIENE. The Fourth Revised and Enlarged Edition, for Medical Officers of the Army, Civil Medical Officers, Boards of Health, &c., &c. With many Illustrations. One volume Octavo. Price $6.00

This work, previously unrivalled as a text-book for medical officers of the army, is now equally unrivalled as a text-book for civil medical officers. The first book treats in successive chapters of water, air, ventilation, examination of air, food, quality, choice, and cooking of food, beverages, and condiments; soil, habitations, removal of excreta, warming of houses, exercise, clothing, climate, meteorology, individual hygienic management, disposal of the dead, the prevention of some common diseases, disinfection, and statistics. The second book is devoted to the service of the soldier, but is hardly less instructive to the civil officer of health. It is, in short, a comprehensive and trustworthy text-book of hygiene for the scientific or general reader. —*London Lancet.*

POWER (HENRY), M.B., F.R.C.S.,

Senior Ophthalmic Surgeon to St. Bartholomew's Hospital.

THE STUDENT'S GUIDE TO THE DISEASES OF THE EYE. With Engravings. Preparing.

PENNSYLVANIA HOSPITAL REPORTS.

EDITED BY A COMMITTEE OF THE HOSPITAL STAFF. J. M. DA COSTA, M.D., and WILLIAM HUNT, M.D. Vols. 1 and 2; each volume containing upwards of Twenty Original Articles, by former and present Members of the Staff, now eminent in the Profession, with Lithographic and other Illustrations. Price per volume . $4.00

The first Reports were so favorably received, on both sides of the Atlantic, that it is hardly necessary to speak for them the universal welcome of which they are deserving. The papers are all valuable contributions to the literature of medicine, reflecting great credit upon their authors. The work is one of which the Pennsylvania Hospital may well be proud. It will do much towards elevating the profession of this country. —*American Journal of Obstetrics.*

PAGET (JAMES), F.R.S.,

Surgeon to St. Bartholomew's Hospital, &c.

SURGICAL PATHOLOGY. Lectures delivered at the Royal College of Surgeons of England. Third London Edition, Edited and Revised by WILLIAM TURNER, M.D. With Numerous Illustrations. Price, in cloth, $7.50; in leather $8.50

A new and revised edition of Mr. Paget's Classical Lectures needs no introduction to our readers. Commendation would be as superfluous as criticism out of place. Every page bears evidence that this edition has been "carefully revised."—*American Medical Journal.*

PEREIRA (JONATHAN), M.D., F.R.S., &c.

PHYSICIAN'S PRESCRIPTION BOOK. Containing Lists of Terms, Phrases, Contractions, and Abbreviations used in Prescriptions, with Explanatory Notes, the Grammatical Constructions of Prescriptions, Rules for the Pronunciation of Pharmaceutical Terms, a Prosodiacal Vocabulary of the Names of Drugs, &c., and a Series of Abbreviated Prescriptions illustrating the use of the preceding terms, &c.; to which is added a Key, containing the Prescriptions in an unabbreviated Form, with a Literal Translation, intended for the use of Medical and Pharmaceutical Students. From the Fifteenth London Edition. Price, in cloth, $1.25; in leather, with Tucks and Pocket, . $1.50

PROCTOR (BARNARD S.).

PRACTICAL PHARMACY. A Course of Lectures comprising Descriptions of General Processes, Lessons in Dispensing, Pharmacopœial Testing, Qualitative and Quantitative, &c. With Illustrations. Octavo. Price $5.00

PARKER (LANGSTON), F.R.C.S.L.

THE MODERN TREATMENT OF SYPHILITIC DISEASES. Containing the Treatment of Constitutional and Confirmed Syphilis, with numerous Cases, Formulæ, &c., &c. Fifth Edition, Enlarged. $4.25

PRINCE (DAVID), M.D.

PLASTIC AND ORTHOPEDIC SURGERY. Containing 1. A Report on the Condition of, and Advances made in, Plastic and Orthopedic Surgery up to the Year 1871. 2. A New Classification and Brief Exposition of Plastic Surgery. With numerous Illustrations. 3. Orthopedics: A Systematic Work upon the Prevention and Cure of Deformities. With numerous Illustrations. Octavo. Price $4.50

This is a good book upon an important practical subject; carefully written, and abundantly illustrated. It goes over the whole ground of deformities -- from cleft-palate and club-foot to spinal curvatures and ununited fractures. It appears, moreover, to be an original book. — *Medical and Surgical Reporter.*

SAME AUTHOR.

GALVANO-THERAPEUTICS. A Revised reprint of A Report made to the Illinois State Medical Society. With Illustrations. Price, $1.25

PIESSE (G. W. SEPTIMUS),

Analytical Chemist.

WHOLE ART OF PERFUMERY. And the Methods of Obtaining the Odors of Plants; the Manufacture of Perfumes for the Handkerchief, Scented Powders, Odorous Vinegars, Dentifrices, Pomatums, Cosmetics, Perfumed Soaps, &c.; the Preparation of Artificial Fruit Essences, &c. Second American from the Third London Edition. With Illustrations. $3.00

PIGGOTT (A. SNOWDEN), M.D.,

Practical Chemist.

COPPER MINING AND COPPER ORE. Containing a full Description of some of the Principal Copper Mines of the United States, the Art of Mining, the Mode of Preparing the Ore for Market, &c., &c. $1.50

PHYSICIAN'S CASE RECORD & PRESCRIPTION BLANKS. Containing Blanks for Prescriptions and a Marginal Copy, also Blanks for noting Date, Name, Address, Diagnosis, Age, Physique, Pulse, Temperature, Respiration, Tongue, Urine, and Stools of Patients. Pocket Edition, price per copy, 40 cents; per dozen, $3.75; Office Edition, *4to, price* per copy, $1.50.

This book will be found an invaluable aid in the thorough study of Disease, and *finite relief to the* overtasked memory.

RINDFLEISCH (DR. EDWARD).

Professor of Pathological Anatomy, University of Bonn.

TEXT-BOOK OF PATHOLOGICAL HISTOLOGY. An Introduction to the Study of Pathological Anatomy. Translated from the German, by WM. C. KLOMAN, M.D., assisted by F. T. MILES, M.D., Professor of Anatomy, University of Maryland, &c., &c. Containing Two Hundred and Eight elaborately executed Microscopical Illustrations. Octavo. Price, bound in Cloth, ... $6.00
" " Leather, ... 7.00

This is now confessedly the leading book, and the only complete one on the subject in the English language. The *London Lancet* says of it: "Rindfleisch's work forms a mine which no pathological writer or student can afford to neglect, who desires to interpret aright pathological structural changes, and his book is consequently well known to readers of German medical literature. What makes it especially valuable is the fact that it was originated, as its author himself tells us, more at the microscope than at the writing-table. Altogether the book is the result of honest hard labor. It is admirably as well as profusely illustrated, furnished with a capital Index, and got up in a way that is worthy of what must continue to be the standard book of the kind."

ROBERTS (FREDERICK T.)., M. D., B. Sc.

Assistant Physician and Teacher of Clinical Medicine in the University College Hospital; Assistant Physician Brompton Consumption Hospital, &c.

A HAND-BOOK OF THE THEORY AND PRACTICE OF MEDICINE. One volume medium octavo, containing over 1000 pages. Price . . . . . $5.00.

This work has been prepared mainly for the use of Students, and its object is to present in as condensed a form as the present extent of Medical Literature will permit, and in one volume, such information with regard to the Principles and Practice of Medicine, as shall be sufficient not only to enable them to prepare for the various examinations which they may have to undergo, but also to guide them in acquiring that Clinical Knowledge which can alone properly fit them for assuming the active duties of their profession. The work is also adapted to the wants of very many members of the profession who are already busily engaged in general Practice, and consequently have but little leisure and few opportunities for the perusal of the larger works on Practice or of the various special monographs.

REYNOLDS (J. RUSSELL), M. D., F. R. S.,

Lecturer on the Principles and Practice of Medicine, University College, London.

LECTURES ON THE CLINICAL USES OF ELECTRICITY. Delivered at University College Hospital. Second Edition, Revised and Enlarged. Price $1.25

RYAN (MICHAEL), M. D.

Member of the Royal College of Physicians.

PHILOSOPHY OF MARRIAGE, in its Social, Moral, and Physical Relations; with an Account of the Diseases of the Genito-Urinary Organs, &c. Price $1.00

This is a philosophical discussion of the whole subject of Marriage, its influences and results in all their varied aspects, together with a medical history of the reproductive functions of the vegetable and animal kingdoms, and of the abuses and disorders resulting from *it in the latter.* It is intended both for the professional and general reader.

RADCLIFFE (CHARLES BLAND), M.D.,

Fellow of the Royal College of Physicians of London, &c.

LECTURES ON EPILEPSY, PAIN, PARALYSIS, and other Disorders of the Nervous System. With Illustrations. . . $2.00

The reputation which Dr. Radcliffe possesses as a very able authority on nervous affections will commend his work to every medical practitioner. We recommend it as a work that will throw much light upon the Physiology and Pathology of the Nervous System. — *Canada Medical Journal.*

ROBERTSON (A.), M.D., D.D.S.

A MANUAL ON EXTRACTING TEETH. Founded on the Anatomy of the Parts involved in the Operation, the kinds and proper construction of the instruments to be used, the accidents likely to occur from the operation, and the proper remedies to retrieve such accidents. A New Revised Edition. $1.50

The author is well known as a contributor to the literature of the profession, and as a clear, terse, and practical writer. The subject is one to which he has devoted considerable attention, and is treated with his usual care and ability. The work is valuable not only to the dental student and practitioner, but also to the medical student and surgeon. — *Dental Cosmos.*

REESE (JOHN J.), M.D.,

Professor of Medical Jurisprudence and Toxicology in the University of Pennsylvania.

AN ANALYSIS OF PHYSIOLOGY. Being a Condensed View of the most important Facts and Doctrines, designed especially for the Use of Students. Second Edition, Enlarged. . . . $1.50

SAME AUTHOR.

THE AMERICAN MEDICAL FORMULARY. Price . $1.50

A SYLLABUS OF MEDICAL CHEMISTRY. Price . $1.00

RICHARDSON (JOSEPH), D.D.S.

Late Professor of Mechanical Dentistry, &c., &c.

A PRACTICAL TREATISE ON MECHANICAL DENTISTRY. Second Edition, much Enlarged. With over 150 beautifully executed Illustrations. Octavo. Price, in leather $4.50

This work does infinite credit to its author. Its comprehensive style has in no way interfered with most elaborate details where this is necessary; and the numerous and beautifully executed wood-cuts with which it is illustrated make the volume as attractive as its instructions are easily understood. — *Edinburgh Med. Journal.*

ROBERTS (LLOYD D.), M.D.,

Vice-President of the Obstetrical Society of London, Physician to St. Mary's Hospital, Manchester.

THE STUDENT'S GUIDE TO THE PRACTICE OF MIDWIFERY. With Engravings. In Preparation.

ROSS (JAMES), M.D.

THE GRAFT THEORY OF DISEASE. Being an Application of Mr. Darwin's Hypothesis of Pangenesis to the Explanation of *Phenomena* of the Zymotic Diseases. Price . .

RIGBY AND MEADOWS.

DR. RIGBY'S OBSTETRIC MEMORANDA. Fourth Edition, Revised and Enlarged, by ALFRED MEADOWS, M.D., Author of "A Manual of Midwifery," &c. Price 50

RIHL AND O'CONNOR.

THE PHYSICIAN'S DIARY. Monthly, Semi-Annual, and Annual Journal and Cash-Book Combined. The Fourth Revised Edition. A large folio volume, with printed Heads, Index, &c., &c. Bound in full leather. Price $7.50

RUPPANER (ANTOINE), M.D.

THE PRINCIPLES AND PRACTICE OF LARYNGOSCOPY AND RHINOSCOPY IN DISEASES OF THE THROAT, &c. Fifty-nine Illustrations. Price $1.50

SANDERSON, KLEIN, FOSTER, AND BRUNTON.

A HAND-BOOK FOR THE PHYSIOLOGICAL LABORATORY. Being Practical Exercises for Students in Physiology and Histology, by E. KLEIN, M.D., Assistant Professor in the Pathological Laboratory of the Brown Institution, London; J. BURDON-SANDERSON, M.D., F.R.S., Professor of Practical Theology in University College, London; MICHAEL FOSTER, M.D., F.R.S., Fellow of and Prælector of Physiology in Trinity College, Cambridge; and T. LAUDER BRUNTON, M.D., D.Sc., Lecturer on Materia Medica in the Medical College of St. Bartholomew's Hospital. Edited by J. BURDON-SANDERSON. The Illustrations consist of One Hundred and Twenty-three octavo pages, including over Three Hundred and Fifty Figures, with appropriate letter-press explanations attached and references to the text, and bound in a separate volume. Price of the two volumes, text and plates, $8.00

We feel that we cannot recommend this work too highly. To those engaged in physiological work as students or teachers, it is almost indispensable; and to those who are not, a perusal of it will by no means be unprofitable. The execution of the plates leaves nothing to be desired. They are mostly original, and their arrangement in a separate volume has great and obvious advantages. — *Dublin Journal of Medical Sciences.*

SIEVEKING (E. H.), M.D., F.R.C.S.

THE MEDICAL ADVISER IN LIFE ASSURANCE. Price $2.25

This book supplies, in a concise and available form, such facts and figures as are required by the Physician or Examiner to assist him in arriving at a correct estimate of the many contingencies upon which life insurance rests.

SWAIN (WILLIAM PAUL), F.R.C.S.,

Surgeon to the Royal Albert Hospital, Devonport.

SURGICAL EMERGENCIES: A MANUAL CONTAINING CONCISE DESCRIPTIONS OF VARIOUS ACCIDENTS AND EMERGENCIES, WITH DIRECTIONS FOR THEIR IMMEDIATE TREATMENT. With numerous Wood Engravings. In one volume, 12mo. Cloth. Price $2.00

STILLE (ALFRED), M.D.,

Professor of the Theory and Practice of Medicine in the University of Pennsylvania, &c.

EPIDEMIC MENINGITIS; or, Cerebro-Spinal Meningitis. In one volume, Octavo. $2.00

This monograph is a timely publication, comprehensive in its scope, and presenting within a small compass a fair digest of our existing knowledge of the disease, particularly acceptable at the present time. It is just such a one as is needed, and may be taken as a model for similar works. — *American Journal Medical Sciences.*

SAME AUTHOR.

ELEMENTS OF GENERAL PATHOLOGY. A Practical Treatise on the Causes, Forms, Symptoms, and Results of Disease. Second Edition preparing.

SCHULTZE (DR. B. S.),

Professor of Midwifery at the University of Jena.

LECTURE DIAGRAMS FOR INSTRUCTION IN PREGNANCY AND MIDWIFERY. Twenty Plates of the largest Imperial size, printed in colors. Drawn and Edited with Explanatory Notes, and a 4to volume of letter-press. Prices, in sheets, $15.00. Handsomely mounted on rollers for hanging up. $30.00

SANSOM (ARTHUR ERNEST), M.B.,

Physician to King's College Hospital, &c.

CHLOROFORM. Its Action and Administration. Price $2.00

This work may be characterized as most excellent. Written not alone from a theoretical point of view, but showing very considerable experimental study, and an intimate clinical acquaintance with the administration of these remedies, — passing concisely over the whole ground, giving the latest information upon every point. It is just the work for the student and practitioner. — *American Medical Journal.*

SCANZONI (F. W. VON),

Professor in the University of Wurzburg.

A PRACTICAL TREATISE ON THE DISEASES OF THE SEXUAL ORGANS OF WOMEN. Translated from the French. By A. K. GARDNER, M.D. With Illustrations. Octavo. . $5.00

STOKES (WILLIAM),

Regius Professor of Physic in the University of Dublin.

THE DISEASES OF THE HEART AND THE AORTA. Octavo. $3.00

SYDENHAM SOCIETY'S PUBLICATIONS. New Series, 1859 to 1873 inclusive, 15 years, 56 vols. Subscriptions received, and back years furnished at $10.00 per year. Full prospectus, with the Reports of the Society and a list of the Books published, furnished free upon application.

SANKEY (W. H. O.), M.D., F.R.C.P.

LECTURES ON MENTAL DISEASES. Octavo.

SWERINGEN (HIRAM V.).

Member American Pharmaceutical Association, &c.

PHARMACEUTICAL LEXICON. A Dictionary of Pharmaceutical Science. Containing a concise explanation of the various subjects and terms of Pharmacy, with appropriate selections from the collateral sciences. Formulæ for officinal, empirical, and dietetic preparations; selections from the prescriptions of the most eminent physicians of Europe and America; an alphabetical list of diseases and their definitions; an account of the various modes in use for the preservation of dead bodies for interment or dissection; tables of signs and abbreviations, weights and measures, doses, antidotes to poisons, &c., &c. Designed as a guide for the Pharmaceutist, Druggist, Physician, &c. Royal Octavo. Price in cloth $5.00
" leather 6.00

"We have received from publishers so many English reprints ill adapted to the needs of this country, that it is with pleasure we welcome a thorough American book, written for the uses of the American pharmaceutist. Besides, the work is well written, creditably arranged, and neatly printed. It will be found very useful to the druggist as well as to the physician. Being in the form of a dictionary, its aim is to give *immediate* information in a concise manner, and not a complete treatise on each subject. So far as we have been able to see, the PHARMACEUTICAL LEXICON is remarkably correct." — *Druggist's Circular.*

SHEPPARD (EDGAR), M. D.

Professor of Psychological Medicine in King's College, London.

MADNESS, IN ITS MEDICAL, SOCIAL, AND LEGAL ASPECTS. A series of Lectures delivered at King's College, London. Octavo. Price $2.50

SAVAGE (HENRY), M. D., F. R. C. S.

Consulting Physician to the Samaritan Free Hospital, London.

THE SURGERY, SURGICAL PATHOLOGY, and Surgical Anatomy of the Female Pelvic Organs, in a Series of Colored Plates taken from Nature: with Commentaries, Notes, and Cases. Third Edition, greatly enlarged. A quarto volume. Price . .

SAME AUTHOR.

AN EXPOSITION OF THE NATURE OF THE SURGICAL DISEASES OF THE FEMALE PELVIC ORGANS. With a View to their Rational Treatment. Preparing.

SYDENHAM SOCIETY.

A COMPLETE SET OF THE PUBLICATIONS OF THE OLD SYDENHAM SOCIETY, in Thirty-nine Volumes Octavo, together with a Folio Volume of Plates. Price $60.00

SMITH (EUSTACE), M.D.

Physician to the East London Hospital for Diseases of Children, &c.

CLINICAL STUDIES OF DISEASES IN CHILDREN.

Preparing.

TANNER (THOMAS HAWKES), M.D., F.R.C.P., &c.

THE PRACTICE OF MEDICINE. Sixth American from the last London Edition. Revised, much Enlarged, and thoroughly brought up to the present time. With a complete Section on the Diseases Peculiar to Women, an extensive Appendix of Formulæ for Medicines, Baths, &c., &c. Royal Octavo, over 1100 pages. Price, in cloth, $6.00; leather $7.00

There is a common character about the writings of Dr. Tanner — a characteristic which constitutes one of their chief values: they are all essentially and thoroughly practical. Dr. Tanner never, for one moment, allows this utilitarian end to escape his mental view. He aims at teaching how to recognize and how to cure disease, and in this he is thoroughly successful. . . . It is, indeed, a wonderful mine of knowledge. — *Medical Times.*

SAME AUTHOR.

A PRACTICAL TREATISE ON THE DISEASES OF INFANCY AND CHILDHOOD. Third American from the last London Edition, Revised and Enlarged. By ALFRED MEADOWS, M.D., London, M.R.C.P., Physician to the Hospital for Women and to the General Lying-in Hospital, &c., &c. Price $3.50

This book of Dr. Tanner's has been much enlarged and the plan altered by Dr. Meadows. As it now stands, it is probably one of the most complete in our language. It no longer deals with children's diseases only, but includes the peculiar conditions of childhood, both normal and abnormal, as well as the therapeutics specially applicable to that class of patients. The articles on Skin Diseases have been revised by Dr. Tilbury Fox, and those on Diseases of the Eye by Dr. Brudenell Carter, both gentlemen distinguished in these specialties. — *Medical Times and Gazette.*

A MEMORANDA OF POISONS. A New and much Enlarged Edition. Price 75

AN INDEX OF DISEASES AND THEIR TREATMENT. The last London Edition. 12mo. Price $3.00

TYSON (JAMES), M.D.,

Lecturer on Microscopy in the University of Pennsylvania, &c.

THE CELL DOCTRINE. Its History and Present State, with a Copious Bibliography of the Subject, for the use of Students of Medicine and Dentistry. With Colored Plate, and numerous Illustrations on Wood. Price $2.00

BY SAME AUTHOR.

A PRACTICAL GUIDE TO THE EXAMINATION OF URINE. For the use of Physicians and Students. With a Colored Plate and numerous Illustrations Engraved on Wood. A 12mo Volume. Price, $1.50

TAFT (JONATHAN), D.D.S.,

Professor of Operative Dentistry in the Ohio College, &c.

A PRACTICAL TREATISE ON OPERATIVE DENTISTRY. Second Edition, thoroughly Revised, with Additions, and fully brought up to the Present State of the Science. Containing over 100 Illustrations. Octavo. Price, in leather, ... $4.50

Professor Taft has done good service in thus embodying, in a separate volume, a comprehensive view of operative dentistry. This gentleman's position as a teacher must have rendered him familiar with the most recent views which are entertained in America on this matter, while his extensive experience and well-earned reputation in practice must have *rendered him a competent* judge of their merits. We willingly commend Professor *able and useful work to the profession.* — *London* Dental Review.

TROUSSEAU (A.),

Professor of Clinical Medicine to the Faculty of Medicine, Paris, &c.

LECTURES ON CLINICAL MEDICINE. Delivered at the Hôtel Dieu, Paris. Translated from the Third Revised and Enlarged Edition by P. VICTOR BAZIRE, M.D., London and Paris; and JOHN ROSE CORMACK, M.D., Edinburgh, F.R.S., &c. With a full Index, Table of Contents, &c. Complete in Two volumes, royal octavo, bound in cloth. Price $10.00; in leather $12.00

Trousseau's Lectures have attained a reputation both in England and this country far greater than any work of a similar character heretofore written; and, notwithstanding but few medical men could afford to purchase the expensive edition issued by the Sydenham Society, it has had an extensive sale. In order, however, to bring the work within the reach of all the profession, the publishers now issue this edition, containing all the lectures as contained in the five-volume edition, at one-half the price. The *London Lancet*, in speaking of the work, says: "It treats of diseases of daily occurrence and of the most vital interest to the practitioner. And we should think any medical library absurdly incomplete now which did not have alongside of Watson, Graves, and Tanner, the 'Clinical Medicine' of Trousseau."

The Sydenham Society's Edition of Trousseau can also be furnished in sets, or in separate volumes, as follows: Volumes I., II., and III., $5.00 each. Volumes IV. and V., $4.00 each.

TILT (EDWARD JOHN), M.D.

THE CHANGE OF LIFE IN HEALTH AND DISEASE. A Practical Treatise on the Nervous and other Affections incidental to Women at the Decline of Life. From the Third London Edition. Price $3.00

The work is rich in personal experience and observation, as well as in ready and sensible reflection on the experience and observation of others. The book is one that no practitioner should be without, as the best we have on a class of diseases that makes a constant demand upon our care, and requires very judicious management on the part of the practitioner. — *London Lancet.*

TOYNBEE (J.), F.R.S.

ON DISEASES OF THE EAR. Their Nature, Diagnosis, and Treatment. A new London Edition, with a Supplement. By JAMES HINTON, Aural Surgeon to Guy's Hospital, &c. And numerous Illustrations. Octavo. $5.00

THOMPSON (SIR HENRY), F.R.C.S., &c.

ON THE PREVENTIVE TREATMENT OF CALCULOUS DISEASE, and the Use of Solvent Remedies. Price . . $1.00

SAME AUTHOR.

CLINICAL LECTURES IN DISEASES OF THE URINARY ORGANS. Third London Edition, with additional Lectures and Illustrations. $2.50

PRACTICAL LITHOTOMY AND LITHOTRITY. Second Edition, with Illustrations. $4.00

THOROWGOOD (JOHN C.), M.D.,

Lecturer on Materia Medica at the Middlesex Hospital.

THE STUDENT'S GUIDE TO MATERIA MEDICA. With Engravings on Wood. $2.50

TYLER SMITH (W.), M.D.,

Physician, Accoucheur, and Lecturer on Midwifery, &c.

ON OBSTETRICS. A Course of Lectures. Edited by A. K. GARDNER, M.D. With Illustrations. Octavo. . . . $5.00

THOROWGOOD (J. C.), M. D.

Physician to the City of London Hospital for Diseases of the Chest, and to the West London Hospital, &c.

NOTES ON ASTHMA. Its various Forms, their Nature and Treatment, including Hay Asthma, with an Appendix of Formulæ, &c. Second Edition. Price $1.75

TOMES (JOHN), F. R. S.

Late Dental Surgeon to the Middlesex and Dental Hospitals, &c.

A SYSTEM OF DENTAL SURGERY. The Second Revised and Enlarged Edition, by CHARLES S. TOMES, M.A., Lecturer on Dental Anatomy and Physiology, and Assistant Dental Surgeon to the Dental Hospital of London. With 263 Illustrations. Price . . $5.00

This book has been for some time out of print in this country. The material progress made in the science of Dental Surgery since its first publication has rendered large additions and many revisions necessary to the New Edition: in order to bring it fully up to the time; this has been done without increasing the size of the book more than possible. Many improvements, however, will be found added to the Text, and some Sixty new illustrations are incorporated in the volume.

TOMES (C. S.), B. A.

Lecturer on Anatomy and Physiology, and Assistant Surgeon to the Dental Hospital of London.

A MANUAL OF DENTAL ANATOMY AND PHYSIOLOGY, with Numerous Illustrations. Preparing.

TROUSSEAU (A.), M. D.

Professor of Clinical Medicine to the Faculty of Medicine, Paris; Physician to the Hotel Dieu, &c., &c.

LECTURES ON CLINICAL MEDICINE. Delivered at the Hotel Dieu, Paris. Sydenham Society's Edition.

Price of Vols. 1, 2, and 3, each, ... $5.00
" " 4 and 5 " 4 00

TUKE (DANIEL H.), M. D.

Associate Author of "A Manual of Psychological Medicine," &c.

ILLUSTRATIONS OF THE INFLUENCE OF THE MIND UPON THE BODY. Octavo. Price $4.00

The author shows very clearly in this book the curative influence of the mind, as well as its effect in causing disease, and the use of the imagination and emotions as therapeutic agents. His object is also to turn to the use of legitimate medicine the means so frequently employed successfully in many systems of quackery.

TIBBITS (HERBERT), M. D.

Medical Superintendent of the National Hospital for the Paralyzed and Epileptic, &c.

A HANDBOOK OF MEDICAL ELECTRICITY. With Sixty-four large Illustrations. Small octavo. Price . . . $2.00

The author of this volume is the translator of Duchenne's great work on "Localized Electrization." Avoiding contested points in electro-physiology and therapeutics, he has prepared this handbook as containing all that is essential for the busy practitioner to know, not only when, but in EXPLICIT AND FULL DETAIL, how to use Electricity in the treatment of disease, and to make the practitioner as much at home in the use of his electrical *other medical instruments.*

VIRCHOW (RUDOLPHE),

Professor, University of Berlin.

CELLULAR PATHOLOGY. Translated from the Second Edition, with Notes and Emendations, by FRANK CHANCE, B.A., M.A., 144 Illustrations. $5.00

VAN DER KOLK (J. L. C. SCHROEDER),

THE PATHOLOGY AND THERAPEUTICS OF MENTAL DISEASES. Translated by Mr. RUDALL, F.R.C.S. Octavo. $3.00

WARING (EDWARD JOHN), F.R.C.S., F.L.S., &c., &c.

PRACTICAL THERAPEUTICS. Considered chiefly with reference to Articles of the Materia Medica. Third American from the last London Edition. Price, in cloth, $5.00; leather . . $6.00

There are many features in Dr. Waring's Therapeutics which render it especially valuable to the Practitioner and Student of Medicine, much important and reliable information being found in it not contained in similar works; also in its completeness, the convenience of its arrangement, and the greater prominence given to the medicinal application of the various articles of the Materia Medica in the treatment of morbid conditions of the Human Body, &c. It is divided into two parts, the alphabetical arrangement being adopted throughout. It contains also an excellent INDEX OF DISEASES, with a list of the medicines applicable as remedies, and a full INDEX of the medicines and preparations noticed in the work.

WYTHES (JOSEPH H), A.M., M.D., &c.

THE PHYSICIAN'S POCKET, DOSE, AND SYMPTOM BOOK. Containing the Doses and Uses of all the PrincipalArticles of the Materia Medica, and Original Preparations; A Table of Weights and Measures, Rules to Proportion the Doses of Medicines, Common Abbreviations used in Writing Prescriptions, Table of Poisons and Antidotes, Classification of the Materia Medica, Dietetic Preparations, Table of Symptomatology, Outlines of General Pathology and Therapeutics, &c. The Eleventh Revised Edition. Price, in cloth, $1.25; in leather, tucks, with pockets, ... $1.50

This manual has been received with much favor, and a large number of copies sold. It was compiled for the assistance of students, and as a vade mecum for the general practitioner, to save the trouble of reference to larger and more elaborate works. This edition has undergone a careful revision. The therapeutical arrangement of the Materia Medica has been added, together with other improvements of value to the work.

WILKS AND MOXON.

LECTURES ON PATHOLOGICAL ANATOMY. By SAMUEL WILKS, M.D., F.R.S., Physician to, and Lecturer on Medicine at, Guy's Hospital. Second Edition, Enlarged and Revised. By WALTER MOXON, M.D., F.R.S., Physician to, and late Lecturer on Pathology at, Guy's Hospital. $6.50

WILSON (ERASMUS), F.R.S.

HEALTHY SKIN. A Popular Treatise on the Skin and Hair, their *Preservation* and Management. Seventh Edition. . . $1.25

WILSON (GEORGE), M. A., M. D.

Medical Officer to the Convict Prison at Portsmouth.

A HANDBOOK OF HYGIENE AND SANITARY SCIENCE.

With Engravings. Second Edition, carefully Revised.

CONTENTS.

Chap. 1. Introductory — Public Health and Preventable Disease.
" 2. Food — Construction of Dietaries; Examination; Effects of Unwholesome Food.
" 3. Air: its Impurities; Unwholesome Trades.
" 4. Ventilation and Warming.
" 5. Examination of Air.
" 6. Water, Waterworks, Water Analysis.
" 7. Effects of Impure Water on Public Health.
" 8. Dwellings, Structural Arrangements, Dwellings of the Poor.
" 9. Hospitals; Plans of Pavilion, Cottage, and Contagious Diseases Hospitals.
Chap. 10. Removal of Sewage and Refuse Matter.
" 11. Purification and Utilization of Sewage.
" 12. Effects of Improved Sewerage and Drainage on Public Health.
" 13. Preventive Measures; Disinfection; Management of Epidemics.
" 14. Duties of Medical Officers of Health.
APPENDIX I. Excerpts from the various Public Health and Sanitary Acts.
II. List of Analytical Apparatus and Reagents, with prices.

Price $2.50

WARD (STEPHEN H.), M.D., F. R. C. P.

Physician to the Seaman's Hospital, &c., &c.

ON SOME AFFECTIONS OF THE LIVER and Intestinal Canal; with Remarks on Ague and its Sequelæ, Scurvy, Purpura, &c.

Price $3.00

"Dr. Ward's book is of a purely practical character, embodying the author's experience, from his long connection as physician to the Seaman's Hospital. His accurate description of the diseases treated will amply repay the reader."—*Dublin Medical Journal.*

WILSON (ERASMUS), F. R. C. S., &c.

CONTAINING THREE HUNDRED AND SEVENTY-ONE ILLUSTRATIONS.

THE ANATOMIST'S VADE MECUM. A Complete System of Human Anatomy. The Ninth Revised and Enlarged London Edition. Edited and fully brought to the Science of the day by Prof. GEORGE BUCHANAN, Lecturer on Anatomy in Anderson's University, Glasgow, with many New Illustrations, prepared expressly for this Edition.

Price $5.50

WEDL (CARL), M. D.

Professor of Histology, &c., in the University of Vienna.

DENTAL PATHOLOGY. The Pathology of the Teeth. With Special Reference to their Anatomy and Physiology. First American Edition, translated by W. E. BOARDMAN, M.D., with Notes by THOS. B. HITCHCOCK, M.D., Professor of Dental Pathology and Therapeutics in the Dental School of Harvard University, Cambridge. With 105 Illustrations. . . . Price, in Cloth, $4.50; Leather, $5.50

This work exhibits laborious research and medical culture of no ordinary character. It covers the entire field of Anatomy, Physiology, and Pathology of the Teeth. The author, Prof. Wedl, has thoroughly mastered the subject, using with great benefit to the book the very valuable material left by the late Dr. Heider, Professor of Dental Pathology in the University of Vienna, the result of the life-long work of this eminent man.

WOODMAN AND TIDY.

A HANDY-BOOK OF FORENSIC MEDICINE AND TOXICOLOGY. By W. BATHURST WOODMAN, M. D. St. And., Assistant Physician and Lecturer on Physiology at the London Hospital; and C. MEYMOTT TIDY, M.A., M.B., Lecturer on Chemistry, and Professor of Medical Jurisprudence and Public Health, at the London Hospital. With numerous Illustrations. Preparing.

WELLS (J. SŒLBERG),

Ophthalmic Surgeon to King's College Hospital, &c.

TREATISE ON THE DISEASES OF THE EYE. Illustrated by Ophthalmoscopic Plates and numerous Engravings on Wood. The Third London Edition. Cloth, $5.00; leather . . . $6.00

This is the author's own edition, printed in London under his supervision, and issued in this country by special arrangement with him.

SAME AUTHOR.

ON LONG, SHORT, AND WEAK SIGHT, and their Treatment by the Scientific Use of Spectacles. Third Edition Revised, with Additions and numerous Illustrations. Price $3.00

WRIGHT (HENRY G.), M.D.,

Member of the Royal College of Physicians, &c.

ON HEADACHES. Their Causes and their Cure. From the Fourth London Edition. 12mo. Cloth. $1.25

The author's plan is simple and practical. He treats of headaches in childhood and youth, in adult life and old age, giving in each their varieties and symptoms, and their causes and treatment. It is a most satisfactory monograph, as the mere fact that this is a reprint of the *fourth* edition testifies.

WALTON (HAYNES),

Surgeon in Charge of the Ophthalmic Department of, and Lecturer on Ophthalmic Medicine and Surgery in, St. Mary's Hospital.

A PRACTICAL TREATISE ON DISEASES OF THE EYE, with an Introductory Chapter on the Anatomy of the Eyeball. With nearly 300 Engravings on Wood and about 20 Chromo-Lithographs. Third Edition. Octavo. Nearly Ready.

WATERS (A. T. H.), M.D., F.R.C.P., &c.

DISEASES OF THE CHEST. Contributions to their Clinical History, Pathology, and Treatment. Second Edition, Revised and Enlarged. With numerous Illustrative Cases and Chapters on Hæmoptysis, Hay Fever, Thoracic Aneurism, and the Use of Chloral in certain Diseases of the Chest, and Plates. Octavo. Price $5.00

WALKER (ALEXANDER),

Author of "Woman," "Beauty," &c.

*INTER*MARRIAGE; or, the Mode in which, and the Causes why, *Beauty*, Health, Intellect result from certain Unions, and Deformity, *Disease*, and Insanity from others. With Illustrations. 12mo. $1.50

THE LATEST TEXT-BOOK

ON THE

PRACTICE OF MEDICINE.

Uniformly Commended by the Profession and the Press.

A HAND-BOOK OF THE THEORY AND PRACTICE OF MEDICINE. By FREDERICK T. ROBERTS, M.D., M.R.C.P., Assistant Professor and Teacher of Clinical Medicine in University College Hospital, Assistant Physician in Brompton Consumptive Hospital, &c., &c.

In One Volume, Octavo, of over 1000 pages. Price, in cloth . $5.00
" leather . $6.00

The Publishers are in receipt of numerous letters from Professors in the various Medical Schools, uniformly commending this book; whilst the following extracts from the Medical Press, both English and American, fully attest its superiority and great value not only to the student, but also to the busy practitioner.

This is a good book, yes, a very good book. It is not so full in its Pathology as "Aitken," so charming in its composition as "Watson," nor so decisive in its treatment as "Tanner;" but it is more compendious than any of them, and therefore more useful. We know of no other work in the English language, or in any other, for that matter, which competes with this one.—*Edinburgh Medical Journal.*

We have much pleasure in expressing our sense of the author's conscientious anxiety to make his work a faithful representation of modern medical beliefs and practice. In this he has succeeded in a degree that will earn the gratitude of very many students and practitioners: it is a remarkable evidence of industry, experience, and research.—*Practitioner.*

That Dr. Roberts's book is admirably fitted to supply the want of a good hand-book of medicine, so much felt by every medical student, does not admit of a question.—*Students' Journal and Hospital Gazette.*

Dr. Roberts has accomplished his task in a satisfactory manner, and has produced a work mainly intended for students that will be cordially welcomed by them; most of the observations on treatment are carefully written and worthy of attentive study; the arrangement is good, and the style clear and simple.—*London Lancet.*

It contains a vast deal of capital instruction for the student, much valuable matter in it to commend, and merit enough to insure for it a rapid sale.—*London Medical Times and Gazette.*

There are great excellencies in this book, which will make it a favorite both with the accurate student and busy practitioner. The author has had ample experience.—*Richmond and Louisville Journal.*

We confess ourselves most favorably impressed with this work. The author has performed his task most creditably, and we cordially recommend the book to our readers.—*Canada Medical and Surgical Journal.*

A careful reading of the book has led us to believe that the author has written a work more nearly up to the times than any that we have seen; to the student, it will be a gift of priceless value.—*Detroit Review of Medicine.*

Our opinion of it is one of almost unqualified praise. The style is clear, and the amount of useful and, indeed, indispensable information which it contains is marvellous. We heartily recommend it to students, teachers, and practitioners.—*Boston Med. and Surgical Journal.*

It is of a much higher order than the usual compilations and abstracts placed in the hands of students. It embraces many suggestions and hints from a carefully compiled hospital experience; the style is clear and concise, and the plan of the work very judicious.—*Medical and Surgical Reporter.*

It is unsurpassed by any work that has fallen into our hands as a compendium for students preparing for examination. It is thoroughly practical and fully up to the times.—*The Clinic.*

We find it an admirable book. Indeed, we know of no hand-book on the subject just now to be preferred to it. We particularly commend it to students about to enter upon the practice of their profession.—*St. Louis Medical and Surgical Journal.*

If there is a book in the whole of medical literature in which so much is said in so few words, it has never come within our reach. So clear, terse, and pointed is the style; so accurate the diction, and so varied the matter of this book, that it is almost a dictionary of practical medicine.—*Chicago Medical Journal.*

The author's style is clear, concise, and methodical.—*Chicago Medical Examiner.*

Dr. Roberts has given us a work of real value, and especially for the use of students is the book a good one.—*Lancet and Observer.*

TROUSSEAU'S CLINICAL MEDICINE.

COMPLETE.

In Two Large Royal Octavo Volumes.

EMBRACING ALL THE LECTURES CONTAINED IN THE FIVE VOLUME EDITION AS ISSUED BY THE SYDENHAM SOCIETY.

Price, handsomely bound in cloth $10.00
" " " leather 12.00

Lectures on Clinical Medicine.

Delivered at the Hôtel Dieu, Paris, by A. TROUSSEAU, Professor of Clinical Medicine to the Faculty of Medicine, Paris, &c., &c. Translated from the Third Revised and Enlarged Edition by P. VICTOR BAZIRE, M. D., London and Paris; and JOHN ROSE CORMACK, M. D., Edinburgh, F. R. S., &c. With a full Index, Table of Contents, &c.

Trousseau's Lectures have attained a reputation both in England and in this country far greater than any work of a similar character heretofore written, and, notwithstanding but few medical men could afford to purchase the expensive edition issued by the Sydenham Society, it has had an extensive sale. In order, however, to bring the work within the reach of all the profession, the publishers now issue this edition, containing all the lectures as contained in the five-volume edition, at one-half the price. Below are a few only of the many favorable opinions expressed of the work:

"It treats of diseases of daily occurrence and of the most vital interest to the practitioner. And we should think any medical library absurdly incomplete now which did not have alongside of Watson, Graves, and Tanner, the 'Clinical Medicine' of Trousseau.

"The work is full of the results of the richest natural observation, and is the production of one who was enlightened enough to combine with new methods of investigation the vigorous and independent ideas of the old physicians whom he so eloquently magnifies. It is an extremely rich and valuable addition to the library of physicians and practitioners generally." — *London Lancet.*

"This book furnishes an example of the best kind of clinical teaching. It deserves to be popularized. We scarcely know of any work better fitted for presentation to a young man when entering upon the practical work of his life. The delineation of the recorded cases is graphic, and their narration devoid of that prolixity which, desirable as it is for purposes of extended analysis, is highly undesirable when the object is to point to a practical lesson."— *London Medical Times and Gazette.*

"The publication of Trousseau's Lectures furnishes medical men with one of the best practical treatises on disease as seen at the bedside. The conversational style adopted by the author lends animation to the work, and the translator deserves credit for having so well preserved the easy and ready style of the original." — *British and Foreign Medico-Chirurgical Review.*

"The great reputation of Prof. Trousseau as a practitioner and teacher of Medicine in all its branches, renders the present appearance of his Clinical Lectures particularly welcome." — *Medical Press and Circular.*

"*A clever translation of* Prof. Trousseau's admirable and exhaustive work, the best book *of reference upon the* Practice of Medicine." — *Indian* Medical Gazette.

LANE MEDICAL LIBRARY

To avoid fine, this book should be returned on or before the date last stamped below.

JUN 5 1961


N286 Tilt, E.J.
T58 Change of life...
1871 1706
NAME
DATE DUE
Miriam DeCamp
JUN 5 1961